



Beachwalk 2600 Hallandale Beach Blvd.

Traffic Impact Report


Prepared by:



Prepared For:

PRH-2600 HALLANDALE BEACH LLC

August 2011



PROFESSIONAL ENGINEER CERTIFICATE

I hereby certify that I am a registered professional engineer in the State of Florida practicing with Calvin, Giordano & Associates, a corporation authorized to operate as an engineering business, EB 00006500, by the State of Florida Department of Professional Regulation, Board of Professional Engineers, and that I have prepared or approved the evaluation, findings, opinions, conclusions, or technical advice hereby for:

PROJECT: Beachwalk – 2600 Hallandale Beach Boulevard

LOCATION: Hallandale Beach, Florida

CLIENT: PRH-2600 Hallandale Beach LLC

I acknowledge that the procedures and references used to develop the results contained in these computations are standard to the professional practice of transportation engineering as applied through professional judgment and experience.

NAME: James E. Spinks III, PE, PTOE

P.E. NO.: 66775

DATE: August 5, 2011

SIGNATURE: 



TABLE OF CONTENTS

EXECUTIVE SUMMARY	i
1. INTRODUCTION.....	1
1.1 Project Description	1
1.2 Project Location	1
1.3 Traffic Impact Study Area	1
2. DATA COLLECTION	3
2.1 Existing Transport Characteristics	3
2.2 Traffic Count Data.....	3
2.3 Additional Traffic Data Collection	4
2.4 Roadway Description.....	4
2.5 Intersection Description.....	5
3. EXISTING CONDITIONS ANALYSIS	6
3.1 Roadway Segment Level of Service Summary	7
3.2 Intersection Level of Service Summary.....	7
4. FUTURE TRAFFIC PROJECTIONS.....	13
4.1 Planned and Programmed Roadway Improvements	13
4.2 Background Traffic.....	13
4.3 Committed Developments	14
4.4 Project Traffic	20
4.4.1 Trip Generation	20
4.4.2 Trip Distribution	23
4.4.3 Trip Assignment	23
5. FUTURE TRAFFIC ANALYSIS	28
5.1 Roadway Segment Level of Service Summary	31
5.2 Intersection Level of Service Summary.....	31
6. CONCLUSION AND RECOMMENDATIONS	41



List of Appendices

Appendix A:	Transit Route Information
Appendix B:	Traffic Data
Appendix C:	Growth Rate Analysis/Historical Traffic Data
Appendix D:	Broward County Signal Timing Data
Appendix E:	Synchro Output Sheets – Existing
Appendix F:	Committed Development Data – Wal-Mart Expansion Study – August 2010
Appendix G:	Trip Generation Analysis Data
Appendix H:	Synchro Output Sheets – Future (2015)

List of Tables

Table 3-1 – Existing Conditions Segment Analysis – AM and PM Peak Hour	12
Table 4-1 – Committed Developments	14
Table 4-1 – Trip Generation	22
Table 5-1a – Future Peak Hour Vehicular Traffic Analysis (2015) – AM Peak Hour	29
Table 5-1b – Future Peak Hour Vehicular Traffic Analysis (2015) – PM Peak Hour	30

List of Figures

Figure 1-1 – Project Location Map	2
Figure 3-1a – 2011 Existing AM Peak Hour Vehicle Trip Summary (1 of 2)	8
Figure 3-1a – 2011 Existing AM Peak Hour Vehicle Trip Summary (2 of 2)	9
Figure 3-1b – 2011 Existing PM Peak Hour Vehicle Trip Summary (1 of 2)	10
Figure 3-1b – 2011 Existing PM Peak Hour Vehicle Trip Summary (2 of 2)	11
Figure 4-1a – 2015 Total Background Vehicular Trips – AM Peak Hour (1 of 2)	16
Figure 4-1a – 2015 Total Background Vehicular Trips – AM Peak Hour (2 of 2)	17
Figure 4-1b – 2015 Total Background Vehicular Trips – PM Peak Hour (1 of 2)	18
Figure 4-1b – 2015 Total Background Vehicular Trips – PM Peak Hour (2 of 2)	19
Figure 4-3a – Project Trip Distribution and Assignment – AM Peak Hour (1 of 2)	24
Figure 4-3a – Project Trip Distribution and Assignment – AM Peak Hour (2 of 2)	25
Figure 4-3b – Project Trip Distribution and Assignment – PM Peak Hour (1 of 2)	26
Figure 4-3b – Project Trip Distribution and Assignment – PM Peak Hour (2 of 2)	27
Figure 5-1a – Future Total Traffic – AM Peak Hour (1 of 2)	33
Figure 5-1a – Future Total Traffic – AM Peak Hour (2 of 2)	34
Figure 5-1b – Future Total Traffic – PM Peak Hour (1 of 2)	35
Figure 5-1b – Future Total Traffic – PM Peak Hour (2 of 2)	36
Figure 5-1c – Optimized Future Total Traffic – AM Peak Hour (1 of 2)	37
Figure 5-1c – Optimized Future Total Traffic – AM Peak Hour (2 of 2)	38
Figure 5-1d – Optimized Future Total Traffic – PM Peak Hour (1 of 2)	39
Figure 5-1d – Optimized Future Total Traffic – PM Peak Hour (2 of 2)	40



EXECUTIVE SUMMARY

CGA was commissioned by PRH-2600 Hallandale Beach LLC to provide a Traffic Impact Study for the development of "Beachwalk", located at 2600 Hallandale Beach Boulevard (State Road 858) within the City of Hallandale Beach. The proposed development is a multi-story building that will consist of hotel and residential units. The project will be developed in one (1) distinct phase, with opening year anticipated to occur in year 2015, as follows:

1. Hotel: 216 Two (2) bedroom suites and 216 standard rooms as well as a 1,225 square foot accessory hotel restaurant
2. High-Rise Condominium: 84 dwelling units

An assessment of the proposed development traffic for both the AM and PM peak period during typical weekday conditions was performed. The existing roadway segment analysis shows that all of the roadway segments within the study area currently operate at or above level of service (LOS) "D" during the AM and PM peak period, with the exception of Hallandale Beach Boulevard from NE 10th Avenue to NE 14th Avenue which operates below LOS "D" during the PM peak period. The existing intersection analysis shows that all intersections within the study area currently operate at or above LOS "D" during the AM peak hour, with the exception of E. Hallandale Beach Boulevard at US 1. During the PM peak hour, the existing intersection analysis shows that all intersections currently operate at or above LOS "D", with the exception of Hallandale Beach Boulevard at NE 14th Avenue and Hallandale Beach Boulevard at US 1.

Committed development information was obtained from the *Wal-mart Expansion Traffic Impact Study, August 2010*, provided by City staff, which included data from several of the most up-to-date committed development studies for the city. The studies provided trip generation for the PM peak period, however, no available AM peak period committed development data was available. Therefore, since the developments listed in Table 4-1 would likely yield a higher number of project trips in the PM peak hour, to be conservative, the reciprocal movements of the PM peak hour committed trips were calculated and utilized for the AM peak hour committed development trips.

The future traffic growth rate was developed using a trend analysis based on historical traffic data from the FDOT Traffic DVD database. Historical trend analyses for traffic count stations within the study area indicate that the average annual growth rate is approximately 0.5 percent (%). This conservative annual growth rate was utilized to calculate expected background traffic growth from the existing 2011 traffic volumes for the traffic impact area.

An analysis of Year 2015 traffic shows that each of the studied intersections operates at or above LOS "D" with or without project-generated traffic, with the exception of the following intersections which operate below LOS "D" with or without project-generated traffic:

1. Hallandale Beach Boulevard at Ocean Drive (AM and PM Peak)
2. Hallandale Beach Boulevard at NE 14th Avenue (AM and PM Peak)
3. Hallandale Beach Boulevard at US 1 (AM and PM Peak)
4. Hallandale Beach Boulevard at Golden Isles Drive (PM Peak Only). However, signal timing improvements proposed in this report will allow the intersection to operate at or above LOS "D" with project-generated traffic included.



In addition, all studied arterial links operate at or above LOS "D" with or without project-generated traffic, with the exception of the following arterial links which operate below LOS "D" with or without project-generated traffic:

1. Hallandale Beach Boulevard from US 1 to NE 10th Avenue (AM Peak)
2. Hallandale Beach Boulevard from US 1 to Layne Boulevard (PM Peak)

An analysis of the future 2015 conditions with project traffic showed that each of the failing roadway segments within the study area will operate below acceptable levels of service regardless of the addition of project traffic. The intersection level of service analysis for future conditions including project traffic showed that each of the intersections performed at the same level of service as the future conditions without project traffic during both the AM and PM peak hour.

For the intersection of Hallandale Beach Boulevard at Golden Isles Drive, optimization of the intersection signal timing resulted in the intersection operating at or above LOS "D" during both the AM and PM peak periods with the addition of project-generated traffic.

In conclusion, the results of this study demonstrate that the traffic generated by the proposed "Beachwalk" development project can be accommodated on the existing roadway network and levels of service expected without the project can be maintained upon the addition of project-generated traffic.



1. Introduction

The purpose of this report is to document the results of the Traffic Impact Study for the development of "Beachwalk", located at 2600 Hallandale Beach Boulevard (State Road 858) within the City of Hallandale Beach. There are currently no existing land uses at the proposed site.

The following sections summarize the results of the traffic study, and provide a list of options to be considered to mitigate any potential impacts of the project.

1.1 Project Description

PRH-2600 Hallandale Beach LLC is proposing the development of "Beachwalk", located at 2600 Hallandale Beach Boulevard (State Road 858) within the City of Hallandale Beach. This development is a multi-story building that will consist of a mix of hotel and residential units. The project will be developed in one (1) distinct phase, with opening year anticipated to occur in year 2015, as follows:

1. Hotel: 216 Two (2) bedroom suites and 216 standard rooms with an accessory hotel restaurant: 1,225 square feet
2. High-Rise Condominium: 84 dwelling units

1.2 Project Location

The project site is located just east of NE 26th Avenue, along the south side of Hallandale Beach Boulevard. **Figure 1-1** depicts the general location of the Beachwalk development site and the study area.

1.3 Traffic Impact Study Area

The proposed study impact area for this project includes the region bounded by a one mile radius circle extending out from the proposed project site. More specifically, the study impact area is bounded by US 1 to the west and S. Ocean Drive (A1A to the east), along Hallandale Beach Boulevard.

Since the proposed site is easily accessed via the regional roadway system, the area of influence, where most of the traffic entering and exiting the project will be concentrated, is limited to adjacent roadways and intersections in close proximity to the site.



Figure 1-1 – Project Location Map



2. Data Collection

2.1 Existing Transport Characteristics

The proposed site is surrounded by the following state and/or local roadways: Hallandale Beach Boulevard to the immediate north, SE 26th Ave to the east, Diana Drive to the immediate south, and Golden Isles Drive to the west.

Transit service to the project study area is provided by Broward County Transit lines 1, 4, 5, 28, and the US 1 Breeze.

Transit route maps and service schedules are shown in Appendix A.

2.2 Traffic Count Data

Turning movement counts (TMC's) were collected during the AM and PM peak period on a typical weekday within the determined traffic study area. A seasonal factor obtained from the 2009 FDOT Florida Traffic Information DVD of 1.2 was used to adjust the raw turning movement counts to peak season turning movement counts. Locations for typical weekday turning movement counts are included in Appendix B, and listed below:

1. Hallandale Beach Boulevard at US 1
2. Hallandale Beach Boulevard at NE 8th Avenue
3. Hallandale Beach Boulevard at NE 10th Avenue
4. Hallandale Beach Boulevard at NE 14th Avenue
5. Hallandale Beach Boulevard at 3 Islands Boulevard
6. Hallandale Beach Boulevard at Golden Isles Drive
7. Hallandale Beach Boulevard at Layne Boulevard
8. Hallandale Beach Boulevard at SE 26th Avenue
9. Hallandale Beach Boulevard at Diplomat Parkway
10. Hallandale Beach Boulevard at South Ocean Drive
11. South Ocean Drive NB Ramp to Hallandale Beach Boulevard WB

In addition to the traffic data counts, existing characteristics of the roadway network including intersection geometry, lane geometry and posted speed limits within the traffic study area were verified.

A conservative growth rate factor of 0.5% was applied to all of the existing traffic data counts to forecast future background conditions. Growth rate data is included in Appendix C.



2.3 Additional Traffic Data Collection

2.3.1 Signal Timing Analysis – Existing signal timing and phasing was obtained from Broward County Traffic Engineering, and is included in Appendix D.

2.3.2 Weekly Adjustment Factors - These factors were used to adjust raw counts to reflect average annual traffic for typical weekday conditions. These factors were obtained from the 2009 FDOT Florida Traffic Information DVD.

2.3.3 Peak Hour Factors – A peak hour factor of 0.95 was used for hourly variation of the traffic flow in the peak period, as prescribed by the Florida Department of Transportation (FDOT) within the Quality/Level of Service Handbook.

2.4 Roadway Description

The following sections describe the physical characteristics of the roadways within the traffic impact area.

Hallandale Beach Boulevard – Six-lane divided state road, running in an east-west direction, serving as the northern border of the proposed site. The posted speed limit along Hallandale Beach Boulevard in the vicinity of the project is 35 mph.

US 1 – Four-lane divided US highway north of Hallandale Beach running in a north-south direction, west of the proposed site. Six-lane divided US highway south of Hallandale Beach Boulevard. The posted speed limit along US 1 in the vicinity of the project is 35 mph north of Hallandale Beach Boulevard and 45 mph to the south.

NE 8th Avenue – Two-lane undivided local road, running in a north-south direction, west of the proposed site. The posted speed limit along NE 8th Avenue in the vicinity of the project is 25 mph.

NE 10th Avenue – Two-lane undivided local road, running in a north-south direction, west of the proposed site. The posted speed limit along NE 10th Avenue in the vicinity of the project is 25 mph.



NE 14th Avenue – Two-lane undivided local road, running in a north-south direction, west of the proposed site. The posted speed limit along NE 14th Avenue in the vicinity of the project is 25 mph.

Layne Boulevard – Four-lane divided local road, running in a north-south direction, west of the proposed site. The posted speed limit along Layne Boulevard in the vicinity of the project is 30 mph.

Golden Isles Drive – Two-lane undivided local road, south of the proposed site. The posted speed limit along Golden Isles Drive in the vicinity of the project is 25 mph.

Diana Drive – Two-lane undivided local road, running in an east-west direction, south of the proposed site. The posted speed limit along Diana Drive in the vicinity of the project is 30 mph.

Diplomat Parkway – Two-lane undivided local road, running in a north-south direction, west of the proposed site. The posted speed limit along Diplomat Parkway in the vicinity of the project is 25 mph.

3 Islands Boulevard – Six-lane divided local road, running in a north-south direction, west of the proposed site. The posted speed limit along 3 Islands Boulevard in the vicinity of the project is 35 mph.

South Ocean Drive – Six-lane divided state road, running in a north-south direction, east of the proposed site. The posted speed limit along South Ocean Drive in the vicinity of the project is 35 mph.

2.5 Intersection Descriptions

There are 9 signalized intersections and 3 stop-controlled intersections located within the project study area, as follows:

2.5.1 Signalized Intersections

1. Hallandale Beach Boulevard at US 1
2. Hallandale Beach Boulevard at NE 8th Avenue
3. Hallandale Beach Boulevard at NE 10th Avenue
4. Hallandale Beach Boulevard at NE 14th Avenue
5. Hallandale Beach Boulevard at Layne Boulevard
6. Hallandale Beach Boulevard at Golden Isles Drive



7. Hallandale Beach Boulevard at Diplomat Parkway
8. Hallandale Beach Boulevard at 3 Islands Boulevard
9. Hallandale Beach Boulevard at South Ocean Drive

2.5.2 Stop-Controlled Intersections

1. Hallandale Beach Boulevard at SE 26th Avenue
2. Diana Drive at SE 26th Avenue
3. Diana Drive at Golden Isles Drive

3. Existing Conditions Analysis

Analysis of existing traffic conditions was performed for the AM and PM peak hour conditions on the roadway segments within the study area. The Florida Department of Transportation (FDOT) Generalized Level of Service (LOS) Tables were used to identify the vehicular capacity on the roadway segments. Intersection levels of service were determined for the AM and PM peak period conditions using Synchro (version 7.0) based on the procedures of the Highway Capacity Manual (HCM) at all intersections within the study area, with the exception of E. Hallandale Beach Boulevard at SE 26th Avenue, which was analyzed based on the procedures of the Intersection Capacity Utilization (ICU). The levels of service thresholds used for the analysis are based on the "Generalized" tables for Urbanized Areas within the FDOT Level of Service Handbook for the Broward County adopted threshold, which is Level of Service "D".

Level of Service (LOS) is a quality measure describing operational conditions within a traffic stream, generally in terms of such service measures as speed and travel time, freedom to maneuver, traffic interruptions, and comfort and convenience.

Six (6) LOS are defined for each type of facility that have HCM analysis procedures available. Letters designate each level, from A to F, with LOS A representing the best operating conditions and LOS F the worst. Each level of service represents a range of operating conditions and the driver's perception of those conditions. Safety is not included in the measures that establish service levels. Eight (8) LOS are defined for each intersection analyzed using ICU procedures. Letters designate each level, ranging from A to H. Similar to the HCM method, LOS A signifies that an intersection has no congestion and LOS H represents an intersection that is over capacity.



3.1 Roadway Segment Level of Service Summary

The AM and PM peak hour weekday link volumes within the study area were estimated using the adjusted AM and PM peak hour turning movement counts. The resulting link and intersection data are summarized on Figure 3-1.

The link maximum service volumes used in this study are derived from the 2009 FDOT Quality/Level of Service Handbook. Table 3-1 includes facility type, number of travel lanes, existing AM and PM peak hour volumes, AM and PM peak hour maximum service volumes, the adopted level of service standard and AM and PM peak hour level of service.

The analysis shows that all of the roadway segments within the study area currently operate at acceptable levels of service during the AM and PM peak period, with the exception of Hallandale Beach Boulevard from NE 10th Avenue to NE 14th Avenue during the PM peak period.

3.2 Intersection Level of Service Summary


The collected turning movement counts were converted to average turning movement volumes by applying a peak season conversion factor (PSCF). The peak season conversion factors were obtained from the 2009 Florida Traffic Information & Highway DVD. These volumes are also summarized on Figure 3-1.

The analysis shows that all intersections within the study area currently operate at acceptable levels of service¹ during the AM peak hour, with the exception of Hallandale Beach Boulevard at US 1. During the PM peak hour, all intersections currently operate at acceptable levels of service, with the exception of Hallandale Beach Boulevard at NE 14th Avenue and Hallandale Beach Boulevard at US 1. The existing intersection levels of service analysis worksheets are summarized on Figure 3-1a, Figure 3-1b and included in Appendix E.


¹ LOS D or better represents the adopted level of service by Broward County.




Beachwalk Development - 2011 Existing AM (1 of 2)



Beachwalk Development - 2011 Existing AM (2 of 2)



Beachwalk Development - Existing PM Peak (1 of 2)



Beachwalk Development - Existing PM Peak (2 of 2)




Table 3-1 – Existing Conditions Segment Analysis – AM and PM Peak Hour

Peak Hour Volume Level Of Service Analysis						
LOCATION	ROADWAY TYPE	PH LOS "D" Volume*	AM Peak Hour		PM Peak Hour	
			Existing Peak Hour (PH) Volume**	Existing Peak Hour LOS	Existing Peak Hour (PH) Volume**	Existing Peak Hour LOS
Hallandale Beach Blvd - From U.S. 1 to NE 8th Ave	6LD	4,240	3,773	D or better	4,192	D or better
Hallandale Beach Blvd - From NE 8th Ave to NE 10th Ave	6LD	4,240	3,623	D or better	4,021	D or better
Hallandale Beach Blvd - From NE 10th Ave to NE 14th Ave	6LD	4,240	3,410	D or better	4,505	F
Hallandale Beach Blvd - From NE 14th Ave to Layne Blvd	6LD	4,240	2,971	D or better	3,486	D or better
Hallandale Beach Blvd - From Layne Blvd to Golden Isles Dr	6LD	4,240	2,611	D or better	3,221	D or better
Hallandale Beach Blvd - From Golden Isles Dr to Diplomat Pkwy	6LD	4,240	2,486	D or better	3,236	D or better
Hallandale Beach Blvd - From Diplomat Pkwy to 3 Islands Blvd	6LD	4,240	2,358	D or better	3,266	D or better
Hallandale Beach Blvd - From 3 Islands Blvd to SE 26th Ave	6LD	4,240	2,028	D or better	2,995	D or better
Hallandale Beach Blvd - From SE 26th Ave to Ocean Dr	6LD	4,240	2,251	D or better	3,080	D or better
SE 26 Avenue - From Hallandale Beach Blvd to Diana Drive	2LU	1,040	119	D or better	113	D or better
Diana Drive - From SE 26 Avenue to Golden Isles Drive	2LU	1,040	172	D or better	246	D or better
Golden Isles Drive - From Diana Drive to Hallandale Beach Blvd	2LU	1,040	275	D or better	346	D or better

* - From FDOT Generalized LOS Tables

** - 2011 Collected Data



4. Future Traffic Projections

Analysis of future traffic projections within the study area was performed for two scenarios: a) background traffic plus committed development traffic and b) total traffic which includes background traffic, committed development traffic, plus project traffic. The purpose of the analysis is to isolate the impacts of the traffic associated with the project from traffic due to population growth and construction of new developments.

The following sections describe the process used to determine future roadway improvements planned by the City, County, and state agencies; the methodology used to estimate background traffic; traffic from committed developments; and trips associated with the proposed site.

4.1 Planned and Programmed Roadway Improvements

Programmed (funded and/or committed) transportation improvements within the traffic impact study area were collected using Florida Department of Transportation (FDOT) five year work program, Broward County's Metropolitan Planning Organization (MPO) Transportation Improvement Program (TIP) and the 2035 Long Range Transportation Plan (LRTP). There were no capacity improvement projects funded for construction prior to or on the proposed project site opening year, planned for 2015. Therefore, the existing roadway geometry within the study area was used as the future roadway network in the future analysis.

4.2 Background Traffic

Background traffic was calculated to account for committed traffic and growth in the area. Future background traffic for this study was developed by applying a yearly growth rate to the seasonally adjusted 2011 traffic counts to estimate the background traffic for the year 2015, which is the project's anticipated build out year.

The growth rate utilized was 0.5 percent (%) to represent the expected traffic growth within the entire traffic impact area. This growth rate was then applied to the 2011 traffic counts to estimate the 2015 future background traffic volumes within the traffic impact area.



4.3 Committed Developments

Committed development information was obtained from The City of Hallandale staff from the *Wal-mart Expansion Traffic Impact Study, August 2010*, which included data from several of the most up-to-date committed development studies for the city. Table 4-1 lists the committed development information provided within this study, including their project trips. Committed development data is included in Appendix F.

Table 4-1 – Committed Developments

Committed Development	
Development	Year
Ocean Marine	2003
Village of Gulfstream	Ongoing
European Club	2005
Millenium Hallandale	2005
Regency SPA	2002
Oasis	2006
Park Central	2006
Hallandale Square	2008
Domus Hallandale	n/a
Walmart Expansion	Ongoing

N/A – Not available from City staff

The studies provided trip generation for the PM peak period. However, no available AM peak period committed development data was available. Therefore, since the developments listed in Table 4-1 would likely yield a higher number of project trips in the PM peak hour, to be conservative, the reciprocal movements of the AM peak hour committed trips were calculated for the PM peak hour committed development trips. The number of trips from each development was added to the 2015 background traffic based on the trip assignment included in the traffic report to develop the total background traffic.

An analysis of existing traffic, plus background, plus committed traffic, shows that each of the intersections operates at acceptable levels of service, with the exception of the following:

1. Hallandale Beach Boulevard at Ocean Drive (AM and PM Peak)
2. Hallandale Beach Boulevard at NE 14th Avenue (AM and PM Peak)
3. Hallandale Beach Boulevard at US 1 (AM and PM Peak)
4. Hallandale Beach Boulevard at Golden Isles Drive (PM Peak Only)




In addition, all the arterial links operate at acceptable levels of service, with the exception of the following:

1. Hallandale Beach Boulevard from US 1 to NE 10th Avenue (AM Peak)
2. Hallandale Beach Boulevard from US 1 to Layne Boulevard (PM Peak)

Figure 4-1 summarizes the total background development traffic within the study area.



Beachwalk Development - Total Background AM (1 of 2)



Beachwalk Development

AM Background Plus Committed Traffic
Figure 4-1a

LEGEND

A

PM Peak Link Level of Service

E

Level of Service

0

Project Trip Turning Movement Volume

10%

Project Trip Turning Movement Percentage

250

Total Approach Volume

250


Total Exit Volume

PSCF


EAST-A1A TO US1

1.20


Beachwalk Development - Total Background AM (2 of 2)



Beachwalk Development - Total Background PM (1 of 2)



Beachwalk Development - Total Background PM (2 of 2)



4.4 Project Traffic

Project traffic was developed using trip generation rates from The Trip Generation Manual, 7th Edition, by the Institute of Transportation Engineers (ITE).

4.4.1 Trip Generation

Trip generation is the method by which the amount of traffic, or the number of trips to and from a site, is estimated. The Trip Generation Manual, 7th Edition, by the Institute of Transportation Engineers (ITE), is a common source of trip generation characteristics, providing data on a variety of development types on daily and peak-hour basis.

Based upon the ITE land use codes, the proposed project's trip generation was determined, as follows:

- ITE Land Use Code 311 (All Suites Hotel)
- ITE Land Use Code 310 (Hotel)
- ITE Land Use Code 232 (High-Rise Condominium)

ITE land uses for Hotel as well as All Suites Hotel were applied to the 216 units due to the fact that each unit will have the capability of functioning as two distinct hotel units, one with a kitchen and one without a kitchen.

Internal Capture Volumes

Internal capture trips are trips that occur between various land uses within the development without needing to access the external roadway network. Internal capture is not expected for the project.

Pass-By Capture Volumes

A portion of the trips at the project driveways will be the result of the project's new trips. Pass-by trips are stops on the way from an origin to a primary trip destination without a route diversion and that are existing trips on the roadway network. The pass-by percentage for the various land uses were determined using the rates provided in the *ITE Trip Generation Handbook*.



Net New Project Trips

Net new, external vehicle trips are equal to the gross project trips minus the internal capture trips and the pass-by capture trips. As identified in the 2035 Broward County Long Range Transportation Plan (LRTP), Hallandale Beach Boulevard and SR A1A (Ocean Drive) have been identified as routes for premium rapid bus transit services within the limits of this project study area with a mobility hub planned for implementation in FY 2014-2015 at Hallandale Beach Boulevard and US 1. A community hub is also planned for inclusion at Hallandale Beach Boulevard and A1A, as well as Hallandale Beach Boulevard and NE 14th Avenue.

Table 4-2 shows the project trip generation for the AM, PM and daily periods for the project site.



Table 4-2 – Trip Generation

Trip Generation - AM Peak Hour																	
Land Uses	ITE Land Use Code	Description	Unit	Total Units	Rate/Unit	Trips	Driveway Volumes		Passerby Rate		Total Trips	Directional Distribution					
							Entering	Exiting	%	Trips		Entering		Exiting			
EXISTING																	
Lodging	311	All Suites Hotel	Rooms	216	0.38	82	55.0%	45	45.0%	37	0%	0	82	55.0%	45	45.0%	37
Lodging	310	Hotel	Rooms	216	0.56	121	58.0%	70	42.0%	51	0%	0	121	55.0%	67	45.0%	54
Lodging	232	High-Rise Condominium	Dwelling Units	84	0.34	29	19.0%	5	81.0%	23	0%	0	29	19.0%	5	81.0%	23
Total													Entering	117	Exiting	115	

Trip Generation - PM Peak Hour																	
Land Uses	ITE Land Use Code	Description	Unit	Total Units	Rate/Unit	Trips	Driveway Volumes				Passerby Rate		Total Trips	Directional Distribution			
							Entering		Exiting		%	Trips		Entering		Exiting	
EXISTING																	
Lodging	311	All Suites Hotel	Rooms	216	0.4	86	45.0%	39	55.0%	48	0%	0	86	45.0%	39	55.0%	48
Lodging	310	Hotel	Rooms	216	0.59	127	49.0%	62	51.0%	65	0%	0	127	45.0%	57	55.0%	70
Lodging	232	High-Rise Condominium	Dwelling Units	84	0.38	32	62.0%	20	38.0%	12	0%	0	32	62.0%	20	38.0%	12
Total														Entering	116	Exiting	130

Trip Generation - Daily																	
Land Uses	ITE Land Use Code	Description	Unit	Total Units	Rate/Unit	Trips	Driveway Volumes			Passerby Rate		Total Trips	Directional Distribution				
							Entering	Exiting		%	Trips		Entering		Exiting		
EXISTING																	
Lodging	311	All Suites Hotel	Rooms	216	4.9	1058	50.0%	529	50.0%	529	0%	0	1058	50.0%	529	50.0%	529
Lodging	310	Hotel	Rooms	216	8.17	1765	50.0%	882	50.0%	882	0%	0	1765	50.0%	882	50.0%	882
Lodging	232	High-Rise Condominium	Dwelling Units	84	4.18	351	50.0%	176	50.0%	176	0%	0	351	50.0%	176	50.0%	176
Total													Entering	1587	Exiting	1587	



4.4.2 Trip Distribution

The trip distribution of the project's traffic was estimated based on an analysis of the surrounding roadway network characteristics, review of current entering and exiting traffic volume ratios for the project study area and existing land use patterns. This was primarily done due to the small-scale nature of this project. A FSUTMS model run would not provide the same level of detail as the analysis of current trend analysis. This trip distribution method used the existing turning movement counts to calculate the AM and PM peak hour link volumes entering and exiting the project impact area. Using the total volumes in the traffic impact area, distribution ratios were calculated entering and exiting each link. These ratios were then applied to the AM and PM peak trips.



4.4.3 Trip Assignment

Based upon the trip distribution described in the previous section, the total weekday AM and PM peak project trips were assigned to the roadway network. Figure 4-3 shows the trip distribution and assignment on the roadway network.


Trip generation analysis data is included in Appendix G.




Beachwalk Development - Trip Distribution AM (1 of 2)



Beachwalk Development - Trip Distribution AM (2 of 2)



Beachwalk Development - Trip Distribution PM (1 of 2)



Beachwalk Development

PM Project Trip Distribution and Assignment
Figure 4-3b

LEGEND

A

PM Peak Link Level of Service

E

Level of Service

0

Project Trip Turning Movement Volume

10%

Project Trip Turning Movement Percentage

250

Total Approach Volume

250


Total Exit Volume

PGCF

EAST-A1A TO US1

1.20

Beachwalk Development - Trip Distribution PM (2 of 2)



5. Future Traffic Analysis

Analysis of future conditions was performed for weekday AM and PM peak hour conditions on the roadway segments within the study area based on the Florida Department of Transportation Generalized Level of Service (LOS) Tables.

Intersection levels of service were determined for the AM and PM peak period conditions using Synchro (version 7.0) based on the procedures of the 2000 Highway Capacity Manual and Intersection Capacity Utilization. Intersection signal timing green splits were optimized for all future traffic analysis with the cycle lengths held consistent with existing conditions, as shown on the Synchro output sheets in Appendix H.

The levels of service thresholds used for the analysis are based on the “Generalized” tables for Urbanized Areas within the FDOT Level of Service Handbook adopted for Broward County which is LOS D. Level of service thresholds are discussed in more detail in Section 3.2 of this document.

Table 5-1 summarizes the arterial analysis of existing, background plus committed, and project traffic vehicular volumes.



Table 5-1a – Future Peak Hour Vehicular Traffic Analysis (2015) – AM Peak Hour

Peak Hour Volume Level Of Service Analysis (AM)												
LOCATION	ROADWAY TYPE	Existing Peak Hour (PH) Volume**	PH LOS "D" Volume*	Existing Peak Hour LOS	Future Roadway Type (2015)			Future without project trips		Future with project trips		
					Programmed Improvements	Future Roadway Type	Future PH LOS "D" Volume*	Future PH Volume***	Future Peak Hour LOS	Project Trips***	Future PH Volume***	Future PH LOS
Hallandale Beach Blvd - From U.S. 1 to NE 8th Ave	6LD	3,773	4,240	D or better	NO	6LD	4,240	4,747	F	132	4,879	F
Hallandale Beach Blvd - From NE 8th Ave to NE 10th Ave	6LD	3,623	4,240	D or better	NO	6LD	4,240	4,321	F	137	4,458	F
Hallandale Beach Blvd - From NE 10th Ave to NE 14th Ave	6LD	3,410	4,240	D or better	NO	6LD	4,240	4,081	D or better	142	4,222	D or better
Hallandale Beach Blvd - From NE 14th Ave to Layne Blvd	6LD	2,971	4,240	D or better	NO	6LD	4,240	3,680	D or better	158	3,839	D or better
Hallandale Beach Blvd - From Layne Blvd to Golden Isles Dr	6LD	2,611	4,240	D or better	NO	6LD	4,240	3,268	D or better	164	3,453	D or better
Hallandale Beach Blvd - From Golden Isles Dr to Diplomat Pkwy	6LD	2,486	4,240	D or better	NO	6LD	4,240	3,024	D or better	87	3,240	D or better
Hallandale Beach Blvd - From Diplomat Pkwy to 3 Islands Blvd	6LD	2,358	4,240	D or better	NO	6LD	4,240	2,899	D or better	87	2,986	D or better
Hallandale Beach Blvd - From 3 Islands Blvd to SE 26th Ave	6LD	2,028	4,240	D or better	NO	6LD	4,240	2,738	D or better	93	2,830	D or better
Hallandale Beach Blvd - From SE 26th Ave to Ocean Dr	6LD	2,251	4,240	D or better	NO	6LD	4,240	2,964	D or better	48	3,012	D or better
SE 26 Avenue - From Hallandale Beach Blvd to Diana Drive	2LU	119	1,040	D or better	NO	2LU	1,040	121	D or better	141	212	D or better
Diana Drive - From SE 26 Avenue to Golden Isles Drive	2LU	172	1,040	D or better	NO	2LU	1,040	200	D or better	91	291	D or better
Golden Isles Drive - From Diana Drive to Hallandale Beach Blvd	2LU	275	1,040	D or better	NO	2LU	1,040	393	D or better	92	485	D or better

* - From FDOT Generalized LOS Tables

** - 2011 Collected Data

*** - Calculated from 2011 data

Table 5-2b – Future Peak Hour Vehicular Traffic Analysis (2015) – PM Peak Hour

Peak Hour Volume Level Of Service Analysis (PM)												
LOCATION	ROADWAY TYPE	Existing Peak Hour (PH) Volume**	PH LOS "D" Volume*	Existing Peak Hour LOS	Future Roadway Type (2015)			Future without project trips		Future with project trips		
					Programmed Improvements	Future Roadway Type	Future PH LOS "D" Volume*	Future PH Volume***	Future Peak Hour LOS	Project Trips***	Future PH Volume***	Future PH LOS
Hallandale Beach Blvd - From U.S. 1 to NE 8th Ave	6LD	4,150	4,240	D or better	NO	6LD	4,240	5,185	F	132	5,317	F
Hallandale Beach Blvd - From NE 8th Ave to NE 10th Ave	6LD	4,118	4,240	D or better	NO	6LD	4,240	4,813	F	135	4,949	F
Hallandale Beach Blvd - From NE 10th Ave to NE 14th Ave	6LD	4,505	4,240	F	NO	6LD	4,240	5,255	F	138	5,392	F
Hallandale Beach Blvd - From NE 14th Ave to Layne Blvd	6LD	3,772	4,240	D or better	NO	6LD	4,240	4,497	F	158	4,654	F
Hallandale Beach Blvd - From Layne Blvd to Golden Isles Dr	6LD	3,342	4,240	D or better	NO	6LD	4,240	4,022	D or better	164	4,186	D or better
Hallandale Beach Blvd - From Golden Isles Dr to Diplomat Pkwy	6LD	3,401	4,240	D or better	NO	6LD	4,240	4,101	D or better	87	4,189	D or better
Hallandale Beach Blvd - From Diplomat Pkwy to 3 Islands Blvd	6LD	3,330	4,240	D or better	NO	6LD	4,240	3,847	D or better	87	3,934	D or better
Hallandale Beach Blvd - From 3 Islands Blvd to SE 26th Ave	6LD	2,995	4,240	D or better	NO	6LD	4,240	3,725	D or better	85	3,810	D or better
Hallandale Beach Blvd - From SE 26th Ave to Ocean Dr	6LD	3,085	4,240	D or better	NO	6LD	4,240	3,814	D or better	62	3,788	D or better
SE 26 Avenue - From Hallandale Beach Blvd to Diana Drive	2LU	113	1,040	D or better	NO	2LU	1,040	115	D or better	147	214	D or better
Diana Drive - From SE 26 Avenue to Golden Isles Drive	2LU	246	1,040	D or better	NO	2LU	1,040	276	D or better	99	375	D or better
Golden Isles Drive - From Diana Drive to Hallandale Beach Blvd	2LU	346	1,040	D or better	NO	2LU	1,040	487	D or better	101	588	D or better

* - From FDOT Generalized LOS Tables

** - 2011 Collected Data

*** - Calculated from 2011 data

5.1 Roadway Segment Level of Service Summary

Similar to Figure 4-1, Figure 5-1 shows that all the arterial links operate at acceptable levels of service, with the exception of the following:

1. Hallandale Beach Boulevard from US 1 to NE 10th Avenue (AM Peak)
2. Hallandale Beach Boulevard from US 1 to Layne Boulevard (PM Peak)

Therefore, each of the failing roadway segments within the study area will operate below acceptable levels of service regardless of the addition of project traffic.

5.2 Intersection Level of Service Summary

The intersection level of service analysis performed for future conditions including the project traffic showed that each of the intersections performed at the same level of service as the future conditions without including the project traffic.

An analysis of existing traffic, plus background, plus committed traffic, shows that each of the intersections operates at acceptable levels of service, with the exception of the following:

1. Hallandale Beach Boulevard at Ocean Drive (AM and PM Peak)
2. Hallandale Beach Boulevard at NE 14th Avenue (AM and PM Peak)
3. Hallandale Beach Boulevard at US 1 (AM and PM Peak)
4. Hallandale Beach Boulevard at Golden Isles Drive (PM Peak Only)

As a secondary measure, operational improvements were examined to improve intersection levels of service. As a first step, signal operations were improved by optimization of the intersection green splits. This operational improvement showed reduced delay time for each of the signalized intersections and even improved several intersections which were operating below acceptable levels of service. Upon completion of this measure, the analysis shows that the following intersections will still operate below an acceptable level of service:

1. Hallandale Beach Boulevard at Ocean Drive (PM Peak Only)
2. Hallandale Beach Boulevard at NE 14th Avenue (PM Peak Only)
3. Hallandale Beach Boulevard at US 1 (AM and PM Peak)




As shown, the addition of the project traffic to the roadway network will not deteriorate the intersection level of service for any studied intersections beyond projected future background conditions.


All Synchro output sheets are included in Appendix H.




Beachwalk Development - Future Total Traffic AM (1 of 2)




Beachwalk Development - Future Total Traffic AM (2 of 2)




Beachwalk Development - Future Total Traffic PM (1 of 2)




Beachwalk Development - Future Total Traffic PM (2 of 2)




Beachwalk Development - *Optimized* Future Total Traffic AM (1 of 2)




Beachwalk Development - *Optimized* Future Total Traffic AM (2 of 2)



Beachwalk Development - *Optimized* Future Total Traffic PM (1 of 2)



Beachwalk Development - *Optimized* Future Total Traffic PM (2 of 2)



6. Conclusion and Recommendations

CGA was commissioned by PRH-2600 Hallandale Beach LLC to provide a Traffic Impact Study for the development of "Beachwalk", located at 2600 Hallandale Beach Boulevard (State Road 858) within the City of Hallandale Beach. The proposed development is a multi-story building that will consist of hotel and residential units. The project will be developed in one (1) distinct phase, with opening year anticipated to occur in year 2015, as follows:

1. Hotel: 216 Two (2) bedroom suites and 216 standard rooms as well as a 1,225 square foot accessory hotel restaurant
2. High-Rise Condominium: 84 dwelling units

An assessment of the proposed development traffic for both the AM and PM peak period during typical weekday conditions was performed. The existing roadway segment analysis shows that all of the roadway segments within the study area currently operate at or above level of service (LOS) "D" during the AM and PM peak period, with the exception of Hallandale Beach Boulevard from NE 10th Avenue to NE 14th Avenue which operates below LOS "D" during the PM peak period. The existing intersection analysis shows that all intersections within the study area currently operate at or above LOS "D" during the AM peak hour, with the exception of E. Hallandale Beach Boulevard at US 1. During the PM peak hour, the existing intersection analysis shows that all intersections currently operate at or above LOS "D", with the exception of Hallandale Beach Boulevard at NE 14th Avenue and Hallandale Beach Boulevard at US 1.

Committed development information was obtained from the Wal-mart Expansion Traffic Impact Study, August 2010, provided by City staff, which included data from several of the most up-to-date committed development studies for the city. The studies provided trip generation for the PM peak period, however, no available AM peak period committed development data was available. Therefore, since the developments listed in Table 4-1 would likely yield a higher number of project trips in the PM peak hour, to be conservative, the reciprocal movements of the PM peak hour committed trips were calculated and utilized for the AM peak hour committed development trips.

The future traffic growth rate was developed using a trend analysis based on historical traffic data from the FDOT Traffic DVD database. Historical trend analyses for traffic count stations within the study area indicate that the average annual growth rate is

approximately 0.5 percent (%). This conservative annual growth rate was utilized to calculate expected background traffic growth from the existing 2011 traffic volumes for the traffic impact area.

An analysis of Year 2015 traffic shows that each of the studied intersections operates at or above LOS "D" with or without project-generated traffic, with the exception of the following intersections which operate below LOS "D" with or without project-generated traffic:

1. Hallandale Beach Boulevard at Ocean Drive (AM and PM Peak)
2. Hallandale Beach Boulevard at NE 14th Avenue (AM and PM Peak)
3. Hallandale Beach Boulevard at US 1 (AM and PM Peak)
4. Hallandale Beach Boulevard at Golden Isles Drive (PM Peak Only). However, signal timing improvements proposed in this report will allow the intersection to operate at or above LOS "D" with project-generated traffic included.

In addition, all studied arterial links operate at or above LOS "D" with or without project-generated traffic, with the exception of the following arterial links which operate below LOS "D" with or without project-generated traffic:

1. Hallandale Beach Boulevard from US 1 to NE 10th Avenue (AM Peak)
2. Hallandale Beach Boulevard from US 1 to Layne Boulevard (PM Peak)

An analysis of the future 2015 conditions with project traffic showed that each of the failing roadway segments within the study area will operate below acceptable levels of service regardless of the addition of project traffic. The intersection level of service analysis for future conditions including project traffic showed that each of the intersections performed at the same level of service as the future conditions without project traffic during both the AM and PM peak hour.

For the intersection of Hallandale Beach Boulevard at Golden Isles Drive, optimization of the intersection signal timing resulted in the intersection operating at or above LOS "D" during both the AM and PM peak periods with the addition of project-generated traffic.

In conclusion, the results of this study demonstrate that the traffic generated by the proposed "Beachwalk" development project can be accommodated on the existing roadway network and levels of service expected without the project can be maintained upon the addition of project-generated traffic.



APPENDIX – A

Transit Route Information



TIMETABLE

ROUTE 28

Monday - Friday

Effective 10/31/10

Memorial Hospital Miramar
to Aventura Mall

via Miramar Parkway/
Hallandale
Beach Boulevard



Download & Print at
www.broward.org/bct



Wheelchair Accessible
Bike Racks

Customer Service

Monday - Friday 7 am - 8 pm

Saturday, Sunday and Holidays 8:30 am - 5 pm

Transit Operations Agents help with:

- Trip planning
- Identifying Bus Pass
- Routes, times and sales locations transfer information
- Special event information

Lost and Found: 954-357-6414, Monday - Friday,
8:30 am - 4:30 pm

Holiday Bus Service

Sunday bus service is provided on the following observed holidays:

New Year's Day	Labor Day
Memorial Day	Thanksgiving Day
Independence Day	Christmas Day

Fares

Exact fare, dollar bill or coins required. Operators do not carry change.

Fares are: Regular, Senior/Youth/Disabled/Medicare/Student.*
Children (under 40 inches ride FREE)

Fare Deals

All Day Bus Pass offers unlimited rides on all routes. On sale aboard all BCT buses.

NOTE: Other cost saving passes cannot be purchased on BCT buses, but are available at the Central Bus Terminal and at authorized distributors.

10 Ride Pass

10 Rides any time, any day.

Expires after the tenth ride is taken.

7 Day Pass

Unlimited rides for seven consecutive days.

Starts on the first day card is used.

Expires after the seventh day.

31 Day Adult Pass

Unlimited rides for 31 consecutive days. Starts on the first day card is used.

31 Day Reduced Pass

Youth*, Seniors*, Disabled*, Medicare*, College Student*. Unlimited rides for 31 consecutive days.

Starts on the first day card is used.

Bus Passes are not redeemable, refundable or transferrable. Damaged cards are invalid. Lost, stolen or damaged cards will not be replaced.

***NOTICE:** Proof of age is required for Youth fare (18 years or younger) and for Senior fare (65 years or older). For College Student Bus Pass, a college photo ID card is required. For Disabled and Medicare fare, proof of disability (Medicare card) and photo I.D. is required. Eligible Senior fare patrons are encouraged to acquire their BCT Reduced Fare Photo ID cards.

TRANSFER POLICY

NO TRANSFERS ARE ISSUED BETWEEN BCT BUSES.

TO OTHER TRANSIT SYSTEMS:

When transferring from BCT to Miami-Dade Transit (MDT), Palm-Tran or Tri-Rail you get a free transfer and must pay the appropriate fare on the other transit system.

FROM OTHER TRANSIT SYSTEMS:

When transferring to BCT from Miami-Dade Transit (MDT), Palm Tran or Tri-Rail, passengers pay \$.50 with a transfer issued by MDT, Palm Tran, or with a Tri-Rail pass.

MONDAY -FRIDAY

EASTBOUND

To Aventura Mall

MEMORIAL HOSPITAL MIRAMAR	MIRAMAR PKY & FLAMINGO RD	MIRAMAR PKY & UNIVERSITY DR	HALLANDALE BEACH BLVD. & HWY. 441	HALLANDALE BEACH BLVD. & U.S. 1	COUNTYLINE RD & A-1-A	AVENTURA MALL
1	2	3	4	5	6	7
		5:10a	5:19a	5:35a	5:46a	5:56a
	5:30a	5:42a	5:51a	6:07a	6:19a	6:29a
5:45a	5:57a	6:10a	6:20a	6:37a	6:49a	6:59a
6:05a	6:18a	6:31a	6:41a	6:58a	7:11a	7:21a
6:25a	6:38a	6:51a	7:01a	7:19a	7:32a	7:42a
6:45a	6:58a	7:12a	7:23a	7:41a	7:54a	8:04a
7:05a	7:19a	7:33a	7:44a	8:02a	8:15a	8:25a
7:25a	7:39a	7:53a	8:04a	8:22a	8:35a	8:45a
7:45a	7:59a	8:13a	8:24a	8:42a	8:55a	9:06a
8:05a	8:19a	8:33a	8:44a	9:02a	9:16a	9:27a
8:25a	8:39a	8:52a	9:02a	9:20a	9:34a	9:45a
8:45a	8:59a	9:12a	9:22a	9:41a	9:55a	10:06a
9:15a	9:28a	9:41a	9:51a	10:10a	10:24a	10:35a
9:45a	9:58a	10:11a	10:21a	10:40a	10:54a	11:05a
10:15a	10:28a	10:41a	10:51a	11:10a	11:24a	11:35a
10:45a	10:58a	11:11a	11:21a	11:40a	11:54a	12:05p
11:15a	11:28a	11:41a	11:51a	12:10p	12:24p	12:35p
11:45a	11:58a	12:11p	12:21p	12:40p	12:54p	1:05p
12:15p	12:28p	12:41p	12:51p	1:10p	1:24p	1:35p
12:45p	12:58p	1:11p	1:21p	1:40p	1:54p	2:05p
1:15p	1:28p	1:41p	1:51p	2:10p	2:24p	2:35p
1:45p	1:58p	2:11p	2:21p	2:40p	2:54p	3:05p
2:15p	2:28p	2:41p	2:51p	3:10p	3:24p	3:35p
	2:43p	2:56p	3:06p	3:25p	3:39p	3:50p
2:45p	2:58p	3:11p	3:21p	3:40p	3:54p	4:05p
3:05p	3:18p	3:31p	3:41p	4:00p	4:13p	4:23p
3:25p	3:38p	3:51p	4:01p	4:19p	4:32p	4:42p
3:45p	3:58p	4:12p	4:23p	4:41p	4:54p	5:04p
4:05p	4:19p	4:33p	4:44p	5:02p	5:15p	5:25p
4:25p	4:39p	4:53p	5:04p	5:22p	5:35p	5:45p
4:45p	4:59p	5:13p	5:24p	5:42p	5:55p	6:05p
5:05p	5:19p	5:33p	5:44p	6:02p	6:15p	6:25p
5:25p	5:39p	5:53p	6:04p	6:22p	6:35p	6:45p
5:45p	5:59p	6:12p	6:22p	6:39p	6:51p	7:01p
6:05p	6:18p	6:31p	6:41p	6:58p	7:10p	7:20p
6:25p	6:38p	6:51p	7:01p	7:18p	7:30p	7:40p
6:45p	6:58p	7:11p	7:21p	7:38p	7:50p	8:00p
7:15p	7:28p	7:41p	7:51p	8:08p	8:20p	8:30p
7:45p	7:58p	8:11p	8:21p	8:38p	8:50p	9:00p
8:15p	8:28p	8:41p	8:51p	9:08p	9:20p	9:30p
8:45p	8:57p	9:09p	9:18p	9:34p	9:45p	9:55p
9:15p	9:27p	9:39p	9:48p	10:04p	10:15p	10:25p
10:00p	10:12p	10:24p	10:33p	10:50p		
10:45p	10:57p	11:09p	11:18p	11:35p		

MONDAY -FRIDAY


WESTBOUND

To Memorial Hospital Miramar

AVENTURA MALL	COUNTYLINE RD & A-I-A	HALLANDALE BEACH BLVD. & US 1	HALLANDALE BEACH BLVD. & HWY. 441	MIRAMAR PKY & UNIVERSITY DR.	MIRAMAR PKY & FLAMINGO RD	MEMORIAL HOSPITAL MIRAMAR
7	6	5	4	3	2	1
6:05a	6:15a	5:30a 6:00a 6:27a	5:46a 6:17a 6:45a 7:00a	5:55a 6:27a 6:55a 7:11a	6:08a 6:40a 7:09a 7:25a	6:20a 6:53a 7:23a 7:39a
6:35a	6:45a	6:57a	7:15a	7:26a	7:40a	7:54a
6:55a	7:05a	7:18a	7:36a	7:47a	8:01a	8:15a
7:15a	7:25a	7:38a	7:56a	8:07a	8:21a	8:35a
7:35a	7:45a	7:58a	8:16a	8:27a	8:41a	8:55a
7:55a	8:05a	8:18a	8:36a	8:47a	9:01a	G9:15a
8:15a	8:25a	8:38a	8:56a	9:06a	9:19a	9:32a
8:35a	8:46a	9:00a	9:19a	9:29a	9:42a	9:55a
8:55a	9:06a	9:20a	9:39a	9:49a	10:02a	G10:15a
9:15a	9:26a	9:40a	9:59a	10:09a	10:22a	10:35a
9:45a	9:56a	10:10a	10:29a	10:39a	10:52a	11:05a
10:15a	10:26a	10:40a	10:59a	11:09a	11:22a	11:35a
10:45a	10:56a	11:10a	11:29a	11:39a	11:52a	12:05p
11:15a	11:26a	11:40a	11:59a	12:09p	12:22p	12:35p
11:45a	11:56a	12:10p	12:29p	12:39p	12:52p	1:05p
12:15p	12:26p	12:40p	12:59p	1:09p	1:22p	1:35p
12:45p	12:56p	1:10p	1:29p	1:39p	1:52p	2:05p
1:15p	1:26p	1:40p	1:59p	2:09p	2:22p	2:35p
1:45p	1:56p	2:10p	2:29p	2:39p	2:52p	3:05p
2:15p	2:26p	2:40p	2:59p	3:09p	3:22p	3:35p
2:45p	2:56p	3:10p	3:29p	3:39p	3:52p	4:05p
3:15p	3:26p	3:40p	3:59p	4:10p	4:24p	4:38p
3:35p	3:46p	4:00p	4:18p	4:29p	4:43p	4:57p
3:55p	4:05p	4:18p	4:36p	4:47p	5:01p	5:15p
4:15p	4:25p	4:38p	4:56p	5:07p	5:21p	5:35p
4:35p	4:45p	4:58p	5:16p	5:27p	5:41p	5:55p
4:55p	5:05p	5:18p	5:36p	5:47p	6:01p	6:14p
5:15p	5:25p	5:38p	5:56p	6:06p	6:19p	6:32p
5:35p	5:45p	5:57p	6:14p	6:24p	6:37p	G6:50p
5:55p	6:05p	6:17p	6:34p	6:44p	6:57p	7:10p
6:15p	6:25p	6:37p	6:54p	7:04p	7:17p	7:30p
6:45p	6:55p	7:07p	7:24p	7:34p	7:47p	8:00p
7:15p	7:25p	7:37p	7:54p	8:04p	8:17p	8:30p
7:45p	7:55p	8:07p	8:24p	8:34p	8:47p	9:00p
8:15p	8:25p	8:37p	8:54p	9:04p	9:17p	G9:30p
8:45p	8:55p	9:06p	9:22p	9:31p	9:42p	9:55p
9:15p	9:25p	9:36p	9:52p	10:01p	10:13p	10:25p
10:00p	10:10p	10:21p	10:36p	10:44p	G10:55p	
10:45p	10:55p	11:06p	11:21p	11:29p	G11:40p	

ROUTE 28

Memorial Hospital - Miramar to Aventura Mall
via Miramar Parkway/Hallandale Beach Boulevard



For more details on our fares please
visit our web site at
broward.org/bct/faresandpasses.htm
or call customer service: 954.357.8400.

Reading A Timetable - It's Easy

1. The map shows the exact bus route.
2. Major route intersections are called time points. Time points are shown with the symbol □ .
3. The timetable lists major time points for bus route. Listed under time points are scheduled departure times.
4. Reading from left to right, indicates the time for each bus trip.
5. The bus picks up and drops off riders at all BCT bus stop signs along the route where there is a Broward County bus stop sign.
6. Arrive at the bus stop five minutes early. Buses operate as close to published timetables as traffic conditions allow.

Information: 954.357.8400

Hearing-speech impaired/TTY:
954.357.8302

This publication can be made
available in large print, tape cassette,
or Braille, by request.



This symbol is used on
bus stop signs to indicate
accessible bus stops.



BOARD OF COUNTY COMMISSIONERS
An equal opportunity employer and provider of services.

This public document was promulgated at a cost of \$1,062 or \$.028
per copy, to inform the public about the Transportation Division's schedule
and route information. 09/08



printed on recycled paper



WHEN IT COMES TO OUR SAFETY, WE CAN ALWAYS
USE AN EXTRA PAIR OF EYES AND EARS.
BE ALERT.
CALL 954-357-LOOK (5665). TELL US.

PROTECTIONS OF TITLE VI OF THE CIVIL RIGHTS ACT OF 1964 AS AMENDED

Any person(s) or group(s) who believes that they have been subjected to discrimination because of race, color, or national origin, under any transit program or activity provided by Broward County Transit (BCT), may call 954-357-8481 to file a Title VI discrimination complaint or write to Broward County Transportation Department, Compliance Manager, 3201 West Copans Road, Bldg. 1, Pompano Beach, Florida 33069.

TIME TABLE

ROUTE 5

Monday - Sunday
Effective 1/9/11

Pembroke Lakes Mall to
Hallandale Beach City Hall
via Pembroke Road

BROWARD
COUNTY
Transit
A service of the
Broward County Commission

facebook

You Tube

Download & Print at broward.org/bct
Wheelchair Accessible
Bike Racks

Customer Service

Monday - Friday 7 am - 8 pm
Saturday, Sunday and Holidays 8:30 am - 5 pm

Transit Operations Agents help with:

- Trip planning
- Identifying Bus Pass
- Routes, times and sales locations transfer information
- Special event information

Lost and Found: 954-357-6414, Monday - Friday,
8:30 am - 4:30 pm

Holiday Bus Service

Sunday bus service is provided on the following observed holidays:

New Year's Day	Labor Day
Memorial Day	Thanksgiving Day
Independence Day	Christmas Day

Fares

Exact fare, dollar bill or coins required. Operators do not carry change.

Fares are: Regular, Senior/Youth/Disabled/Medicare/Student.*
Children (under 40 inches ride FREE)

Fare Deals

All Day Bus Pass offers unlimited rides on all routes. On sale aboard all BCT buses.

NOTE: Other cost saving passes cannot be purchased on BCT buses, but are available at the Central Bus Terminal and at authorized distributors.

10 Ride Pass

10 Rides any time, any day.
Expires after the tenth ride is taken.

7 Day Pass

Unlimited rides for seven consecutive days.
Starts on the first day card is used.
Expires after the seventh day.

31 Day Adult Pass

Unlimited rides for 31 consecutive days. Starts on the first day card is used.

31 Day Reduced Pass

Youth*, Seniors*, Disabled*, Medicare*, College Student*. Unlimited rides for 31 consecutive days.
Starts on the first day card is used.

Bus Passes are not redeemable, refundable or transferrable. Damaged cards are invalid. Lost, stolen or damaged cards will not be replaced.

***NOTICE:** Proof of age is required for Youth fare (18 years or younger) and for Senior fare (65 years or older). For College Student Bus Pass, a college photo ID card is required. For Disabled and Medicare fare, proof of disability (Medicare card) and photo I.D. is required. Eligible Senior fare patrons are encouraged to acquire their BCT Reduced Fare Photo ID cards.

TRANSFER POLICY

NO TRANSFERS ARE ISSUED BETWEEN BCT BUSES.

TO OTHER TRANSIT SYSTEMS:

When transferring from BCT to Miami-Dade Transit (MDT), Palm-Tran or Tri-Rail you get a free transfer and must pay the appropriate fare on the other transit system.

FROM OTHER TRANSIT SYSTEMS:

When transferring to BCT from Miami-Dade Transit (MDT), Palm Tran or Tri-Rail, passengers pay \$.50 with a transfer issued by MDT, Palm Tran, or with a Tri-Rail pass.

Route 5

MONDAY-FRIDAY

There are additional bus stops in between those listed.

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP

Times with the letter "G" before them indicate bus returns to garage.

EASTBOUND

To Hallandale Beach City Hall

PEMBROKE LAKES MALL	MIRAMAR TOWN CENTER	PEMBROKE RD. & UNIVERSITY DR.	PEMBROKE RD. & HWY. 441	PEMBROKE RD. & S. 26 AVE.	SE 3 ST & US 1
1	2	3	4	5	6
6:00a	6:15a	6:27a	6:36a	6:46a	7:00a
6:30a	6:45a	6:57a	7:07a	7:18a	7:33a
7:00a	7:16a	7:29a	7:39a	7:50a	8:05a
7:30a	7:46a	7:59a	8:09a	8:20a	8:35a
8:00a	8:16a	8:29a	8:39a	8:50a	9:05a
8:30a	8:46a	8:59a	9:09a	9:20a	9:35aG
9:00a	9:15a	9:27a	9:36a	9:46a	10:00a
9:45a	10:00a	10:12a	10:21a	10:31a	10:45a
10:30a	10:45a	10:57a	11:06a	11:16a	11:30a
11:15a	11:30a	11:42a	11:51a	12:01p	12:15p
12:00p	12:15p	12:27p	12:36p	12:46p	1:00p
12:45p	1:00p	1:12p	1:21p	1:31p	1:45p
1:30p	1:45p	1:57p	2:06p	2:16p	2:30p
2:15p	2:30p	2:42p	2:51p	3:01p	3:15p
3:00p	3:15p	3:27p	3:36p	3:46p	4:00p
3:30p	3:45p	3:57p	4:06p	4:16p	4:30p
4:00p	4:15p	4:27p	4:36p	4:46p	5:00p
4:30p	4:45p	4:57p	5:06p	5:16p	5:30p
5:00p	5:15p	5:27p	5:36p	5:46p	6:00p
5:30p	5:45p	5:57p	6:06p	6:16p	6:30pG
6:00p	6:15p	6:27p	6:36p	6:46p	7:00p
6:45p	7:00p	7:12p	7:21p	7:31p	7:45p
7:30p	7:45p	7:57p	8:05p	8:14p	8:27p
8:15p	8:29p	8:40p	8:48p	8:57p	9:10p
9:00p	9:14p	9:25p	9:33p	9:42p	9:55pG

Route 5

MONDAY-FRIDAY

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP

Times with the letter "G" before them indicate bus returns to garage.

WESTBOUND

To Pembroke Lakes Mall

SE 3 ST & US 1	PEMBROKE RD. & S. 26 AVE.	PEMBROKE RD. & HWY. 441	PEMBROKE RD. & UNIVERSITY DR.	MIRAMAR TOWN CENTER	PEMBROKE LAKES MALL
6	5	4	3	2	1
6:15a	6:28a	6:38a	6:47a	7:01a	7:15a
6:45a	6:58a	7:08a	7:17a	7:31a	7:45a
7:15a	7:28a	7:38a	7:47a	8:01a	8:15a
7:45a	7:58a	8:08a	8:17a	8:31a	8:45a
8:15a	8:28a	8:38a	8:47a	9:01a	9:15aG
8:45a	8:58a	9:08a	9:17a	9:31a	9:45a
9:25a	9:38a	9:48a	9:57a	10:11a	10:25a
10:10a	10:23a	10:33a	10:42a	10:56a	11:10a
10:55a	11:08a	11:18a	11:27a	11:41a	11:55a
11:40a	11:53a	12:03p	12:12p	12:26p	12:40p
12:25p	12:38p	12:48p	12:57p	1:11p	1:25p
1:10p	1:23p	1:33p	1:42p	1:56p	2:10p
1:55p	2:08p	2:18p	2:27p	2:41p	2:55p
2:40p	2:53p	3:03p	3:12p	3:26p	3:40p
3:15p	3:28p	3:38p	3:47p	4:01p	4:16p
3:45p	3:58p	4:09p	4:19p	4:34p	4:49p
4:15p	4:29p	4:40p	4:50p	5:05p	5:20p
4:45p	4:59p	5:10p	5:20p	5:35p	5:50p
5:15p	5:29p	5:40p	5:50p	6:05p	6:19p
5:45p	5:58p	6:08p	6:17p	6:32p	6:45pG
6:20p	6:33p	6:43p	6:52p	7:06p	7:20p
7:05p	7:18p	7:28p	7:37p	7:51p	8:05p
7:50p	8:03p	8:12p	8:20p	8:33p	8:46p
8:35p	8:47p	8:56p	9:04p	9:17p	9:30pG
9:20p	9:32p	9:41p	9:49p	10:02p	10:15pG

Route 5

SATURDAY

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP
Times with the letter "G" before them indicate bus returns to garage.

EASTBOUND

To Hallandale Beach City Hall

PEMBROKE LAKES MALL	PEMBROKE RD. & HIATUS RD.	PEMBROKE RD. & UNIVERSITY DR.	PEMBROKE RD. & HWY. 441	PEMBROKE RD. & S. 26 AVE.	SE 3 ST & US 1
1	2	3	4	5	6
7:00a	7:11a	7:20a	7:28a	7:37a	7:50a
8:00a	8:11a	8:20a	8:28a	8:37a	8:50a
9:00a	9:12a	9:22a	9:31a	9:41a	9:55a
10:00a	10:12a	10:22a	10:31a	10:41a	10:55a
11:00a	11:12a	11:22a	11:31a	11:41a	11:55a
12:00p	12:12p	12:22p	12:31p	12:41p	12:55p
1:00p	1:12p	1:22p	1:31p	1:41p	1:55p
2:00p	2:12p	2:22p	2:31p	2:41p	2:55p
3:00p	3:12p	3:22p	3:31p	3:41p	3:55p
4:00p	4:12p	4:22p	4:31p	4:41p	4:55p
5:00p	5:12p	5:22p	5:31p	5:41p	5:55p
6:00p	6:11p	6:20p	6:28p	6:37p	6:50p
7:00p	7:11p	7:20p	7:28p	7:37p	7:50p
8:00p	8:11p	8:20p	8:28p	8:37p	8:50p
9:00p	9:11p	9:20p	9:28p	9:37p	9:50pG

Route 5

SATURDAY

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP
Times with the letter "G" before them indicate bus returns to garage.

WESTBOUND

To Pembroke Lakes Mall

SE 3 ST & US 1	PEMBROKE RD. & S. 26 AVE.	PEMBROKE RD. & HWY. 441	PEMBROKE RD. & UNIVERSITY DR.	PEMBROKE RD. & HIATUS RD.	PEMBROKE LAKES MALL
6	5	4	3	2	1
7:00a	7:12a	7:21a	7:29a	7:38a	7:50a
8:00a	8:12a	8:21a	8:29a	8:38a	8:50a
9:00a	9:13a	9:23a	9:32a	9:42a	9:55a
10:00a	10:13a	10:23a	10:32a	10:42a	10:55a
11:00a	11:13a	11:23a	11:32a	11:42a	11:55a
12:00p	12:13p	12:23p	12:32p	12:42p	12:55p
1:00p	1:13p	1:23p	1:32p	1:42p	1:55p
2:00p	2:13p	2:23p	2:32p	2:42p	2:55p
3:00p	3:13p	3:23p	3:32p	3:42p	3:55p
4:00p	4:13p	4:23p	4:32p	4:42p	4:55p
5:00p	5:13p	5:23p	5:32p	5:42p	5:55p
6:00p	6:12p	6:21p	6:29p	6:38p	6:50p
7:00p	7:12p	7:21p	7:29p	7:38p	7:50p
8:00p	8:12p	8:21p	8:29p	8:38p	8:50p
9:00p	9:12p	9:21p	9:29p	9:38p	9:50pG

Route 5

SUNDAY

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP

Times with the letter "G" before them indicate bus returns to garage.

EASTBOUND

To Hallandale Beach City Hall

PEMBROKE LAKES MALL	PEMBROKE RD & HIATUS RD	PEMBROKE RD. & UNIVERSITY DR.	PEMBROKE RD. & HWY. 441	PEMBROKE RD. & S. 26 AVE.	SE 3 ST & US 1
1	2	3	4	5	6
8:00a	8:11a	8:20a	8:28a	8:37a	8:50a
9:00a	9:11a	9:20a	9:28a	9:37a	9:50a
10:00a	10:11a	10:20a	10:28a	10:37a	10:50a
11:00a	11:11a	11:20a	11:28a	11:37a	11:50a
12:00p	12:11p	12:20p	12:28p	12:37p	12:50p
1:00p	1:11p	1:20p	1:28p	1:37p	1:50p
2:00p	2:11p	2:20p	2:28p	2:37p	2:50p
3:00p	3:11p	3:20p	3:28p	3:37p	3:50p
4:00p	4:11p	4:20p	4:28p	4:37p	4:50p
5:00p	5:11p	5:20p	5:28p	5:37p	5:50p
6:00p	6:11p	6:20p	6:28p	6:37p	6:50p
7:00p	7:11p	7:20p	7:28p	7:37p	7:50p
8:00p	8:11p	8:20p	8:28p	8:37p	8:50p G
8:00p	8:11p	8:20p	8:28p	8:37p	8:50p G

Route 5

SUNDAY

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP

Times with the letter "G" before them indicate bus returns to garage.


WESTBOUND

To Pembroke Lakes Mall

SE 3 ST & US 1	PEMBROKE RD. & S. 26 AVE.	PEMBROKE RD. & HWY. 441	PEMBROKE RD. & UNIVERSITY DR.	PEMBROKE RD & HIATUS RD	PEMBROKE LAKES MALL
6	5	4	3	2	1
8:00a	8:12a	8:21a	8:29a	8:38a	8:50a
9:00a	9:12a	9:21a	9:29a	9:38a	9:50a
10:00a	10:12a	10:21a	10:29a	10:38a	10:50a
11:00a	11:12a	11:21a	11:29a	11:38a	11:50a
12:00p	12:12p	12:21p	12:29p	12:38p	12:50p
1:00p	1:12p	1:21p	1:29p	1:38p	1:50p
2:00p	2:12p	2:21p	2:29p	2:38p	2:50p
3:00p	3:12p	3:21p	3:29p	3:38p	3:50p
4:00p	4:12p	4:21p	4:29p	4:38p	4:50p
5:00p	5:12p	5:21p	5:29p	5:38p	5:50p
6:00p	6:12p	6:21p	6:29p	6:38p	6:50p
7:00p	7:12p	7:21p	7:29p	7:38p	7:50p
8:00p	8:12p	8:21p	8:29p	8:38p	8:50pG

ROUTE 5

Pembroke Lakes Mall to
Hallandale Beach City Hall
via **Pembroke Road**



For more details on our fares please
visit our web site at
broward.org/bct/faresandpasses.htm
or call customer service: 954.357.8400.

Reading A Timetable - It's Easy

1. The map shows the exact bus route.
2. Major route intersections are called time points. Time points are shown with the symbol □ .
3. The timetable lists major time points for bus route. Listed under time points are scheduled departure times.
4. Reading from left to right, indicates the time for each bus trip.
5. The bus picks up and drops off riders at all BCT bus stop signs along the route where there is a Broward County bus stop sign.
6. Arrive at the bus stop five minutes early. Buses operate as close to published timetables as traffic conditions allow.

Information: 954.357.8400

**Hearing-speech impaired/TTY:
954.357.8302**

This publication can be made
available in large print, tape cassette,
or Braille, by request.



This symbol is used on
bus stop signs to indicate
accessible bus stops.



BROWARD COUNTY
BOARD OF COUNTY COMMISSIONERS
An equal opportunity employer and provider of services.

This public document was promulgated at a cost of \$1,062 or \$.028
per copy, to inform the public about the Transportation Division's schedule
and route information. 09/08



printed on recycled paper

PROTECTIONS OF TITLE VI OF THE CIVIL RIGHTS ACT OF 1964 AS AMENDED

Any person(s) or group(s) who believes that they have been subjected to discrimination because of race, color, or national origin, under any transit program or activity provided by Broward County Transit (BCT), may call 954-357-8481 to file a Title VI discrimination complaint or write to Broward County Transportation Department, Compliance Manager, 3201 West Copans Road, Bldg. 1, Pompano Beach, Florida 33069.

TIMETABLE

ROUTE 4

Monday - Sunday
Effective 10/31/10

Hallandale Beach Blvd. to
Fort Lauderdale/Hollywood
Airport Tri-Rail Station
via A1A



Download & Print at
www.broward.org/bct



Wheelchair Accessible
Bike Racks

Customer Service

Monday - Friday 7 am - 8 pm

Saturday, Sunday and Holidays 8:30 am - 5 pm

Transit Operations Agents help with:

- Trip planning
- Identifying Bus Pass
- Routes, times and sales locations transfer information
- Special event information

Lost and Found: 954-357-6414, Monday - Friday,
8:30 am - 4:30 pm

Holiday Bus Service

Sunday bus service is provided on the following observed holidays:

New Year's Day	Labor Day
Memorial Day	Thanksgiving Day
Independence Day	Christmas Day

Fares

Exact fare, dollar bill or coins required. Operators do not carry change.

Fares are: Regular, Senior/Youth/Disabled/Medicare/Student.*
Children (under 40 inches ride FREE)

Fare Deals

All Day Bus Pass offers unlimited rides on all routes. On sale aboard all BCT buses.

NOTE: Other cost saving passes cannot be purchased on BCT buses, but are available at the Central Bus Terminal and at authorized distributors.

10 Ride Pass

10 Rides any time, any day.

Expires after the tenth ride is taken.

7 Day Pass

Unlimited rides for seven consecutive days.

Starts on the first day card is used.

Expires after the seventh day.

31 Day Adult Pass

Unlimited rides for 31 consecutive days. Starts on the first day card is used.

31 Day Reduced Pass

Youth*, Seniors*, Disabled*, Medicare*, College Student*. Unlimited rides for 31 consecutive days.

Starts on the first day card is used.

Bus Passes are not redeemable, refundable or transferrable. Damaged cards are invalid. Lost, stolen or damaged cards will not be replaced.

***NOTICE:** Proof of age is required for Youth fare (18 years or younger) and for Senior fare (65 years or older). For College Student Bus Pass, a college photo ID card is required. For Disabled and Medicare fare, proof of disability (Medicare card) and photo I.D. is required. Eligible Senior fare patrons are encouraged to acquire their BCT Reduced Fare Photo ID cards.

TRANSFER POLICY

NO TRANSFERS ARE ISSUED BETWEEN BCT BUSES.

TO OTHER TRANSIT SYSTEMS:

When transferring from BCT to Miami-Dade Transit (MDT), Palm-Tran or Tri-Rail you get a free transfer and must pay the appropriate fare on the other transit system.

FROM OTHER TRANSIT SYSTEMS:

When transferring to BCT from Miami-Dade Transit (MDT), Palm Tran or Tri-Rail, passengers pay \$.50 with a transfer issued by MDT, Palm Tran, or with a Tri-Rail pass.

MONDAY-FRIDAY

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP

Times with the letter "G" before them indicate bus returns to garage.

NORTHBOUND

To Fort Lauderdale Airport Tri-Rail

HALLANDALE BCH. BLVD. & NE 14 AVE.	HALLANDALE BCH. BLVD. & SR A1A	YOUNG CIRCLE & GREYHOUND STATION	DANIA BEACH	DANIA BCH. BLVD. & US 1	FORT LAUDERDALE AIRPORT TRI-RAIL STATION
1	2	3	4	5	6
5:35a	5:47a	6:00a	6:20a	6:25a	6:35a
6:20a	6:32a	6:45a	7:05a	7:11a	7:22a
7:00a	7:13a	7:27a	7:48a	7:54a	8:05a
7:50a	8:03a	8:17a	8:38a	8:44a	8:55a
8:35a	8:48a	9:02a	9:22a	9:27a	9:37a
9:20a	9:32a	9:45a	10:05a	10:10a	10:20a
10:05a	10:17a	10:30a	10:50a	10:55a	11:05a
10:50a	11:02a	11:15a	11:35a	11:40a	11:50a
11:35a	11:47a	12:00p	12:20p	12:25p	12:35p
12:20p	12:32p	12:45p	1:05p	1:10p	1:20p
1:05p	1:17p	1:30p	1:50p	1:55p	2:05p
1:50p	2:02p	2:15p	2:35p	2:40p	2:50p
2:35p	2:47p	3:00p	3:20p	3:25p	3:35p
3:20p	3:32p	3:45p	4:05p	4:11p	4:22p
4:05p	4:18p	4:32p	4:53p	4:59p	5:10p
4:50p	5:03p	5:17p	5:38p	5:44p	5:55p
5:35p	5:48p	6:02p	6:22p	6:27p	6:37p
6:20p	6:32p	6:45p	7:05p	7:10p	7:20p
7:05p	7:17p	7:30p	7:50p	7:55p	8:05p
7:50p	8:02p	8:15p	8:35p	8:40p	8:50p
8:35p	8:47p	9:00p	9:20p	9:25p	9:35p
9:20p	9:32p	9:45p	10:05p	10:10p	10:20p

SOUTHBOUND

Hallandale Beach Blvd.

FORT LAUDERDALE AIRPORT TRI-RAIL STATION	DANIA BCH. BLVD. & US 1	DANIA BEACH	YOUNG CIRCLE & GREYHOUND STATION	HALLANDALE BCH. BLVD. & SR A1A	HALLANDALE BCH. BLVD. & NE 14 AVE.
6	5	4	3	2	1
5:15a	5:25a	5:30a	5:50a	6:05a	6:10a
6:00a	6:10a	6:15a	6:35a	6:50a	6:55a
6:45a	6:55a	7:00a	7:21a	7:37a	7:43a
7:30a	7:41a	7:47a	8:08a	8:24a	8:30a
8:15a	8:26a	8:32a	8:53a	9:08a	9:13a
9:00a	9:10a	9:15a	9:35a	9:50a	9:55a
9:45a	9:55a	10:00a	10:20a	10:35a	10:40a
10:30a	10:40a	10:45a	11:05a	11:20a	11:25a
11:15a	11:25a	11:30a	11:50a	12:05p	12:10p
12:00p	12:10p	12:15p	12:35p	12:50p	12:55p
12:45p	12:55p	1:00p	1:20p	1:35p	1:40p
1:30p	1:40p	1:45p	2:05p	2:20p	2:25p
2:15p	2:25p	2:30p	2:50p	3:05p	3:10p
3:00p	3:10p	3:15p	3:35p	3:50p	3:55p
3:45p	3:55p	4:00p	4:21p	4:37p	4:43p
4:30p	4:41p	4:47p	5:08p	5:24p	5:30p
5:15p	5:26p	5:32p	5:53p	6:08p	6:13p
6:00p	6:10p	6:15p	6:35p	6:50p	6:55p
6:45p	6:55p	7:00p	7:20p	7:35p	7:40p
7:30p	7:40p	7:45p	8:05p	8:20p	8:25p
8:15p	8:25p	8:30p	8:50p	9:05p	9:10p
9:00p	9:10p	9:15p	9:35p	9:50p	9:55p

SATURDAY

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP

Times with the letter "G" before them indicate bus returns to garage.

NORTHBOUND

To Fort Lauderdale Airport Tri-Rail

SOUTHBOUND

Hallandale Beach Blvd.



HALLANDALE BLVD. & NE 14 AVE.	HALLANDALE BLVD. & SR A1A	YOUNG CIRCLE & GREYHOUND STATION	DANIA BEACH	DANIA BCH. BLVD. & US 1	FORT LAUDERDALE AIRPORT TRI-RAIL STATION	FORT LAUDERDALE AIRPORT TRI-RAIL STATION	DANIA BCH. BLVD. & US 1	DANIA BEACH	YOUNG CIRCLE & GREYHOUND STATION	HALLANDALE BLVD. & SR A1A	HALLANDALE BLVD. & NE 14 AVE.
1	2	3	4	5	6	6	5	4	3	2	1
6:20a	6:32a	6:00a	6:20a	6:25a	6:35a	6:00a	6:10a	6:15a	6:35a	6:50a	6:55a
7:05a	7:17a	6:45a	7:05a	7:10a	7:20a	6:45a	6:55a	7:00a	7:20a	7:35a	7:40a
7:50a	8:02a	7:30a	7:50a	7:55a	8:05a	7:30a	7:40a	7:45a	8:05a	8:20a	8:25a
8:35a	8:47a	8:15a	8:35a	8:40a	8:50a	8:15a	8:25a	8:30a	8:50a	9:05a	9:10a
9:20a	9:32a	9:00a	9:20a	9:25a	9:35a	9:00a	9:10a	9:15a	9:35a	9:50a	9:55a
10:05a	10:17a	9:45a	10:05a	10:10a	10:20a	9:45a	9:55a	10:00a	10:20a	10:35a	10:40a
10:50a	11:02a	10:30a	10:50a	10:55a	11:05a	10:30a	10:40a	10:45a	11:05a	11:20a	11:25a
11:35a	11:47a	11:15a	11:35a	11:40a	11:50a	11:15a	11:25a	11:30a	11:50a	12:05p	12:10p
12:20p	12:32p	12:00p	12:20p	12:25p	12:35p	12:00p	12:10p	12:15p	12:35p	12:50p	12:55p
1:05p	1:17p	12:45p	1:05p	1:10p	1:20p	12:45p	12:55p	1:00p	1:20p	1:35p	1:40p
1:50p	2:02p	1:30p	1:50p	1:55p	2:05p	1:30p	1:40p	1:45p	2:05p	2:20p	2:25p
2:35p	2:47p	2:15p	2:35p	2:40p	2:50p	2:15p	2:25p	2:30p	2:50p	3:05p	3:10p
3:20p	3:32p	3:00p	3:20p	3:25p	3:35p	3:00p	3:10p	3:15p	3:35p	3:50p	3:55p
4:05p	4:17p	3:45p	4:05p	4:10p	4:20p	3:45p	3:55p	4:00p	4:20p	4:35p	4:40p
4:50p	5:02p	4:30p	4:50p	4:55p	5:05p	4:30p	4:40p	4:45p	5:05p	5:20p	5:25p
5:35p	5:47p	5:15p	5:35p	5:40p	5:50p	5:15p	5:25p	5:30p	5:50p	6:05p	6:10p
6:20p	6:32p	6:00p	6:20p	6:25p	6:35p	6:00p	6:10p	6:15p	6:35p	6:50p	6:55p
7:05p	7:17p	6:45p	7:05p	7:10p	7:20p	6:45p	6:55p	7:00p	7:20p	7:35p	7:40p
7:50p	8:02p	7:30p	7:50p	7:55p	8:05p	7:30p	7:40p	7:45p	8:05p	8:20p	8:25p
8:35p	8:47p	8:15p	8:35p	8:40p	8:50p	8:15p	8:25p	8:30p	8:50p	9:05p	9:10p
		9:00p	9:20p	9:25p	9:35p						

SUNDAY

8:35a	8:47a	9:00a	9:20a	9:25a	9:35a	8:15a	8:25a	8:30a	8:50a	9:05a	9:10a
9:20a	9:32a	9:45a	10:05a	10:10a	10:20a	9:00a	9:10a	9:15a	9:35a	9:50a	9:55a
10:05a	10:17a	10:30a	10:50a	10:55a	11:05a	9:45a	9:55a	10:00a	10:20a	10:35a	10:40a
10:50a	11:02a	11:15a	11:35a	11:40a	11:50a	10:30a	10:40a	10:45a	11:05a	11:20a	11:25a
11:35a	11:47a	12:00p	12:20p	12:25p	12:35p	11:15a	11:25a	11:30a	11:50a	12:05p	12:10p
12:20p	12:32p	12:45p	1:05p	1:10p	1:20p	12:00p	12:10p	12:15p	12:35p	12:50p	12:55p
1:05p	1:17p	1:30p	1:50p	1:55p	2:05p	12:45p	12:55p	1:00p	1:20p	1:35p	1:40p
1:50p	2:02p	2:15p	2:35p	2:40p	2:50p	1:30p	1:40p	1:45p	2:05p	2:20p	2:25p
2:35p	2:47p	3:00p	3:20p	3:25p	3:35p	2:15p	2:25p	2:30p	2:50p	3:05p	3:10p
3:20p	3:32p	3:45p	4:05p	4:10p	4:20p	3:00p	3:10p	3:15p	3:35p	3:50p	3:55p
4:05p	4:17p	4:30p	4:50p	4:55p	5:05p	3:45p	3:55p	4:00p	4:20p	4:35p	4:40p
4:50p	5:02p	5:15p	5:35p	5:40p	5:50p	4:30p	4:40p	4:45p	5:05p	5:20p	5:25p
5:35p	5:47p	6:00p	6:20p	6:25p	6:35p	5:15p	5:25p	5:30p	5:50p	6:05p	6:10p
6:20p	6:32p	6:45p	7:05p	7:10p	7:20p	6:00p	6:10p	6:15p	6:35p	6:50p	6:55p
7:05p	7:17p	7:30p	7:50p	7:55p	8:05p	6:45p	6:55p	7:00p	7:20p	7:35p	7:40p
7:50p	8:02p	8:15p	8:35p	8:40p	8:50p	7:30p	7:40p	7:45p	8:05p	8:20p	8:25p

ROUTE 4

Hallandale Beach Blvd. to
Fort Lauderdale-Hollywood Airport
Tri-Rail Station
via A1A



- POINTS OF INTEREST**
- Diplomat Mall
 - Hollywood North Beach
 - Dania Jai Alai
 - Dania Beach Fishing Pier
 - IGFA Fishing Hall of Fame
 - Ocean Walk

For more details on our fares please
visit our web site at
broward.org/bct/faresandpasses.htm
or call customer service: 954.357.8400.

Reading A Timetable - It's Easy

1. The map shows the exact bus route.
2. Major route intersections are called time points. Time points are shown with the symbol □ .
3. The timetable lists major time points for bus route. Listed under time points are scheduled departure times.
4. Reading from left to right, indicates the time for each bus trip.
5. The bus picks up and drops off riders at all BCT bus stop signs along the route where there is a Broward County bus stop sign.
6. Arrive at the bus stop five minutes early. Buses operate as close to published timetables as traffic conditions allow.

Information: 954.357.8400

**Hearing-speech impaired/TTY:
954.357.8302**

This publication can be made
available in large print, tape cassette,
or Braille, by request.



This symbol is used on
bus stop signs to indicate
accessible bus stops.



BOARD OF COUNTY COMMISSIONERS
An equal opportunity employer and provider of services.

This public document was promulgated at a cost of \$1,062 or \$.028
per copy, to inform the public about the Transportation Division's schedule
and route information. 09/08



printed on recycled paper

PROTECTIONS OF TITLE VI OF THE CIVIL RIGHTS ACT OF 1964 AS AMENDED

Any person(s) or group(s) who believes that they have been subjected to discrimination because of race, color, or national origin, under any transit program or activity provided by Broward County Transit (BCT), may call 954-357-8481 to file a Title VI discrimination complaint or write to Broward County Transportation Department, Compliance Manager, 3201 West Copans Road, Bldg. 1, Pompano Beach, Florida 33069.

TIME TABLE

ROUTE 1

Monday - Friday
Effective 10/31/10

Aventura Mall to
Broward Central Terminal
via Federal Highway/US 1



BROWARD
COUNTY
Transit
A service of the
Broward County Commission

facebook

You Tube

Download & Print at broward.org/bct
Wheelchair Accessible
Bike Racks

Customer Service

Monday - Friday.....7 am - 8 pm
Saturday, Sunday and Holidays.....8:30 am - 5 pm

Transit Operations Agents help with:

- Trip planning
- Identifying Bus Pass sales locations
- Routes, times and transfer information
- Special event information

Lost and Found: 954-357-6414, Monday - Friday,
8:30 am - 4:30 pm

Holiday Bus Service

Sunday bus service is provided on the following observed holidays:

New Year's Day	Labor Day	Memorial Day
Independence Day	Thanksgiving Day	Christmas Day

Fares

Exact fare, dollar bill or coins required. Operators do not carry change.

Fares are: Regular, Premium Express, Senior/Youth/Disabled/Medicare.* Children (under 40 inches ride FREE)

Fare Deals

All Day Bus Pass offers unlimited rides on all routes. On sale aboard all BCT buses.

NOTE: Other cost saving passes cannot be purchased on BCT buses, but are available at the Central Bus Terminal and at authorized distributors.

10 Ride Pass: 10 Rides any time, any day. Expires after the tenth ride is taken.

7 Day Pass: Unlimited rides for seven consecutive days. Starts on the first day card is used. Expires after the seventh day.

31 Day Adult Pass: Unlimited rides for 31 consecutive days. Starts on the first day card is used.

31 Day Reduced Pass: Youth*, Seniors*, Disabled*, Medicare*, College Student*. Unlimited rides for 31 consecutive days. Starts on the first day card is used.

****Premium Express 10 Ride Pass:** 10 rides any time, any day. Expires after tenth ride is taken.

****Premium Express 31 Day Pass:** Unlimited rides for 31 consecutive days. Starts on the first day card is used.

Bus Passes are not redeemable, refundable or transferrable. Damaged cards are invalid. Lost, stolen or damaged cards will not be replaced.

*NOTICE: Proof of age is required for Youth fare (18 years or younger) and for Senior fare (65 years or older). For College Student Bus Pass, a college photo ID card is required. For Disabled and Medicare fare, proof of disability (Medicare card) and photo I.D. is required. Eligible Senior fare patrons are encouraged to acquire their BCT Reduced Fare Photo ID cards.

** Premium Bus Pass can be purchased online at broward.org/bct and at select Broward County library locations.

MONDAY-FRIDAY

NORTHBOUND

To Broward Central Terminal

AVENTURA MALL	HALLANDALE BEACH BLVD.	YOUNG CIRCLE/PUBLIX	SHERIDAN STREET	FORT LAUDERDALE/ HOLLYWOOD AIRPORT	S.E. 17 STREET	BROWARD CENTRAL TERMINAL
1	2	3	4	5	6	7
		5:05a	5:12a	5:22a	5:31a	5:39a
		5:20a	5:27a	5:37a	5:46a	5:54a
		5:35a	5:42a	5:52a	6:01a	6:10a
5:30a	5:40a	5:53a	6:00a	6:11a	6:21a	6:30a
5:45a	5:55a	6:08a	6:15a	6:26a	6:36a	6:45a
6:00a	6:11a	6:23a	6:30a	6:41a	6:51a	7:00a
6:15a	6:26a	6:38a	6:45a	6:56a	7:07a	7:17a
6:30a	6:41a	6:53a	7:00a	7:12a	7:23a	7:33a
6:45a	6:56a	7:08a	7:16a	7:28a	7:39a	7:49a
7:00a	7:12a	7:24a	7:32a	7:44a	7:55a	8:06a
7:15a	7:27a	7:39a	7:47a	7:59a	8:11a	8:22a
7:30a	7:42a	7:54a	8:02a	8:15a	8:27a	8:38a
7:45a	7:57a	8:09a	8:18a	8:31a	8:43a	8:54a
8:00a	8:13a	8:25a	8:34a	8:47a	8:59a	9:09a
8:15a	8:28a	8:40a	8:49a	9:02a	9:13a	9:23a
8:30a	8:43a	8:55a	9:04a	9:16a	9:27a	9:37a
8:45a	8:58a	9:10a	9:18a	9:30a	9:41a	9:51a
9:00a	9:12a	9:24a	9:32a	9:44a	9:55a	10:05a
9:15a	9:27a	9:39a	9:47a	9:59a	10:10a	10:20a
9:30a	9:42a	9:54a	10:02a	10:14a	10:25a	10:35a
9:45a	9:57a	10:09a	10:17a	10:29a	10:40a	10:50a
10:00a	10:12a	10:24a	10:32a	10:44a	10:55a	11:05a
10:15a	10:27a	10:39a	10:47a	10:59a	11:10a	11:20a
10:30a	10:42a	10:54a	11:02a	11:14a	11:25a	11:35a
10:45a	10:57a	11:09a	11:17a	11:29a	11:40a	11:50a
11:00a	11:12a	11:24a	11:32a	11:44a	11:55a	12:05p
11:15a	11:27a	11:39a	11:47a	11:59a	12:10p	12:20p
11:30a	11:42a	11:54a	12:02p	12:14p	12:25p	12:35p
11:45a	11:57a	12:09p	12:17p	12:29p	12:40p	12:50p
12:00p	12:12p	12:24p	12:32p	12:44p	12:55p	1:05p
12:15p	12:27p	12:39p	12:47p	12:59p	1:10p	1:20p
12:30p	12:42p	12:54p	1:02p	1:14p	1:25p	1:35p
12:45p	12:57p	1:09p	1:17p	1:29p	1:40p	1:50p
1:00p	1:12p	1:24p	1:32p	1:44p	1:55p	2:05p

Continued on next page

SOUTHBOUND

To Aventura Mall

BROWARD CENTRAL TERMINAL	S.E. 17 STREET	FORT LAUDERDALE/ HOLLYWOOD AIRPORT	SHERIDAN STREET	YOUNG CIRCLE/PUBLIX	HALLANDALE BEACH BLVD.	AVENTURA MALL
7	6	5	4	3	2	1
5:15a	5:23a	5:30a	5:42a	5:56a	6:04a	6:15a
5:30a	5:38a	5:45a	5:57a	6:10a	6:19a	6:30a
5:45a	5:53a	6:00a	6:13a	6:25a	6:34a	6:45a
6:00a	6:09a	6:16a	6:29a	6:40a	6:49a	7:00a
6:15a	6:24a	6:31a	6:44a	6:55a	7:04a	7:16a
6:30a	6:39a	6:46a	6:59a	7:10a	7:20a	7:32a
6:45a	6:54a	7:01a	7:15a	7:26a	7:36a	7:48a
7:00a	7:10a	7:18a	7:32a	7:43a	7:53a	8:05a
7:15a	7:25a	7:33a	7:47a	7:58a	8:09a	8:22a
7:30a	7:40a	7:48a	8:02a	8:13a	8:24a	8:37a
7:45a	7:55a	8:03a	8:18a	8:29a	8:40a	8:53a
8:00a	8:11a	8:20a	8:35a	8:46a	8:57a	9:09a
8:15a	8:26a	8:35a	8:50a	9:01a	9:11a	9:23a
8:30a	8:41a	8:50a	9:05a	9:16a	9:26a	9:38a
8:45a	8:56a	9:04a	9:18a	9:29a	9:39a	9:51a
9:00a	9:10a	9:18a	9:32a	9:43a	9:53a	10:05a
9:15a	9:25a	9:33a	9:47a	9:58a	10:08a	10:20a
9:30a	9:40a	9:48a	10:02a	10:13a	10:23a	10:35a
9:45a	9:55a	10:03a	10:17a	10:28a	10:38a	10:50a
10:00a	10:10a	10:18a	10:32a	10:43a	10:53a	11:05a
10:15a	10:25a	10:33a	10:47a	10:58a	11:08a	11:20a
10:30a	10:40a	10:48a	11:02a	11:13a	11:23a	11:35a
10:45a	10:55a	11:03a	11:17a	11:28a	11:38a	11:50a
11:00a	11:10a	11:18a	11:32a	11:43a	11:53a	12:05p
11:15a	11:25a	11:33a	11:47a	11:58a	12:08p	12:20p
11:30a	11:40a	11:48a	12:02p	12:13p	12:23p	12:35p
11:45a	11:55a	12:03p	12:17p	12:28p	12:38p	12:50p
12:00p	12:10p	12:18p	12:32p	12:43p	12:53p	1:05p
12:15p	12:25p	12:33p	12:47p	12:58p	1:08p	1:20p
12:30p	12:40p	12:48p	1:02p	1:13p	1:23p	1:35p
12:45p	12:55p	1:03p	1:17p	1:28p	1:38p	1:50p
1:00p	1:10p	1:18p	1:32p	1:43p	1:53p	2:05p
1:15p	1:25p	1:33p	1:47p	1:58p	2:08p	2:20p
1:30p	1:40p	1:48p	2:02p	2:13p	2:23p	2:35p
1:45p	1:55p	2:03p	2:17p	2:28p	2:38p	2:50p
2:00p	2:10p	2:18p	2:32p	2:43p	2:53p	3:05p
2:15p	2:25p	2:33p	2:47p	2:58p	3:08p	3:20p

Continued on next page

NUMBERS IN BOXES REFER TO TIME POINTS ON MAP
Times with the letter "G" before them indicate bus
returns to garage.

MONDAY-FRIDAY

NORTHBOUND

To Broward Central Terminal

SOUTHBOUND

To Aventura Mall

AVENTURA MALL	HALLANDALE BEACH BLVD.	YOUNG CIRCLE/PUBLIX	SHERIDAN STREET	FORT LAUDERDALE/ HOLLYWOOD AIRPORT	S.E. 17 STREET	BROWARD CENTRAL TERMINAL
1	2	3	4	5	6	7
1:15p	1:27p	1:39p	1:47p	1:59p	2:10p	2:20p
1:30p	1:42p	1:54p	2:02p	2:14p	2:25p	2:35p
1:45p	1:57p	2:09p	2:17p	2:29p	2:40p	2:50p
2:00p	2:12p	2:24p	2:32p	2:44p	2:55p	3:05p
2:15p	2:27p	2:39p	2:47p	2:59p	3:10p	3:20p
2:30p	2:42p	2:54p	3:02p	3:14p	3:25p	3:35p
2:45p	2:57p	3:09p	3:17p	3:29p	3:40p	3:50p
3:00p	3:12p	3:24p	3:32p	3:44p	3:55p	4:06p
3:15p	3:27p	3:39p	3:47p	3:59p	4:11p	4:22p
3:30p	3:42p	3:54p	4:02p	4:15p	4:27p	4:38p
3:45p	3:57p	4:09p	4:18p	4:31p	4:43p	4:54p
4:00p	4:13p	4:25p	4:34p	4:47p	4:59p	5:10p
4:15p	4:28p	4:40p	4:49p	5:02p	5:14p	5:25p
4:30p	4:43p	4:55p	5:04p	5:17p	5:29p	5:40p
4:45p	4:58p	5:10p	5:19p	5:32p	5:44p	5:55p
5:00p	5:13p	5:25p	5:34p	5:47p	5:59p	6:10p
5:30p	5:43p	5:55p	6:04p	6:16p	6:27p	6:37p
5:15p	5:28p	5:40p	5:49p	6:02p	6:14p	G6:25p
5:45p	5:58p	6:10p	6:18p	6:30p	6:40p	G6:50p
6:00p	6:12p	6:24p	6:32p	6:44p	6:55p	7:05p
6:30p	6:42p	6:54p	7:02p	7:14p	7:25p	7:35p
7:00p	7:12p	7:24p	7:32p	7:44p	7:55p	8:05p
7:30p	7:42p	7:54p	8:02p	8:13p	8:23p	8:32p
8:00p	8:11p	8:23p	8:30p	8:41p	8:51p	9:00p
8:30p	8:41p	8:53p	9:00p	9:11p	9:21p	9:30p
9:00p	9:11p	9:23p	9:30p	9:41p	9:51p	10:00p
9:30p	9:41p	9:53p	10:00p	10:10p	10:19p	10:27p
10:00p	10:10p	10:21p	10:28p	10:38p	10:47p	10:55p
10:30p	10:40p	10:51p	10:58p	11:08p	11:17p	G11:25p
11:00p	11:10p	11:21p	11:28p	11:38p	11:47p	G11:55p

BROWARD CENTRAL TERMINAL	S.E. 17 STREET	FORT LAUDERDALE/ HOLLYWOOD AIRPORT	SHERIDAN STREET	YOUNG CIRCLE/PUBLIX	HALLANDALE BEACH BLVD.	AVENTURA MALL
7	6	5	4	3	2	1
2:30p	2:40p	2:48p	3:02p	3:13p	3:23p	3:35p
2:45p	2:55p	3:03p	3:17p	3:28p	3:38p	3:50p
3:00p	3:10p	3:18p	3:32p	3:43p	3:53p	4:05p
3:15p	3:25p	3:33p	3:47p	3:58p	4:09p	4:22p
3:30p	3:40p	3:48p	4:02p	4:13p	4:24p	4:37p
3:45p	3:55p	4:03p	4:18p	4:29p	4:40p	4:53p
4:00p	4:11p	4:20p	4:35p	4:46p	4:57p	5:10p
4:15p	4:26p	4:35p	4:50p	5:01p	5:12p	5:25p
4:30p	4:41p	4:50p	5:05p	5:16p	5:27p	5:40p
4:45p	4:56p	5:05p	5:20p	5:31p	5:42p	5:55p
5:00p	5:11p	5:20p	5:35p	5:46p	5:57p	G6:10p
5:15p	5:26p	5:35p	5:50p	6:01p	6:12p	6:25p
5:30p	5:41p	5:50p	6:05p	6:16p	6:27p	G6:40p
5:45p	5:56p	6:04p	6:18p	6:29p	6:39p	6:51p
6:00p	6:10p	6:18p	6:32p	6:43p	6:53p	G7:05p
6:15p	6:25p	6:33p	6:47p	6:58p	7:08p	7:20p
6:45p	6:55p	7:03p	7:17p	7:28p	7:38p	7:50p
7:15p	7:25p	7:33p	7:47p	7:58p	8:07p	8:18p
7:45p	7:55p	8:03p	8:16p	8:27p	8:36p	8:47p
8:15p	8:24p	8:31p	8:44p	8:55p	9:04p	9:15p
8:45p	8:54p	9:01p	9:14p	9:25p	9:34p	9:45p
9:15p	9:24p	9:31p	9:44p	9:55p	10:04p	10:14p
9:45p	9:54p	10:01p	10:13p	10:23p	10:31p	10:41p
10:15p	10:23p	10:30p	10:42p	10:52p	11:00p	G11:10p
10:45p	10:53p	11:00p	11:12p	11:22p	G11:30p	
11:15p	11:23p	11:30p	11:42p	11:52p	G12:00a	




TRANSIT WATCH

WHEN IT COMES TO OUR SAFETY,
WE CAN ALWAYS USE AN EXTRA PAIR OF
EYES AND EARS.
BE ALERT.
CALL 954-357-LOOK (5665).
TELL US.

ROUTE 1

Aventura Mall to
Broward Central Terminal
via Federal Highway/US 1



For more details on our fares please
visit our web site at
broward.org/bct or call
customer service: 954.357.8400.

Reading A Timetable - It's Easy

1. The map shows the exact bus route.
2. Major route intersections are called time points. Time points are shown with the symbol □.
3. The timetable lists major time points for bus route. Listed under time points are scheduled departure times.
4. Reading from left to right, indicates the time for each bus trip.
5. The bus picks up and drops off riders at all BCT bus stop signs along the route where there is a Broward County bus stop sign.
6. Arrive at the bus stop five minutes early. Buses operate as close to published timetables as traffic conditions allow.

**Not paying your fare is a crime per
Florida Statute 812.015.
Violation constitutes a misdemeanor,
punishable by jail time and/or a fine.**

Information: 954.357.8400

Hearing-speech impaired/TTY:
954.357.8302

This publication can be made
available in large print, tape cassette,
or Braille, by request.



This symbol is used on bus stop signs
to indicate accessible bus stops.



BROWARD COUNTY
BOARD OF COUNTY COMMISSIONERS
An equal opportunity employer and provider of services.

TRANSFER POLICY 7/10/11

TRANSFERS BETWEEN REGULAR BUS ROUTE SERVICE AND PREMIUM 95 EXPRESS BUS SERVICE

A BCT 31-Day Premium 95 Express Bus Pass is acceptable on all BCT regular bus service. Passengers transferring from regular route bus service to express bus service with an All Day, 7-Day or 31-Day bus pass, must pay a premium upgrade fee of \$1.00. Passengers with a regular 10-Ride bus pass or paying by cash on regular service will not be able to transfer between bus services and must pay the full premium fare when boarding the 95 Express bus.

TRANSFERS FROM BCT TO OTHER SOUTH FLORIDA TRANSIT SYSTEMS

When boarding a BCT bus, passenger pays the appropriate BCT fare and may request a transfer from the bus operator if transferring to Miami-Dade Transit (MDT), Palm Tran or Tri-Rail.

TRANSFERS TO BCT FROM OTHER SOUTH FLORIDA TRANSIT SYSTEMS

When transferring from MDT, Palm Tran and Tri-Rail to BCT regular fixed-route bus service, passenger pays \$.50 with a transfer issued by MDT or Palm Tran and proof of fare payment such as Easy Card and receipt issued by Tri-Rail. Tri-Rail passengers boarding BCT at any locations other than at a Tri-Rail station will be required to pay the full fare.

TRANSFERS BETWEEN OTHER SOUTH FLORIDA TRANSIT SYS- TEMS AND PREMIUM 95 EXPRESS BUS SERVICE

Transfers to MDT or Tri-Rail from 95 Express, a transfer is issued and passenger must pay appropriate MDT or Tri-Rail fare.

Transfer from MDT or Tri-Rail to 95 Express, a \$.50 transfer fee is required with the appropriate transfer from MDT or Tri-Rail.

The 95 Express does not connect with Palm Tran.

The Easy Card issued by MDT and Tri-Rail is not accepted as payment on any BCT bus.

PROTECTIONS OF TITLE VI OF THE CIVIL RIGHTS ACT OF 1964 AS AMENDED

Any person(s) or group(s) who believes that they have been subjected to discrimination because of race, color, or national origin, under any transit program or activity provided by Broward County Transit (BCT), may call 954-357-8481 to file a Title VI discrimination complaint or write to Broward County Transit Division, Compliance Manager, 3201 West Copans Road, Pompano Beach, Florida 33069.

TIME TABLE

ROUTE *U.S. 1* *Breeze*

Monday - Friday Limited Service

Aventura Mall to Sample Road
and U.S. 1

via U.S. 1

Effective 10/07/07

BROWARD
COUNTY
Transit
A service of the
Broward County Commission

facebook

You Tube

Download & Print at broward.org/bct
Wheelchair Accessible
Bike Racks

Customer Service

Monday - Friday.....7 am - 8 pm
Saturday, Sunday and Holidays.....8:30 am - 5 pm

Transit Operations Agents help with:

- Trip planning
- Routes, times and transfer information
- Identifying Bus Pass sales locations
- Special event information

Lost and Found: 954-357-6414, Monday - Friday,
8:30 am - 4:30 pm

Holiday Bus Service

Sunday bus service is provided on the following observed holidays:

New Year's Day	Labor Day	Memorial Day
Independence Day	Thanksgiving Day	Christmas Day

Fares

Exact fare, dollar bill or coins required. Operators do not carry change.

Fares are: Regular, Premium Express, Senior/Youth/Disabled/Medicare.* Children (under 40 inches ride FREE)

Fare Deals

All Day Bus Pass offers unlimited rides on all routes. On sale aboard all BCT buses.

NOTE: Other cost saving passes cannot be purchased on BCT buses, but are available at the Central Bus Terminal and at authorized distributors.

10 Ride Pass: 10 Rides any time, any day. Expires after the tenth ride is taken.

7 Day Pass: Unlimited rides for seven consecutive days. Starts on the first day card is used. Expires after the seventh day.

31 Day Adult Pass: Unlimited rides for 31 consecutive days. Starts on the first day card is used.

31 Day Reduced Pass: Youth*, Seniors*, Disabled*, Medicare*, College Student*. Unlimited rides for 31 consecutive days. Starts on the first day card is used.

****Premium Express 10 Ride Pass:** 10 rides any time, any day. Expires after tenth ride is taken.

****Premium Express 31 Day Pass:** Unlimited rides for 31 consecutive days. Starts on the first day card is used.

Bus Passes are not redeemable, refundable or transferrable. Damaged cards are invalid. Lost, stolen or damaged cards will not be replaced.

*NOTICE: Proof of age is required for Youth fare (18 years or younger) and for Senior fare (65 years or older). For College Student Bus Pass, a college photo ID card is required. For Disabled and Medicare fare, proof of disability (Medicare card) and photo I.D. is required. Eligible Senior fare patrons are encouraged to acquire their BCT Reduced Fare Photo ID cards.

** Premium Bus Pass can be purchased online at broward.org/bct and at select Broward County library locations.



ROUTE US 1 Breeze

Monday - Friday Limited Service
Aventura Mall to Sample Road
via US 1

POINTS OF INTEREST

- Aventura Mall
- Coral Ridge Mall
- Pompano Citi Centre
- Shoppers Haven
- Broward General Medical Center
- BC/FAU/FIU
- Coconut Creek Casino
- Gulfstream Race Track

LEGEND



Route


U.S. 1 Breeze

Weekday Limited Service

BROWARD COUNTY TRANSIT

www.broward.org/bct

- AVENTURA MALL
- HALLANDALE BEACH BLVD.
- PEMBROKE RD.
- YOUNG CIRCLE
- SHERIDAN ST.
- DANIA BEACH BLVD.
- S.E. 17 ST./S.E. 3 AVE.
- S.E. 6 ST./ANDREWS AVE.
- BROWARD CENTRAL TERMINAL
- SUNRISE BLVD./N.E. 15 AVE.
- OAKLAND PARK BLVD.
- COMMERCIAL BLVD.
- N.E. 62 ST.
- ATLANTIC BLVD.
- COPANS RD.
- SAMPLE RD.



For more details on our fares please visit our
web site at
broward.org/bct/faresandpasses
or call customer service: 954.357.8400.

Information: 954.357.8400

Hearing-speech impaired/TTY: 954.357.8302

This publication can be made available in large print, tape
cassette, or Braille, by request.



This symbol is used on bus stop signs to indicate
accessible bus stops.



BROWARD COUNTY
BOARD OF COUNTY COMMISSIONERS
An equal opportunity employer and provider of services.



printed on recycled paper

PROTECTIONS OF TITLE VI OF THE CIVIL RIGHTS ACT OF 1964 AS AMENDED

Any person(s) or group(s) who believes that they have
been subjected to discrimination because of race, color,
or national origin, under any transit program or activity
provided by Broward County Transit (BCT), may call
954-357-8481 to file a Title VI discrimination complaint
or write to Broward County Office of Transportation,
Compliance Manager, 3201 West Copans Road, Bldg.
1, Pompano Beach, Florida 33069.

APPENDIX - B

Traffic Data



Seasonal factors.txt

2009 Peak Season Factor Category Report - Report Type: ALL
 Category: 8600 EAST-A1A TO US1

Week	Dates	SF	MOCF: 0.90 PSCF
1	01/01/2009 - 01/03/2009	0.97	1.08
2	01/04/2009 - 01/10/2009	0.95	1.06
3	01/11/2009 - 01/17/2009	0.93	1.04
* 4	01/18/2009 - 01/24/2009	0.92	1.02
* 5	01/25/2009 - 01/31/2009	0.91	1.01
* 6	02/01/2009 - 02/07/2009	0.90	1.00
* 7	02/08/2009 - 02/14/2009	0.89	0.99
* 8	02/15/2009 - 02/21/2009	0.88	0.98
* 9	02/22/2009 - 02/28/2009	0.88	0.98
*10	03/01/2009 - 03/07/2009	0.88	0.98
*11	03/08/2009 - 03/14/2009	0.89	0.99
*12	03/15/2009 - 03/21/2009	0.89	0.99
*13	03/22/2009 - 03/28/2009	0.90	1.00
*14	03/29/2009 - 04/04/2009	0.90	1.00
*15	04/05/2009 - 04/11/2009	0.91	1.01
*16	04/12/2009 - 04/18/2009	0.92	1.02
17	04/19/2009 - 04/25/2009	0.95	1.06
18	04/26/2009 - 05/02/2009	0.99	1.10
19	05/03/2009 - 05/09/2009	1.02	1.14
20	05/10/2009 - 05/16/2009	1.05	1.17
21	05/17/2009 - 05/23/2009	1.06	1.18
22	05/24/2009 - 05/30/2009	1.06	1.18
23	05/31/2009 - 06/06/2009	1.07	1.19
24	06/07/2009 - 06/13/2009	1.08	1.20
25	06/14/2009 - 06/20/2009	1.09	1.21
26	06/21/2009 - 06/27/2009	1.08	1.20
27	06/28/2009 - 07/04/2009	1.08	1.20
28	07/05/2009 - 07/11/2009	1.08	1.20
29	07/12/2009 - 07/18/2009	1.08	1.20
30	07/19/2009 - 07/25/2009	1.08	1.20
31	07/26/2009 - 08/01/2009	1.08	1.20
32	08/02/2009 - 08/08/2009	1.08	1.20
33	08/09/2009 - 08/15/2009	1.09	1.21
34	08/16/2009 - 08/22/2009	1.10	1.23
35	08/23/2009 - 08/29/2009	1.11	1.24
36	08/30/2009 - 09/05/2009	1.12	1.25
37	09/06/2009 - 09/12/2009	1.13	1.26
38	09/13/2009 - 09/19/2009	1.14	1.27
39	09/20/2009 - 09/26/2009	1.13	1.26
40	09/27/2009 - 10/03/2009	1.11	1.24
41	10/04/2009 - 10/10/2009	1.09	1.21
42	10/11/2009 - 10/17/2009	1.07	1.19
43	10/18/2009 - 10/24/2009	1.06	1.18
44	10/25/2009 - 10/31/2009	1.05	1.17
45	11/01/2009 - 11/07/2009	1.03	1.15
46	11/08/2009 - 11/14/2009	1.02	1.14
47	11/15/2009 - 11/21/2009	1.01	1.13
48	11/22/2009 - 11/28/2009	1.00	1.11
49	11/29/2009 - 12/05/2009	0.99	1.10
50	12/06/2009 - 12/12/2009	0.98	1.09
51	12/13/2009 - 12/19/2009	0.97	1.08
52	12/20/2009 - 12/26/2009	0.95	1.06
53	12/27/2009 - 12/31/2009	0.93	1.04

* Peak Season

Page 1 of 7

2009 Peak Season Factor Category Report - Report Type: ALL
 Category: 8601 CEN. -W OF US1 TO SR7

Week	Dates	SF	MOCF: 0.96 PSCF
1	01/01/2009 - 01/03/2009	0.99	1.03
2	01/04/2009 - 01/10/2009	0.99	1.03
3	01/11/2009 - 01/17/2009	0.98	1.02

KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & US-1
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : hal-us1
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 1

Groups Printed- All Traffic

	US-1 SB			Hallandale Beach Blvd WB			US-1 NB			Hallandale Beach Blvd EB			
Start Time	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Int. Total
07:00 AM	7	70	24	14	185	47	38	76	24	35	88	5	613
07:15 AM	13	109	33	18	189	91	48	61	38	24	108	20	752
07:30 AM	12	144	33	27	209	65	85	72	32	57	164	15	915
07:45 AM	7	193	30	15	173	81	68	116	61	59	177	26	1006
Total	39	516	120	74	756	284	239	325	155	175	537	66	3286
08:00 AM	14	223	39	21	194	76	68	107	65	106	227	22	1162
08:15 AM	26	201	34	20	304	137	64	127	68	74	179	30	1264
08:30 AM	13	287	64	19	205	125	76	122	69	64	204	24	1272
08:45 AM	19	212	63	27	270	112	81	142	52	98	254	19	1349
Total	72	923	200	87	973	450	289	498	254	342	864	95	5047
*** BREAK ***													
04:00 PM	48	193	104	39	273	146	114	250	99	72	212	25	1575
04:15 PM	14	183	69	33	248	118	140	262	125	66	199	27	1484
04:30 PM	27	206	80	45	285	127	123	231	107	63	226	42	1562
04:45 PM	23	194	84	48	229	128	126	215	85	82	196	83	1493
Total	112	776	337	165	1035	519	503	958	416	283	833	177	6114
05:00 PM	32	202	62	40	353	134	141	320	141	63	174	65	1727
05:15 PM	26	224	63	28	305	139	103	238	136	82	183	45	1572
05:30 PM	25	166	80	29	234	132	144	290	98	94	238	33	1563
05:45 PM	16	222	87	43	231	117	133	268	124	86	213	28	1568
Total	99	814	292	140	1123	522	521	1116	499	325	808	171	6430
Grand Total	322	3029	949	466	3887	1775	1552	2897	1324	1125	3042	509	20877
Apprch %	7.5	70.4	22.1	7.6	63.4	29	26.9	50.2	22.9	24.1	65.1	10.9	
Total %	1.5	14.5	4.5	2.2	18.6	8.5	7.4	13.9	6.3	5.4	14.6	2.4	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & US-1
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : hal-us1
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 2

	US-1 SB				Hallandale Beach Blvd WB				US-1 NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 08:00 AM																	
08:00 AM	14	223	39	276	21	194	76	291	68	107	65	240	106	227	22	355	1162
08:15 AM	26	201	34	261	20	304	137	461	64	127	68	259	74	179	30	283	1264
08:30 AM	13	287	64	364	19	205	125	349	76	122	69	267	64	204	24	292	1272
08:45 AM	19	212	63	294	27	270	112	409	81	142	52	275	98	254	19	371	1349
Total Volume	72	923	200	1195	87	973	450	1510	289	498	254	1041	342	864	95	1301	5047
% App. Total	6	77.2	16.7		5.8	64.4	29.8		27.8	47.8	24.4		26.3	66.4	7.3		
PHF	.692	.804	.781	.821	.806	.800	.821	.819	.892	.877	.920	.946	.807	.850	.792	.877	.935



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & US-1
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : hal-us1
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 3

	US-1 SB				Hallandale Beach Blvd WB				US-1 NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 05:00 PM																	
05:00 PM	32	202	62	296	40	353	134	527	141	320	141	602	63	174	65	302	1727
05:15 PM	26	224	63	313	28	305	139	472	103	238	136	477	82	183	45	310	1572
05:30 PM	25	166	80	271	29	234	132	395	144	290	98	532	94	238	33	365	1563
05:45 PM	16	222	87	325	43	231	117	391	133	268	124	525	86	213	28	327	1568
Total Volume	99	814	292	1205	140	1123	522	1785	521	1116	499	2136	325	808	171	1304	6430
% App. Total	8.2	67.6	24.2		7.8	62.9	29.2		24.4	52.2	23.4		24.9	62	13.1		
PHF	.773	.908	.839	.927	.814	.795	.939	.847	.905	.872	.885	.887	.864	.849	.658	.893	.931



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & S Ocean Dr
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-OCE
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 1

Groups Printed- All Traffic

	S Ocean Dr SB			Hallandale Beach Blvd WB			S Ocean Dr NB			Hallandale Beach Blvd EB			
Start Time	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Int. Total
07:00 AM	67	38	4	2	54	2	1	41	5	39	14	56	323
07:15 AM	66	46	3	1	28	1	0	58	1	65	18	48	335
07:30 AM	76	56	1	1	33	3	1	76	0	103	20	79	449
07:45 AM	84	69	1	2	32	2	0	84	4	112	10	105	505
Total	293	209	9	6	147	8	2	259	10	319	62	288	1612
08:00 AM	87	116	1	1	34	1	1	89	3	112	8	72	525
08:15 AM	84	105	4	1	33	2	1	89	3	110	10	100	542
08:30 AM	36	39	0	2	36	1	0	87	2	160	4	79	446
08:45 AM	0	0	0	1	41	1	3	87	8	174	8	107	430
Total	207	260	5	5	144	5	5	352	16	556	30	358	1943
*** BREAK ***													
04:00 PM	91	91	0	5	21	5	0	123	5	194	26	113	674
04:15 PM	83	92	1	2	15	4	0	132	4	180	12	146	671
04:30 PM	79	109	1	8	16	8	0	152	11	157	21	153	715
04:45 PM	84	101	2	6	18	3	0	137	11	185	14	123	684
Total	337	393	4	21	70	20	0	544	31	716	73	535	2744
05:00 PM	100	128	1	11	17	4	1	136	5	179	16	124	722
05:15 PM	136	150	4	4	19	3	2	147	1	206	15	126	813
05:30 PM	142	181	4	4	17	1	1	148	7	157	20	142	824
05:45 PM	135	133	5	6	21	2	1	115	5	188	19	143	773
Total	513	592	14	25	74	10	5	546	18	730	70	535	3132
Grand Total	1350	1454	32	57	435	43	12	1701	75	2321	235	1716	9431
Apprch %	47.6	51.3	1.1	10.7	81.3	8	0.7	95.1	4.2	54.3	5.5	40.2	
Total %	14.3	15.4	0.3	0.6	4.6	0.5	0.1	18	0.8	24.6	2.5	18.2	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & S Ocean Dr
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-OCE
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 2

	S Ocean Dr SB				Hallandale Beach Blvd WB				S Ocean Dr NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 07:30 AM																	
07:30 AM	76	56	1	133	1	33	3	37	1	76	0	77	103	20	79	202	449
07:45 AM	84	69	1	154	2	32	2	36	0	84	4	88	112	10	105	227	505
08:00 AM	87	116	1	204	1	34	1	36	1	89	3	93	112	8	72	192	525
08:15 AM	84	105	4	193	1	33	2	36	1	89	3	93	110	10	100	220	542
Total Volume	331	346	7	684	5	132	8	145	3	338	10	351	437	48	356	841	2021
% App. Total	48.4	50.6	1		3.4	91	5.5		0.9	96.3	2.8		52	5.7	42.3		
PHF	.951	.746	.438	.838	.625	.971	.667	.980	.750	.949	.625	.944	.975	.600	.848	.926	.932



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971)

Turning Movement - All Traffic
Hallandale Beach Blvd & S Ocean Dr
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-OCE
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 3

	S Ocean Dr SB				Hallandale Beach Blvd WB				S Ocean Dr NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 05:00 PM																	
05:00 PM	100	128	1	229	11	17	4	32	1	136	5	142	179	16	124	319	722
05:15 PM	136	150	4	290	4	19	3	26	2	147	1	150	206	15	126	347	813
05:30 PM	142	181	4	327	4	17	1	22	1	148	7	156	157	20	142	319	824
05:45 PM	135	133	5	273	6	21	2	29	1	115	5	121	188	19	143	350	773
Total Volume	513	592	14	1119	25	74	10	109	5	546	18	569	730	70	535	1335	3132
% App. Total	45.8	52.9	1.3		22.9	67.9	9.2		0.9	96	3.2		54.7	5.2	40.1		
PHF	.903	.818	.700	.856	.568	.881	.625	.852	.625	.922	.643	.912	.886	.875	.935	.954	.950



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & Layne Blvd
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-LAY
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 1

Groups Printed- All Traffic

	Layne Blvd SB			Hallandale Beach Blvd WB			Layne Blvd NB			Hallandale Beach Blvd EB			
Start Time	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Int. Total
07:00 AM	1	0	2	2	209	0	6	1	7	5	136	2	371
07:15 AM	4	0	0	1	231	2	5	0	4	8	181	4	440
07:30 AM	8	1	5	4	225	2	3	0	12	10	201	9	480
07:45 AM	8	0	3	2	239	7	5	2	19	11	213	2	511
Total	21	1	10	9	904	11	19	3	42	34	731	17	1802
08:00 AM	12	1	3	4	300	5	5	2	14	19	177	6	548
08:15 AM	9	0	2	3	284	3	14	3	22	12	175	5	532
08:30 AM	12	1	6	5	323	6	11	1	18	10	253	15	661
08:45 AM	9	2	6	7	292	9	11	6	27	16	264	15	664
Total	42	4	17	19	1199	23	41	12	81	57	869	41	2405

*** BREAK ***

04:00 PM	10	2	14	5	297	11	6	2	35	10	254	20	666
04:15 PM	15	3	19	3	264	6	10	2	29	5	359	22	737
04:30 PM	12	0	16	6	331	11	13	6	25	3	344	23	790
04:45 PM	18	1	13	5	292	1	12	4	25	3	262	14	650
Total	55	6	62	19	1184	29	41	14	114	21	1219	79	2843
05:00 PM	23	4	21	5	321	6	13	2	36	8	307	14	760
05:15 PM	8	2	14	7	292	5	13	5	30	14	293	30	713
05:30 PM	15	4	18	7	305	5	8	2	21	8	345	19	757
05:45 PM	13	0	14	7	270	4	14	3	21	10	376	19	751
Total	59	10	67	26	1188	20	48	12	108	40	1321	82	2981
Grand Total	177	21	156	73	4475	83	149	41	345	152	4140	219	10031
Apprch %	50	5.9	44.1	1.6	96.6	1.8	27.9	7.7	64.5	3.4	91.8	4.9	
Total %	1.8	0.2	1.6	0.7	44.6	0.8	1.5	0.4	3.4	1.5	41.3	2.2	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & Layne Blvd
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-LAY
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 2

	Layne Blvd SB				Hallandale Beach Blvd WB				Layne Blvd NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 08:00 AM																	
08:00 AM	12	1	3	16	4	300	5	309	5	2	14	21	19	177	6	202	548
08:15 AM	9	0	2	11	3	284	3	290	14	3	22	39	12	175	5	192	532
08:30 AM	12	1	6	19	5	323	6	334	11	1	18	30	10	253	15	278	661
08:45 AM	9	2	6	17	7	292	9	308	11	6	27	44	16	264	15	295	664
Total Volume	42	4	17	63	19	1199	23	1241	41	12	81	134	57	869	41	967	2405
% App. Total	66.7	6.3	27		1.5	96.6	1.9		30.6	9	60.4		5.9	89.9	4.2		
PHF	.875	.500	.708	.829	.679	.928	.639	.929	.732	.500	.750	.761	.750	.823	.683	.819	.905



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971)

Turning Movement - All Traffic
Hallandale Beach Blvd & Layne Blvd
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-LAY
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 3

	Layne Blvd SB				Hallandale Beach Blvd WB				Layne Blvd NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 05:00 PM																	
05:00 PM	23	4	21	48	5	321	6	332	13	2	36	51	8	307	14	329	760
05:15 PM	8	2	14	24	7	292	5	304	13	5	30	48	14	293	30	337	713
05:30 PM	15	4	18	37	7	305	5	317	8	2	21	31	8	345	19	372	757
05:45 PM	13	0	14	27	7	270	4	281	14	3	21	38	10	376	19	405	751
Total Volume	59	10	67	136	26	1188	20	1234	48	12	108	168	40	1321	82	1443	2981
% App. Total	43.4	7.4	49.3		2.1	96.3	1.6		28.6	7.1	64.3		2.8	91.5	5.7		
PHF	.641	.625	.798	.708	.929	.925	.833	.929	.857	.600	.750	.824	.714	.878	.683	.891	.981



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Manual Turning Movement - All Traffic
Hallandale Beach Blvd & Golden Isles Dr
Hallandale Beach, FL
Locatin counted: July 13, 2011

File Name : HAL-GOLD
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 1

Groups Printed- All Traffic

	Golden Isles Dr SB			Hallandale Beach Blvd WB			Golden Isles Dr NB			Hallandale Beach Blvd EB			
Start Time	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Int. Total
07:00 AM	4	0	0	5	212	1	4	2	13	1	113	0	355
07:15 AM	1	0	3	6	180	0	4	0	19	10	162	0	385
07:30 AM	6	0	2	2	239	4	6	4	20	4	204	0	491
07:45 AM	3	0	2	4	228	5	9	2	16	7	183	0	459
Total	14	0	7	17	859	10	23	8	68	22	662	0	1690
08:00 AM	0	1	4	2	266	5	13	2	26	10	189	0	518
08:15 AM	2	0	1	4	278	6	4	6	23	7	224	0	555
08:30 AM	0	2	1	6	245	9	7	2	27	10	190	0	499
08:45 AM	0	1	5	2	283	16	13	4	19	16	286	3	648
Total	2	4	11	14	1072	36	37	14	95	43	889	3	2220
*** BREAK ***													
04:00 PM	0	2	14	11	361	12	11	3	39	21	336	0	810
04:15 PM	2	4	9	7	350	16	9	7	31	21	317	1	774
04:30 PM	4	5	11	2	276	12	12	5	45	8	262	0	642
04:45 PM	3	2	9	11	293	22	14	3	36	23	326	0	742
Total	9	13	43	31	1280	62	46	18	151	73	1241	1	2968
05:00 PM	2	3	9	7	277	9	14	6	44	3	305	1	680
05:15 PM	1	1	12	12	366	13	8	3	21	22	341	0	800
05:30 PM	3	4	5	11	318	7	15	1	26	13	375	1	779
05:45 PM	1	3	18	12	259	11	8	5	17	31	358	0	723
Total	7	11	44	42	1220	40	45	15	108	69	1379	2	2982
Grand Total	32	28	105	104	4431	148	151	55	422	207	4171	6	9860
Apprch %	19.4	17	63.6	2.2	94.6	3.2	24	8.8	67.2	4.7	95.1	0.1	
Total %	0.3	0.3	1.1	1.1	44.9	1.5	1.5	0.6	4.3	2.1	42.3	0.1	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Manual Turning Movement - All Traffic
Hallandale Beach Blvd & Golden Isles Dr
Hallandale Beach, FL
Locatin counted: July 13, 2011

File Name : HAL-GOLD
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 2

	Golden Isles Dr SB				Hallandale Beach Blvd WB				Golden Isles Dr NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 08:00 AM																	
08:00 AM	0	1	4	5	2	266	5	273	13	2	26	41	10	189	0	199	518
08:15 AM	2	0	1	3	4	278	6	288	4	6	23	33	7	224	0	231	555
08:30 AM	0	2	1	3	6	245	9	260	7	2	27	36	10	190	0	200	499
08:45 AM	0	1	5	6	2	283	16	301	13	4	19	36	16	286	3	305	648
Total Volume	2	4	11	17	14	1072	36	1122	37	14	95	146	43	889	3	935	2220
% App. Total	11.8	23.5	64.7		1.2	95.5	3.2		25.3	9.6	65.1		4.6	95.1	0.3		
PHF	.250	.500	.550	.708	.583	.947	.563	.932	.712	.583	.880	.890	.672	.777	.250	.766	.856



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Manual Turning Movement - All Traffic
Hallandale Beach Blvd & Golden Isles Dr
Hallandale Beach, FL
Locatin counted: July 13, 2011

File Name : HAL-GOLD
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 3

	Golden Isles Dr SB				Hallandale Beach Blvd WB				Golden Isles Dr NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 04:45 PM																	
04:45 PM	3	2	9	14	11	293	22	326	14	3	36	53	23	326	0	349	742
05:00 PM	2	3	9	14	7	277	9	293	14	6	44	64	3	305	1	309	680
05:15 PM	1	1	12	14	12	366	13	391	8	3	21	32	22	341	0	363	800
05:30 PM	3	4	5	12	11	318	7	336	15	1	26	42	13	375	1	389	779
Total Volume	9	10	35	54	41	1254	51	1346	51	13	127	191	61	1347	2	1410	3001
% App. Total	16.7	18.5	64.8		3	93.2	3.8		26.7	6.8	66.5		4.3	95.5	0.1		
PHF	.750	.625	.729	.964	.854	.857	.580	.861	.850	.542	.722	.746	.663	.898	.500	.906	.938



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & Diplomat Pkwy
Hallandale Beach, FL
Location counted: July 13, 2011

File Name : HAL-DIP
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 1

Groups Printed- All Traffic

	Diplomat Pkwy SB			Hallandale Beach Blvd WB			Driveway NB			Hallandale Beach Blvd EB			
Start Time	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Int. Total
07:00 AM	6	2	1	8	190	0	1	0	1	0	115	4	328
07:15 AM	6	0	4	1	172	0	0	0	0	0	144	4	331
07:30 AM	9	2	8	6	235	2	0	1	4	1	198	12	478
07:45 AM	8	0	6	6	239	3	1	0	0	3	199	9	474
Total	29	4	19	21	836	5	2	1	5	4	656	29	1611
08:00 AM	22	4	4	5	264	1	1	0	0	4	171	2	478
08:15 AM	10	2	9	13	259	1	0	1	1	2	199	9	506
08:30 AM	9	6	9	4	289	3	1	0	4	3	177	14	519
08:45 AM	11	7	12	11	264	7	2	0	2	4	259	16	595
Total	52	19	34	33	1076	12	4	1	7	13	806	41	2098
*** BREAK ***													
04:00 PM	11	0	11	9	318	7	5	1	7	1	299	21	690
04:15 PM	18	1	7	5	283	0	3	2	11	0	318	19	667
04:30 PM	9	0	16	13	275	0	2	4	7	1	282	34	643
04:45 PM	22	0	10	5	256	1	3	2	1	0	310	15	625
Total	60	1	44	32	1132	8	13	9	26	2	1209	89	2625
05:00 PM	8	0	8	14	273	0	2	5	2	0	364	17	693
05:15 PM	12	1	22	9	326	1	4	1	1	0	356	34	767
05:30 PM	9	0	11	5	313	1	2	3	2	0	388	22	756
05:45 PM	14	0	10	7	267	1	2	0	2	0	336	15	654
Total	43	1	51	35	1179	3	10	9	7	0	1444	88	2870
Grand Total	184	25	148	121	4223	28	29	20	45	19	4115	247	9204
Apprch %	51.5	7	41.5	2.8	96.6	0.6	30.9	21.3	47.9	0.4	93.9	5.6	
Total %	2	0.3	1.6	1.3	45.9	0.3	0.3	0.2	0.5	0.2	44.7	2.7	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & Diplomat Pkwy
Hallandale Beach, FL
Location counted: July 13, 2011

File Name : HAL-DIP
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 2

	Diplomat Pkwy SB				Hallandale Beach Blvd WB				Drivewy NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 08:00 AM																	
08:00 AM	22	4	4	30	5	264	1	270	1	0	0	1	4	171	2	177	478
08:15 AM	10	2	9	21	13	259	1	273	0	1	1	2	2	199	9	210	506
08:30 AM	9	6	9	24	4	289	3	296	1	0	4	5	3	177	14	194	519
08:45 AM	11	7	12	30	11	264	7	282	2	0	2	4	4	259	16	279	595
Total Volume	52	19	34	105	33	1076	12	1121	4	1	7	12	13	806	41	860	2098
% App. Total	49.5	18.1	32.4		2.9	96	1.1		33.3	8.3	58.3		1.5	93.7	4.8		
PHF	.591	.679	.708	.875	.635	.931	.429	.947	.500	.250	.438	.600	.813	.778	.641	.771	.882



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & Diplomat Pkwy
Hallandale Beach, FL
Location counted: July 13, 2011

File Name : HAL-DIP
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 3

	Diplomat Pkwy SB				Hallandale Beach Blvd WB				Driveway NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 05:00 PM																	
05:00 PM	8	0	8	16	14	273	0	287	2	5	2	9	0	364	17	381	693
05:15 PM	12	1	22	35	9	326	1	336	4	1	1	6	0	356	34	390	767
05:30 PM	9	0	11	20	5	313	1	319	2	3	2	7	0	388	22	410	756
05:45 PM	14	0	10	24	7	267	1	275	2	0	2	4	0	336	15	351	654
Total Volume	43	1	51	95	35	1179	3	1217	10	9	7	26	0	1444	88	1532	2870
% App. Total	45.3	1.1	53.7		2.9	96.9	0.2		38.5	34.6	26.9		0	94.3	5.7		
PHF	.768	.250	.580	.679	.625	.904	.750	.906	.625	.450	.875	.722	.000	.930	.647	.934	.935



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & SE 26 Ave
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-26
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 1

Groups Printed- All Traffic

	Hallandale Beach Blvd WB		SE 26 Ave NB	Hallandale Beach Blvd EB		
Start Time	Thru	Left	Right	Right	Thru	Int. Total
07:00 AM	163	5	6	2	97	273
07:15 AM	132	5	8	1	144	290
07:30 AM	179	7	10	1	185	382
07:45 AM	190	6	10	0	175	381
Total	664	23	34	4	601	1326
08:00 AM	215	8	13	0	188	424
08:15 AM	198	9	13	1	179	400
08:30 AM	233	9	12	1	182	437
08:45 AM	247	13	10	1	243	514
Total	893	39	48	3	792	1775
*** BREAK ***						
04:00 PM	313	13	3	1	277	607
04:15 PM	283	12	8	1	256	560
04:30 PM	325	10	6	0	270	611
04:45 PM	225	14	7	4	285	535
Total	1146	49	24	6	1088	2313
05:00 PM	288	13	11	2	301	615
05:15 PM	333	14	13	0	317	677
05:30 PM	298	21	6	3	358	686
05:45 PM	251	14	13	1	320	599
Total	1170	62	43	6	1296	2577
Grand Total	3873	173	149	19	3777	7991
Apprch %	95.7	4.3	100	0.5	99.5	
Total %	48.5	2.2	1.9	0.2	47.3	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & SE 26 Ave
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-26
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 2

	Hallandale Beach Blvd WB			SE 26 Ave NB		Hallandale Beach Blvd EB			
Start Time	Thru	Left	App. Total	Right	App. Total	Right	Thru	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1									
Peak Hour for Entire Intersection Begins at 08:00 AM									
08:00 AM	215	8	223	13	13	0	188	188	424
08:15 AM	198	9	207	13	13	1	179	180	400
08:30 AM	233	9	242	12	12	1	182	183	437
08:45 AM	247	13	260	10	10	1	243	244	514
Total Volume	893	39	932	48	48	3	792	795	1775
% App. Total	95.8	4.2		100		0.4	99.6		
PHF	.904	.750	.896	.923	.923	.750	.815	.815	.863



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & SE 26 Ave
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : HAL-26
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 3

	Hallandale Beach Blvd WB			SE 26 Ave NB		Hallandale Beach Blvd EB			
Start Time	Thru	Left	App. Total	Right	App. Total	Right	Thru	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1									
Peak Hour for Entire Intersection Begins at 05:00 PM									
05:00 PM	288	13	301	11	11	2	301	303	615
05:15 PM	333	14	347	13	13	0	317	317	677
05:30 PM	298	21	319	6	6	3	358	361	686
05:45 PM	251	14	265	13	13	1	320	321	599
Total Volume	1170	62	1232	43	43	6	1296	1302	2577
% App. Total	95	5		100		0.5	99.5		
PHF	.878	.738	.888	.827	.827	.500	.905	.902	.939



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE 14 Ave
Hallandale Beach, FL
Location counted: July 14,2011

File Name : HAL-14
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 1

Groups Printed- All Traffic

	NE 14 Ave SB			Hallandale Beach Blvd WB			NE 14 Ave NB			Hallandale Beach Blvd EB			
Start Time	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	Int. Total
07:00 AM	17	4	4	3	191	1	2	2	30	22	126	3	405
07:15 AM	25	6	4	1	185	3	3	5	25	21	156	7	441
07:30 AM	22	12	13	6	235	1	0	19	37	24	179	13	561
07:45 AM	20	8	17	3	255	2	4	3	32	37	240	10	631
Total	84	30	38	13	866	7	9	29	124	104	701	33	2038
08:00 AM	28	16	26	4	265	0	3	8	38	54	213	12	667
08:15 AM	36	19	20	11	290	3	5	11	61	49	282	15	802
08:30 AM	38	17	27	7	269	2	7	17	39	31	206	22	682
08:45 AM	39	17	23	7	331	8	4	24	65	52	338	22	930
Total	141	69	96	29	1155	13	19	60	203	186	1039	71	3081
*** BREAK ***													
04:00 PM	41	27	17	17	349	15	22	38	69	64	345	38	1042
04:15 PM	25	21	21	10	290	10	16	29	67	71	382	48	990
04:30 PM	35	12	28	13	401	12	16	20	54	72	304	44	1011
04:45 PM	24	21	24	14	364	16	22	29	68	79	299	35	995
Total	125	81	90	54	1404	53	76	116	258	286	1330	165	4038
05:00 PM	30	24	16	15	441	11	9	22	63	82	354	65	1132
05:15 PM	24	21	16	16	334	13	31	33	54	59	319	78	998
05:30 PM	31	33	24	19	396	8	26	28	60	87	382	52	1146
05:45 PM	23	21	13	14	310	16	21	33	51	67	339	53	961
Total	108	99	69	64	1481	48	87	116	228	295	1394	248	4237
Grand Total	458	279	293	160	4906	121	191	321	813	871	4464	517	13394
Apprch %	44.5	27.1	28.4	3.1	94.6	2.3	14.4	24.2	61.4	14.9	76.3	8.8	
Total %	3.4	2.1	2.2	1.2	36.6	0.9	1.4	2.4	6.1	6.5	33.3	3.9	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE 14 Ave
Hallandale Beach, FL
Location counted: July 14,2011

File Name : HAL-14
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 2

	NE 14 Ave SB				Hallandale Beach Blvd WB				NE 14 Ave NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 11:45 AM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 08:00 AM																	
08:00 AM	28	16	26	70	4	265	0	269	3	8	38	49	54	213	12	279	667
08:15 AM	36	19	20	75	11	290	3	304	5	11	61	77	49	282	15	346	802
08:30 AM	38	17	27	82	7	269	2	278	7	17	39	63	31	206	22	259	682
08:45 AM	39	17	23	79	7	331	8	346	4	24	65	93	52	338	22	412	930
Total Volume	141	69	96	306	29	1155	13	1197	19	60	203	282	186	1039	71	1296	3081
% App. Total	46.1	22.5	31.4		2.4	96.5	1.1		6.7	21.3	72		14.4	80.2	5.5		
PHF	.904	.908	.889	.933	.659	.872	.406	.865	.679	.625	.781	.758	.861	.768	.807	.786	.828



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE 14 Ave
Hallandale Beach, FL
Location counted: July 14,2011

File Name : HAL-14
Site Code : CGA11505
Start Date : 7/14/2011
Page No : 3

	NE 14 Ave SB				Hallandale Beach Blvd WB				NE 14 Ave NB				Hallandale Beach Blvd EB				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 12:00 PM to 05:45 PM - Peak 1 of 1																	
Peak Hour for Entire Intersection Begins at 04:45 PM																	
04:45 PM	24	21	24	69	14	364	16	394	22	29	68	119	79	299	35	413	995
05:00 PM	30	24	16	70	15	441	11	467	9	22	63	94	82	354	65	501	1132
05:15 PM	24	21	16	61	16	334	13	363	31	33	54	118	59	319	78	456	998
05:30 PM	31	33	24	88	19	396	8	423	26	28	60	114	87	382	52	521	1146
Total Volume	109	99	80	288	64	1535	48	1647	88	112	245	445	307	1354	230	1891	4271
% App. Total	37.8	34.4	27.8		3.9	93.2	2.9		19.8	25.2	55.1		16.2	71.6	12.2		
PHF	.879	.750	.833	.818	.842	.870	.750	.882	.710	.848	.901	.935	.882	.886	.737	.907	.932



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL (772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE10th Ave
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : HAL-10
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 1

Groups Printed- All Traffic

Start Time	Hallandale Beach Blvd From East			NE 10th Ave From South			Hallandale Beach Blvd From West			Int. Total
	Right	Thru	Left	Right	Thru	Left	Right	Thru	Left	
07:00 AM	3	259	1	1	0	1	1	171	8	445
07:15 AM	2	279	1	3	0	1	1	229	7	523
07:30 AM	7	318	3	8	0	0	1	253	5	595
07:45 AM	3	283	3	2	0	0	2	283	9	585
Total	15	1139	8	14	0	2	5	936	29	2148
08:00 AM	4	367	2	8	0	0	2	277	8	668
08:15 AM	7	274	70	12	1	0	31	222	18	635
08:30 AM	11	389	16	16	1	0	3	367	23	826
08:45 AM	5	376	25	14	0	0	4	356	48	828
Total	27	1406	113	50	2	0	40	1222	97	2957

*** BREAK ***

04:00 PM	6	300	5	0	0	0	7	321	13	652
04:15 PM	5	332	5	0	0	0	9	345	21	717
04:30 PM	9	324	20	1	0	0	20	334	31	739
04:45 PM	10	394	22	2	0	0	13	357	32	830
Total	30	1350	52	3	0	0	49	1357	97	2938
05:00 PM	7	436	13	2	0	0	9	444	21	932
05:15 PM	7	420	9	2	0	0	17	359	26	840
05:30 PM	8	395	12	1	0	0	20	343	26	805
05:45 PM	4	401	11	2	0	0	16	395	16	845
Total	26	1652	45	7	0	0	62	1541	89	3422
Grand Total	98	5547	218	74	2	2	156	5056	312	11465
Apprch %	1.7	94.6	3.7	94.9	2.6	2.6	2.8	91.5	5.6	
Total %	0.9	48.4	1.9	0.6	0	0	1.4	44.1	2.7	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL (772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE10th Ave
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : HAL-10
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 2

	Hallandale Beach Blvd From East				NE 10th Ave From South				Hallandale Beach Blvd From West				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1													
Peak Hour for Entire Intersection Begins at 08:00 AM													
08:00 AM	4	367	2	373	8	0	0	8	2	277	8	287	668
08:15 AM	7	274	70	351	12	1	0	13	31	222	18	271	635
08:30 AM	11	389	16	416	16	1	0	17	3	367	23	393	826
08:45 AM	5	376	25	406	14	0	0	14	4	356	48	408	828
Total Volume	27	1406	113	1546	50	2	0	52	40	1222	97	1359	2957
% App. Total	1.7	90.9	7.3		96.2	3.8	0		2.9	89.9	7.1		
PHF	.614	.904	.404	.929	.781	.500	.000	.765	.323	.832	.505	.833	.893



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL (772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE10th Ave
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : HAL-10
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 3

	Hallandale Beach Blvd From East				NE 10th Ave From South				Hallandale Beach Blvd From West				
Start Time	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Right	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1													
Peak Hour for Entire Intersection Begins at 05:00 PM													
05:00 PM	7	436	13	456	2	0	0	2	9	444	21	474	932
05:15 PM	7	420	9	436	2	0	0	2	17	359	26	402	840
05:30 PM	8	395	12	415	1	0	0	1	20	343	26	389	805
05:45 PM	4	401	11	416	2	0	0	2	16	395	16	427	845
Total Volume	26	1652	45	1723	7	0	0	7	62	1541	89	1692	3422
% App. Total	1.5	95.9	2.6		100	0	0		3.7	91.1	5.3		
PHF	.813	.947	.865	.945	.875	.000	.000	.875	.775	.868	.856	.892	.918



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE 8th Ave
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : HAL-8
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 1

Groups Printed- All Traffic

	NE 8th Ave SB			Hallandale Beach Blvd WB		NE 8th Ave NB		Hallandale Beach Blvd EB		
Start Time	Right	Thru	Left	Thru	Left	Right	Left	Right	Thru	Int. Total
07:00 AM	11	0	5	233	3	2	0	0	157	411
07:15 AM	22	0	5	293	0	1	1	1	201	524
07:30 AM	27	0	6	292	0	2	0	0	269	596
07:45 AM	30	0	9	324	0	0	0	1	282	646
Total	90	0	25	1142	3	5	1	2	909	2177
08:00 AM	34	0	20	313	0	3	0	0	395	765
08:15 AM	38	0	16	401	1	2	0	0	261	719
08:30 AM	42	1	23	365	1	2	0	5	402	841
08:45 AM	40	0	20	400	0	3	1	2	391	857
Total	154	1	79	1479	2	10	1	7	1449	3182
*** BREAK ***										
04:00 PM	34	0	22	425	1	9	2	5	387	885
04:15 PM	33	0	15	364	1	5	0	0	386	804
04:30 PM	27	0	21	400	1	8	2	4	435	898
04:45 PM	18	0	21	417	0	7	0	0	364	827
Total	112	0	79	1606	3	29	4	9	1572	3414
05:00 PM	34	1	28	453	0	8	3	5	394	926
05:15 PM	36	1	10	426	1	5	0	1	391	871
05:30 PM	35	1	22	381	0	7	0	2	427	875
05:45 PM	28	1	25	309	1	12	3	2	451	832
Total	133	4	85	1569	2	32	6	10	1663	3504
Grand Total	489	5	268	5796	10	76	12	28	5593	12277
Apprch %	64.2	0.7	35.2	99.8	0.2	86.4	13.6	0.5	99.5	
Total %	4	0	2.2	47.2	0.1	0.6	0.1	0.2	45.6	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE 8th Ave
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : HAL-8
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 2

	NE 8th Ave SB				Hallandale Beach Blvd WB			NE 8th Ave NB			Hallandale Beach Blvd EB			
Start Time	Right	Thru	Left	App. Total	Thru	Left	App. Total	Right	Left	App. Total	Right	Thru	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1														
Peak Hour for Entire Intersection Begins at 08:00 AM														
08:00 AM	34	0	20	54	313	0	313	3	0	3	0	395	395	765
08:15 AM	38	0	16	54	401	1	402	2	0	2	0	261	261	719
08:30 AM	42	1	23	66	365	1	366	2	0	2	5	402	407	841
08:45 AM	40	0	20	60	400	0	400	3	1	4	2	391	393	857
Total Volume	154	1	79	234	1479	2	1481	10	1	11	7	1449	1456	3182
% App. Total	65.8	0.4	33.8		99.9	0.1		90.9	9.1		0.5	99.5		
PHF	.917	.250	.859	.886	.922	.500	.921	.833	.250	.688	.350	.901	.894	.928



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772) 221-7971

Turning Movement - All Traffic
Hallandale Beach Blvd & NE 8th Ave
Hallandale Beach, FL
Location counted: July 19, 2011

File Name : HAL-8
Site Code : CGA11505
Start Date : 7/19/2011
Page No : 3

	NE 8th Ave SB				Hallandale Beach Blvd WB			NE 8th Ave NB			Hallandale Beach Blvd EB			
Start Time	Right	Thru	Left	App. Total	Thru	Left	App. Total	Right	Left	App. Total	Right	Thru	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1														
Peak Hour for Entire Intersection Begins at 04:30 PM														
04:30 PM	27	0	21	48	400	1	401	8	2	10	4	435	439	898
04:45 PM	18	0	21	39	417	0	417	7	0	7	0	364	364	827
05:00 PM	34	1	28	63	453	0	453	8	3	11	5	394	399	926
05:15 PM	36	1	10	47	426	1	427	5	0	5	1	391	392	871
Total Volume	115	2	80	197	1696	2	1698	28	5	33	10	1584	1594	3522
% App. Total	58.4	1	40.6		99.9	0.1		84.8	15.2		0.6	99.4		
PHF	.799	.500	.714	.782	.936	.500	.937	.875	.417	.750	.500	.910	.908	.951



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Manual Traffic Count
Hallandale Beach Blvd and Three Island
Hallandale City, FL
Location counted: July 13, 2011

File Name : HAL-3IS
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 1

Groups Printed- All Traffic

	Three Island SB		Hallandale Beach Blvd WB		Hallandale Beach Blvd EB		
Start Time	Right	Left	Right	Thru	Thru	Left	Int. Total
07:00 AM	43	15	3	134	101	17	313
07:15 AM	53	17	7	154	123	21	375
07:30 AM	73	25	3	162	134	38	435
07:45 AM	69	25	14	172	143	27	450
Total	238	82	27	622	501	103	1573
08:00 AM	63	33	2	202	163	36	499
08:15 AM	75	52	2	185	132	27	473
08:30 AM	57	35	7	228	156	44	527
08:45 AM	72	56	8	239	170	51	596
Total	267	176	19	854	621	158	2095
*** BREAK ***							
04:00 PM	74	37	32	176	176	95	590
04:15 PM	64	33	23	201	187	91	599
04:30 PM	60	35	21	235	198	78	627
04:45 PM	57	30	21	265	203	78	654
Total	255	135	97	877	764	342	2470
05:00 PM	54	46	26	271	245	131	773
05:15 PM	49	50	37	309	268	82	795
05:30 PM	60	43	45	230	329	107	814
05:45 PM	52	32	31	245	220	117	697
Total	215	171	139	1055	1062	437	3079
Grand Total	975	564	282	3408	2948	1040	9217
Apprch %	63.4	36.6	7.6	92.4	73.9	26.1	
Total %	10.6	6.1	3.1	37	32	11.3	

KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Manual Traffic Count
Hallandale Beach Blvd and Three Island
Hallandale City, FL
Location counted: July 13, 2011

File Name : HAL-3IS
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 2

	Three Island SB			Hallandale Beach Blvd WB			Hallandale Beach Blvd EB			
Start Time	Right	Left	App. Total	Right	Thru	App. Total	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1										
Peak Hour for Entire Intersection Begins at 08:00 AM										
08:00 AM	63	33	96	2	202	204	163	36	199	499
08:15 AM	75	52	127	2	185	187	132	27	159	473
08:30 AM	57	35	92	7	228	235	156	44	200	527
08:45 AM	72	56	128	8	239	247	170	51	221	596
Total Volume	267	176	443	19	854	873	621	158	779	2095
% App. Total	60.3	39.7		2.2	97.8		79.7	20.3		
PHF	.890	.786	.865	.594	.893	.884	.913	.775	.881	.879



KMF Traffic Group, LLC


www.kmftraffic.com

Stuart, FL(772-221-7971

Manual Traffic Count
Hallandale Beach Blvd and Three Island
Hallandale City, FL
Location counted: July 13, 2011

File Name : HAL-3IS
Site Code : CGA11505
Start Date : 7/13/2011
Page No : 3

	Three Island SB			Hallandale Beach Blvd WB			Hallandale Beach Blvd EB			
Start Time	Right	Left	App. Total	Right	Thru	App. Total	Thru	Left	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1										
Peak Hour for Entire Intersection Begins at 05:00 PM										
05:00 PM	54	46	100	26	271	297	245	131	376	773
05:15 PM	49	50	99	37	309	346	268	82	350	795
05:30 PM	60	43	103	45	230	275	329	107	436	814
05:45 PM	52	32	84	31	245	276	220	117	337	697
Total Volume	215	171	386	139	1055	1194	1062	437	1499	3079
% App. Total	55.7	44.3		11.6	88.4		70.8	29.2		
PHF	.896	.855	.937	.772	.854	.863	.807	.834	.860	.946



KMF Traffic Group, LLCwww.kmftraffic.com

Stuart, FL(772-221-7971)

Manual Count - All Traffic
S Ocean Dr NB Ramp to Hallandale WB
Hallandale Beach, FL
Location counted: July 14, 2011

File Name : OCE-RAMP

Site Code : 00000000

Start Date : 7/14/2011

Page No : 1

Groups Printed- Unshifted

		S Ocean Dr RAMP	
Start Time	Thru		Int. Total
07:00 AM	87		87
07:15 AM	97		97
07:30 AM	111		111
07:45 AM	110		110
Total	405		405
08:00 AM	127		127
08:15 AM	111		111
08:30 AM	90		90
08:45 AM	92		92
Total	420		420
*** BREAK ***			
04:00 PM	101		101
04:15 PM	112		112
04:30 PM	105		105
04:45 PM	123		123
Total	441		441
05:00 PM	152		152
05:15 PM	144		144
05:30 PM	150		150
05:45 PM	147		147
Total	593		593
Grand Total	1859		1859
Apprch %	100		
Total %	100		

KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Manual Count - All Traffic
S Ocean Dr NB Ramp to Hallandale WB
Hallandale Beach, FL
Location counted: July 14, 2011


File Name : OCE-RAMP

Site Code : 00000000

Start Date : 7/14/2011

Page No : 2

	S Ocean Dr RAMP		
Start Time	Thru	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1			
Peak Hour for Entire Intersection Begins at 07:30 AM			
07:30 AM	111	111	111
07:45 AM	110	110	110
08:00 AM	127	127	127
08:15 AM	111	111	111
Total Volume	459	459	459
% App. Total	100		
PHF	.904	.904	.904



KMF Traffic Group, LLC

www.kmftraffic.com

Stuart, FL(772-221-7971

Manual Count - All Traffic
S Ocean Dr NB Ramp to Hallandale WB
Hallandale Beach, FL
Location counted: July 14, 2011


File Name : OCE-RAMP

Site Code : 00000000

Start Date : 7/14/2011

Page No : 3

S Ocean Dr RAMP			
Start Time	Thru	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1			
Peak Hour for Entire Intersection Begins at 05:00 PM			
05:00 PM	152	152	152
05:15 PM	144	144	144
05:30 PM	150	150	150
05:45 PM	147	147	147
Total Volume	593	593	593
% App. Total	100		
PHF	.975	.975	.975



APPENDIX - C

Growth Rate Analysis/Historical Traffic Data



Growth Rate			
Roadway Name	Location	Station No.	Annual Historic Growth Rate
S. Ocean Drive	N. of Hallandale Beach Blvd	86-0418	1.20%
S. Ocean Drive	S. of Hallandale Beach Blvd	86-5044	1.95%
Hallandale Beach Blvd	W. of SR 5/US 1	86-0590	-0.11%
Hallandale Beach Blvd	E. of SR 5/US 1	86-5029	0.34%
Hallandale Beach Blvd	W. of ICWW BR	86-0349	-1.03%
S. 14th Ave	N. of Hallandale Beach Blvd	86-7309	1.65%
Diplomat Parkway	N. of Hallandale Beach Blvd	86-9630	-2.68%

Average Area Growth Rate:

0.189%

Utilized Growth Rate (2011 to 2015):

0.50%

Growth Rate Factor (2011 to 2015):


1.02

Traffic Trends - V2.0

HALLANDALE BCH BLVD -- W. of ICWW BR

PIN#	973215-1
Location	1

County:	Broward (86)
Station #:	86-0349
Highway:	HALLANDALE BCH BLVD



Year	Traffic (ADT/AADT)	
	Count*	Trend**
2000	30500	34400
2001	35500	34100
2002	35500	33700
2003	34000	33300
2004	33500	33000
2005	35500	32600
2006	30500	32300
2007	31000	31900
2008	31500	31500
2009	30500	31200
2013 Opening Year Trend		
2013	N/A	29800
2023 Mid-Year Trend		
2023	N/A	26200
2033 Design Year Trend		
2033	N/A	22600
TRANPLAN Forecasts/Trends		

** Annual Trend Increase:	-358
Trend R-squared:	23.65%
Trend Annual Historic Growth Rate:	-1.03%
Trend Growth Rate (2009 to Design Year):	-1.15%
Printed:	4-Aug-11
Straight Line Growth Option	


*Axle-Adjusted

Traffic Trends - V2.0

S 14TH AVE -- N. of Hallandale Bch Blvd

PIN#	973215-1
Location	1

County:	Broward (86)
Station #:	86-7309
Highway:	S 14TH AVE



Year	Traffic (ADT/AADT)	
	Count*	Trend**
2000	8000	7400
2001	7800	7500
2002	8100	7600
2003	6600	7700
2004	7800	7900
2005	6600	8000
2006	7300	8100
2007	10000	8300
2008	8700	8400
2009	8500	8500
2013 Opening Year Trend		
2013	N/A	9000
2023 Mid-Year Trend		
2023	N/A	10300
2033 Design Year Trend		
2033	N/A	11600
TRANPLAN Forecasts/Trends		

** Annual Trend Increase:	128
Trend R-squared:	14.80%
Trend Annual Historic Growth Rate:	1.65%
Trend Growth Rate (2009 to Design Year):	1.52%
Printed:	4-Aug-11
Straight Line Growth Option	


*Axle-Adjusted

Traffic Trends - V2.0

S. OCEAN DR -- S. of Hallandale Bch Blvd

PIN#	973215-1
Location	1

County:	Broward (86)
Station #:	86-5044
Highway:	S. OCEAN DR



Year	Traffic (ADT/AADT)	
	Count*	Trend**
2000	29000	27400
2001	29000	27900
2002	30000	28500
2003	26000	29000
2004	26500	29500
2005	28500	30100
2006	32000	30600
2007	31000	31100
2008	33000	31700
2009	33000	32200
2013 Opening Year Trend		
2013	N/A	34400
2023 Mid-Year Trend		
2023	N/A	39800
2033 Design Year Trend		
2033	N/A	45200
TRANPLAN Forecasts/Trends		

** Annual Trend Increase:	539
Trend R-squared:	43.56%
Trend Annual Historic Growth Rate:	1.95%
Trend Growth Rate (2009 to Design Year):	1.68%
Printed:	4-Aug-11
Straight Line Growth Option	


*Axle-Adjusted

Traffic Trends - V2.0

HALLANDALE BCH BLVD -- E. of SR 5/U.S. 1

PIN#	973215-1
Location	1

County:	Broward (86)
Station #:	86-5029
Highway:	HALLANDALE BCH BLVD



Year	Traffic (ADT/AADT)	
	Count*	Trend**
2000	46000	46300
2001	44500	46500
2002	48000	46600
2003	48500	46800
2004	49500	46900
2005	47000	47100
2006	45500	47200
2007	39500	47400
2008	55000	47500
2009	46500	47700
2013 Opening Year Trend		
2013	N/A	48200
2023 Mid-Year Trend		
2023	N/A	49700
2033 Design Year Trend		
2033	N/A	51100
TRANPLAN Forecasts/Trends		

** Annual Trend Increase:	145
Trend R-squared:	1.25%
Trend Annual Historic Growth Rate:	0.34%
Trend Growth Rate (2009 to Design Year):	0.30%
Printed:	4-Aug-11
Straight Line Growth Option	


*Axle-Adjusted

Traffic Trends - V2.0

HALLANDALE BCH BLVD -- W. of SR 5/U.S. 1

PIN#	973215-1
Location	1

County:	Broward (86)
Station #:	86-0590
Highway:	HALLANDALE BCH BLVD



Year	Traffic (ADT/AADT)	
	Count*	Trend**
2000	40500	40900
2001	40500	40900
2002	43000	40800
2003	40000	40800
2004	40500	40700
2005	38000	40700
2006	44000	40600
2007	40500	40600
2008	38500	40500
2009	41500	40500
2013 Opening Year Trend		
2013	N/A	40300
2023 Mid-Year Trend		
2023	N/A	39800
2033 Design Year Trend		
2033	N/A	39300
TRANPLAN Forecasts/Trends		

** Annual Trend Increase:	-48
Trend R-squared:	0.66%
Trend Annual Historic Growth Rate:	-0.11%
Trend Growth Rate (2009 to Design Year):	-0.12%
Printed:	4-Aug-11
Straight Line Growth Option	


*Axle-Adjusted

Traffic Trends - V2.0

S. OCEAN DR -- N. of Hallandale Bch Blvd

PIN#	973215-1
Location	1

County:	Broward (86)
Station #:	86-0418
Highway:	S. OCEAN DR



Year	Traffic (ADT/AADT)	
	Count*	Trend**
2000	29500	27800
2001	31600	28200
2002	27500	28500
2003	25500	28800
2004	28000	29100
2005	28000	29500
2006	28500	29800
2007	29500	30100
2008	31500	30500
2009	33500	30800
2013 Opening Year Trend		
2013	N/A	32100
2023 Mid-Year Trend		
2023	N/A	35400
2033 Design Year Trend		
2033	N/A	38700
TRANPLAN Forecasts/Trends		

** Annual Trend Increase:	329
Trend R-squared:	18.03%
Trend Annual Historic Growth Rate:	1.20%
Trend Growth Rate (2009 to Design Year):	1.07%
Printed:	4-Aug-11
Straight Line Growth Option	


*Axle-Adjusted

Traffic Trends - V2.0

DIPLOMAT PARKWAY -- N. of Hallandale Bch Blvd

PIN#	973215-1
Location	1

County:	Broward (86)
Station #:	86-9630
Highway:	DIPLOMAT PARKWAY



Year	Traffic (ADT/AADT)	
	Count*	Trend**
2001	4000	4200
2002	4200	4100
2003	3900	4000
2004	4000	3900
2005	3900	3800
2006	3800	3600
2007	3300	3500
2008	3500	3400
2009	3200	3300
2013 Opening Year Trend		
2013	N/A	2900
2023 Mid-Year Trend		
2023	N/A	1700
2033 Design Year Trend		
2033	N/A	600
TRANPLAN Forecasts/Trends		

** Annual Trend Increase:	-112
Trend R-squared:	79.40%
Trend Annual Historic Growth Rate:	-2.68%
Trend Growth Rate (2009 to Design Year):	-3.41%
Printed:	4-Aug-11
Straight Line Growth Option	

*Axle-Adjusted

APPENDIX - D

Broward County Signal Timing Data



Pattern Timing Plan Data

Hallandale Beach Blvd & NE 8 Ave

Pattern Number	Offset	Cycle Length	Phase Durations			
			EW	SB	NB	WBL
1	58	110	38	41	18	12
2	124	160	76	41	25	18
3	159	160	72	42	25	20
4	24	160	76	41	25	18
5	72	130	54	41	20	15
12	124	180	87	44	28	21
13	159	160	71	43	26	20
14	73	180	85	48	28	20

Fixed Intervals:

Min Green	10	6	6	4
Flashing Don't Walk	17	0	0	0
Yellow	4	4	4	4
All Red	2	2	2	2
Green Returns	1,2	3	5	8
Command	YIELD	FO 1	FO 1	FO 2

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Patten	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

Pattern Timing Plan Data

Federal Highway & Hallandale Beach Blvd

Pattern Number	Offset	Cycle Length	Phase Durations							
			EW	NSL	SBL	NBL	NS	EWL	EBL	WBL
1	21	110	49	15	0	0	23	23	0	0
2	135	160	50	30	0	0	50	30	0	0
3	1	160	49	29	0	0	48	34	0	0
4	8	160	50	30	0	0	50	30	0	0
5	14	130	49	23	0	0	33	25	0	0
12	135	180	60	35	0	0	50	35	0	0
13	1	160	49	29	0	0	48	34	0	0
14	12	180	54	31	0	0	51	33	0	10

Fixed Intervals:

Min Green	7	5	5	5	6	5	5	5
Flashing Don't Walk	33	0	0	0	0	0	0	0
Yellow	4	4	4	4	4	4	4	4
All Red	2	2	2	2	4	2	2	2
Green Returns	1,2	3,4	3	4	5,6	7,8	8	7
Command	YIELD	FO 1&2	FO 1	FO 2	FO 1&2	FO 1&2	FO 2	FO 1

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Pattern	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

Pattern Timing Plan Data

Hallandale Beach Blvd & NE 14 Ave

Pattern Number	Offset	Cycle Length	Phase Durations							
			EW	NSL	SBL	NBL	NS	EWL	WBL	EBL
1	27	110	45	14	0	0	35	15	0	0
2	69	160	63	24	0	0	55	19	0	0
3	91	160	62	27	0	0	48	23	0	0
4	61	160	60	24	0	0	55	21	0	0
5	31	130	40	16	0	0	55	18	0	0
12	69	180	82	28	0	0	48	22	0	0
13	61	160	62	27	0	0	48	23	0	0
14	66	180	80	27	0	0	50	23	0	0

Fixed Intervals:

Min Green	10	5	5	5	6	5	5	5
Flashing Don't Walk	22	0	0	0	0	0	0	0
Yellow	4	4	4	4	4	4	4	4
All Red	2	2	2	2	2	2	2	2
Green Returns	1,2	3,4	3	4	5,6	7,8	8	7
Command	YIELD	FO 1&2	FO 1	FO 2	FO 1&2	FO 1&2	FO 2	FO 1

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Patten	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

Pattern Timing Plan Data

Hallandale Beach Blvd & Layne Blvd

Pattern Number	Offset	Cycle Length	Phase Durations					
			EW	SB	NB	EWL	WBL	EBL
1	8	110	46	25	23	16	0	0
2	49	160	71	28	41	20	0	0
3	97	160	66	30	41	23	0	0
4	63	160	71	28	41	20	0	0
5	6	130	50	33	32	15	0	0
12	39	180	80	33	45	23	0	0
13	67	160	66	30	41	23	0	0
14	53	180	84	31	41	24	0	0

Fixed Intervals:

Min Green	10	6	6	4	5	5
Flashing Don't Walk	28	0	0	0	0	0
Yellow	4	4	4	4	4	4
All Red	2	2	2	2	2	2
Green Returns	1,2	3	5	7,8	8	7
Command	YIELD	FO 1	FO 1	FO 1&2	FO 2	FO 1

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Pattern	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

Pattern Timing Plan Data

Hallandale Beach Blvd & Golden Isles Dr

Pattern Number	Offset	Cycle Length	Phase Durations			
			EW	NB	SB	WBL
1	8	110	60	17	17	16
2	42	160	73	43	27	16
3	100	160	63	44	33	20
4	68	160	72	43	27	18
5	22	130	46	43	25	16
12	32	180	86	40	34	20
13	75	160	63	44	33	20
14	53	180	78	43	34	25

Fixed Intervals:

Min Green	10	6	6	5
Flashing Don't Walk	19	0	0	0
Yellow	4	4	4	4
All Red	2	2	2	2
Green Returns	1,2	3	5	8
Command	YIELD	FO 1	FO 1	FO 2

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Patten	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

Pattern Timing Plan Data

Hallandale Beach Blvd & Diplomat Parkway

Pattern Number	Offset	Cycle Length	Phase Durations			
			EW	WBL	NS	EBL
1	20	110	38	16	40	16
2	50	160	68	25	43	25
3	113	160	62	26	45	26
4	76	160	68	25	43	25
5	12	130	52	17	43	17
12	50	180	79	25	49	28
13	83	160	61	26	46	26
14	76	180	76	25	47	32

Fixed Intervals:

Min Green	10	5	6	5
Flashing Don't Walk	18	0	0	0
Yellow	4	4	4	4
All Red	2	2	2	2
Green Returns	1,2	8	5,6	7
Command	YIELD	FO 2	FO 1&2	FO 1

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Patten	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

Pattern Timing Plan Data

Hallandale Beach Blvd & Three Islands Dr

Pattern Number	Offset	Cycle Length	Phase Durations					
			EW	XPED	SB	EWL	WBL	EBL
1	104	110	45	41	12	12	0	0
2	55	160	59	41	30	30	0	0
3	108	160	65	36	27	32	0	0
4	86	160	59	41	30	30	0	0
5	124	130	45	41	22	22	0	0
12	55	180	72	43	34	31	0	0
13	73	160	65	36	27	32	0	0
14	102	180	60	43	33	35	10	0

Fixed Intervals:

Min Green	10	7	6	5	5	5
Flashing Don't Walk	26	0	0	0	0	0
Yellow	4	4	4	4	4	4
All Red	2	0	2	2	2	2
Green Returns	1,2	3	5	7,8	8	7
Command	YIELD	HOL	FO 1	FO 1&2	FO 2	FO 1

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Pattern	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

Pattern Timing Plan Data

SR A1A & Hallandale Beach Blvd

Pattern Number	Offset	Cycle Length	Phase Durations					
			NS	WB	EB	NSL	NBL	SBL
1	6	110	45	15	35	15	0	0
2	59	110	45	21	31	13	0	0
3	76	110	45	15	35	15	0	0
4	85	110	45	15	35	15	0	0
5	65	110	45	15	35	15	0	0

Fixed Intervals:

Min Green	7	6	6	5	5	5
Flashing Don't Walk	30	0	0	0	0	0
Yellow	4	4	4	4	4	4
All Red	1	2	2	2	2	2
Green Returns	1,2	3	5	7,8	8	7
Command	YIELD	FO 1	FO 1	FO 1&2	FO 2	FO 1

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Patten	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

Pattern Timing Plan Data

Hallandale Beach Blvd & NE 10 Ave

Pattern Number	Offset	Cycle Length	Phase Durations				
			EW	NB	EWL	WBL	EBL
1	47	110	72	21	17	0	0
2	116	160	88	43	22	0	7
3	157	160	77	43	22	18	0
4	16	160	81	43	22	0	14
5	62	130	71	43	16	0	0
12	125	180	112	43	25	0	0
13	157	160	77	43	22	18	0
14	54	180	89	50	30	0	10

Fixed Intervals:

Min Green	10	6	5	5	5
Flashing Don't Walk	21	0	0	0	0
Yellow	4	4	4	4	4
All Red	2	2	2	2	2
Green Returns	1,2	5	7,8	8	7
Command	YIELD	FO 1	FO 1&2	FO 2	FO 1

Time Of Day Schedule

Monday - Friday

Pattern 2	Morning Peak Pattern	06:00 - 09:00
Pattern 3	Midday Pattern	09:00 - 15:10
Pattern 4	Evening Peak Patten	15:10 - 20:00
Pattern 3	Midday Pattern	20:00 - 00:00

Saturday

Pattern 3	Midday Pattern	06:30 - 01:00
-----------	----------------	---------------

Sunday

Pattern 3	Midday Pattern	06:30 - 23:00
-----------	----------------	---------------

APPENDIX – E

Synchro Output Sheets – Existing
























HCM Signalized Intersection Capacity Analysis

3: E. HALLANDALE BEACH BLVD & GOLDEN ISLES DR

Beachwalk Traffic Study

AM Peak Existing




























												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	4	1067	52	43	1286	17	114	17	44	13	5	2
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Lane Util. Factor		0.91		1.00	0.91		0.95	0.95	1.00		0.95	
Frt		0.99		1.00	1.00		1.00	1.00	0.85		0.99	
Flt Protected		1.00		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (prot)		5049		1770	5076		1681	1706	1583		3376	
Flt Permitted		0.93		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (perm)		4715		1770	5076		1681	1706	1583		3376	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	4	1160	57	47	1398	18	124	18	48	14	5	2
RTOR Reduction (vph)	0	4	0	0	1	0	0	0	35	0	2	0
Lane Group Flow (vph)	0	1217	0	47	1415	0	71	71	13	0	19	0
Turn Type	Perm			Prot			Split			Perm	Split	
Protected Phases		4		3	8		2	2			6	6
Permitted Phases	4								2			
Actuated Green, G (s)		45.6		7.0	58.6		37.4	37.4	37.4		21.2	
Effective Green, g (s)		45.6		7.0	58.6		37.4	37.4	37.4		21.2	
Actuated g/C Ratio		0.34		0.05	0.43		0.28	0.28	0.28		0.16	
Clearance Time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Vehicle Extension (s)		3.0		3.0	3.0		3.0	3.0	3.0		3.0	
Lane Grp Cap (vph)		1590		92	2200		465	472	438		529	
v/s Ratio Prot				0.03	c0.28		c0.04	0.04			c0.01	
v/s Ratio Perm	c0.26								0.01			
v/c Ratio		0.77		0.51	0.64		0.15	0.15	0.03		0.04	
Uniform Delay, d1		40.0		62.4	30.1		36.9	36.9	35.7		48.3	
Progression Factor		1.00		1.00	1.00		1.00	1.00	1.00		1.00	
Incremental Delay, d2		2.3		4.7	0.7		0.7	0.7	0.1		0.1	
Delay (s)		42.3		67.2	30.7		37.6	37.6	35.8		48.5	
Level of Service		D		E	C		D	D	D		D	
Approach Delay (s)		42.3			31.9			37.1			48.5	
Approach LOS		D			C			D			D	
Intersection Summary												
HCM Average Control Delay			36.7			HCM Level of Service				D		
HCM Volume to Capacity ratio			0.43									
Actuated Cycle Length (s)			135.2			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			56.0%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

6: E. HALLANDALE BEACH BLVD & LAYNE BLVD

Beachwalk Traffic Study

AM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  			 			 	
Volume (vph)	49	1043	68	28	1439	23	97	14	49	20	5	50
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Lane Util. Factor	1.00	0.91		1.00	0.91		0.95	0.95	1.00		1.00	1.00
Frt	1.00	0.99		1.00	1.00		1.00	1.00	0.85		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	0.96	1.00		0.96	1.00
Satd. Flow (prot)	1770	5039		1770	5073		1681	1706	1583		1790	1583
Flt Permitted	0.95	1.00		0.95	1.00		0.95	0.82	1.00		0.80	1.00
Satd. Flow (perm)	1770	5039		1770	5073		1681	1448	1583		1486	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	53	1134	74	30	1564	25	105	15	53	22	5	54
RTOR Reduction (vph)	0	4	0	0	1	0	0	0	35	0	0	42
Lane Group Flow (vph)	53	1204	0	30	1588	0	60	60	18	0	27	12
Turn Type	Prot			Prot			Prot		Perm	pm+pt		Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2	6		6
Actuated Green, G (s)	7.5	53.7		4.7	50.9		8.1	40.6	40.6		26.5	26.5
Effective Green, g (s)	7.5	53.7		4.7	50.9		8.1	40.6	40.6		26.5	26.5
Actuated g/C Ratio	0.06	0.46		0.04	0.44		0.07	0.35	0.35		0.23	0.23
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0		3.0	3.0
Lane Grp Cap (vph)	113	2313		71	2207		116	520	549		337	359
v/s Ratio Prot	c0.03	c0.24		0.02	c0.31		c0.04	0.01				
v/s Ratio Perm								c0.03	0.01		0.02	0.01
v/c Ratio	0.47	0.52		0.42	0.72		0.52	0.12	0.03		0.08	0.03
Uniform Delay, d1	52.8	22.5		54.8	27.2		52.6	26.0	25.2		35.6	35.3
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00		1.00	1.00
Incremental Delay, d2	3.1	0.2		4.0	1.1		3.9	0.1	0.1		0.1	0.2
Delay (s)	55.9	22.7		58.8	28.3		56.4	26.1	25.4		35.8	35.5
Level of Service	E	C		E	C		E	C	C		D	D
Approach Delay (s)		24.1			28.9			36.4			35.6	
Approach LOS		C			C			D			D	
Intersection Summary												
HCM Average Control Delay			27.6			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.51									
Actuated Cycle Length (s)			117.0			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			56.4%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												




HCM Unsignalized Intersection Capacity Analysis

9: DIANA DR & SE 26 Avenue

Beachwalk Traffic Study

AM Peak Existing





























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Sign Control		Stop	Stop		Stop	
Volume (vph)	56	1	2	0	1	42
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	61	1	2	0	1	46
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total (vph)	62	2	47			
Volume Left (vph)	61	0	1			
Volume Right (vph)	0	0	46			
Hadj (s)	0.23	0.03	-0.55			
Departure Headway (s)	4.2	4.1	3.5			
Degree Utilization, x	0.07	0.00	0.05			
Capacity (veh/h)	838	864	999			
Control Delay (s)	7.6	7.1	6.7			
Approach Delay (s)	7.6	7.1	6.7			
Approach LOS	A	A	A			
Intersection Summary						
Delay			7.2			
HCM Level of Service			A			
Intersection Capacity Utilization			19.8%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

10: E. HALLANDALE BEACH BLVD & DIPLOMAT PKWY

Beachwalk Traffic Study

AM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  			 			 	
Volume (vph)	49	967	16	14	1291	40	8	1	5	41	23	62
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91		1.00	0.91			1.00		1.00	1.00	
Frt	1.00	1.00		1.00	1.00			0.96		1.00	0.89	
Flt Protected	0.95	1.00		0.95	1.00			0.97		0.95	1.00	
Satd. Flow (prot)	1770	5073		1770	5063			1727		1770	1659	
Flt Permitted	0.95	1.00		0.95	1.00			0.89		0.75	1.00	
Satd. Flow (perm)	1770	5073		1770	5063			1580		1393	1659	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	53	1051	17	15	1403	43	9	1	5	45	25	67
RTOR Reduction (vph)	0	1	0	0	2	0	0	3	0	0	44	0
Lane Group Flow (vph)	53	1067	0	15	1444	0	0	12	0	45	48	0
Turn Type	Prot			Prot			Perm			Perm		
Protected Phases	7	4		3	8			2			6	
Permitted Phases							2			6		
Actuated Green, G (s)	7.2	49.5		2.7	45.0			37.9		37.9	37.9	
Effective Green, g (s)	7.2	49.5		2.7	45.0			37.9		37.9	37.9	
Actuated g/C Ratio	0.07	0.46		0.02	0.42			0.35		0.35	0.35	
Clearance Time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	118	2323		44	2108			554		488	582	
v/s Ratio Prot	c0.03	c0.21		0.01	c0.29						0.03	
v/s Ratio Perm								0.01		c0.03		
v/c Ratio	0.45	0.46		0.34	0.68			0.02		0.09	0.08	
Uniform Delay, d1	48.5	20.1		51.8	25.8			23.0		23.6	23.5	
Progression Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Incremental Delay, d2	2.7	0.1		4.6	0.9			0.1		0.4	0.3	
Delay (s)	51.2	20.3		56.4	26.7			23.0		23.9	23.8	
Level of Service	D	C		E	C			C		C	C	
Approach Delay (s)		21.7			27.0			23.0			23.8	
Approach LOS		C			C			C			C	
Intersection Summary												
HCM Average Control Delay			24.7			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.45									
Actuated Cycle Length (s)			108.1			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			51.6%			ICU Level of Service			A			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

17: E. HALLANDALE BEACH BLVD & 3 ISLANDS BLVD

Beachwalk Traffic Study
AM Peak Existing


























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	←←	↑↑↑	↑↑↑	↑	↑	↑
Volume (vph)	190	745	1025	23	211	320
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.97	0.91	0.91	1.00	1.00	1.00
Frt	1.00	1.00	1.00	0.85	1.00	0.85
Flt Protected	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (prot)	3433	5085	5085	1583	1770	1583
Flt Permitted	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (perm)	3433	5085	5085	1583	1770	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	207	810	1114	25	229	348
RTOR Reduction (vph)	0	0	0	17	0	241
Lane Group Flow (vph)	207	810	1114	8	229	107
Turn Type	Prot			Perm		custom
Protected Phases	7	4	8			
Permitted Phases				8	6	6
Actuated Green, G (s)	10.9	42.3	25.4	25.4	24.2	24.2
Effective Green, g (s)	10.9	42.3	25.4	25.4	24.2	24.2
Actuated g/C Ratio	0.14	0.54	0.32	0.32	0.31	0.31
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	477	2740	1645	512	546	488
v/s Ratio Prot	c0.06	0.16	c0.22			
v/s Ratio Perm				0.01	c0.13	0.07
v/c Ratio	0.43	0.30	0.68	0.02	0.42	0.22
Uniform Delay, d1	31.0	9.9	23.0	18.1	21.6	20.1
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	0.6	0.1	1.1	0.0	2.4	1.0
Delay (s)	31.6	10.0	24.1	18.1	23.9	21.2
Level of Service	C	A	C	B	C	C
Approach Delay (s)		14.4	24.0		22.3	
Approach LOS		B	C		C	
Intersection Summary						
HCM Average Control Delay			20.1		HCM Level of Service	C
HCM Volume to Capacity ratio			0.53			
Actuated Cycle Length (s)			78.5		Sum of lost time (s)	18.0
Intersection Capacity Utilization			51.9%		ICU Level of Service	A
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

21: WB E. Hallandale Beach Blvd & S. OCEAN DR

Beachwalk Traffic Study



























AM Peak Existing

												
Movement	EBL	EBT	EBR2	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR2
Lane Configurations												
Volume (vph)	430	36	667	6	173	6	19	422	6	6	312	248
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.95	0.95	1.00		1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00
Frt	1.00	1.00	0.85		1.00	0.85	1.00	1.00	0.85	1.00	1.00	0.85
Flt Protected	0.95	0.96	1.00		1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (prot)	1681	1698	1583		1859	1583	1770	3539	1583	1770	3539	1583
Flt Permitted	0.95	0.96	1.00		1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	1681	1698	1583		1859	1583	1770	3539	1583	1770	3539	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	467	39	725	7	188	7	21	459	7	7	339	270
RTOR Reduction (vph)	0	0	549	0	0	0	0	0	4	0	0	0
Lane Group Flow (vph)	252	254	176	0	195	7	21	459	3	7	339	270
Turn Type	Split		Perm	Split		Perm	Prot		Perm	Prot		Perm
Protected Phases	3	3		7	7		5	2		1	6	
Permitted Phases			3			7			2			6
Actuated Green, G (s)	25.1	25.1	25.1		13.8	13.8	2.7	39.1	39.1	1.3	37.7	37.7
Effective Green, g (s)	25.1	25.1	25.1		13.8	13.8	2.7	39.1	39.1	1.3	37.7	37.7
Actuated g/C Ratio	0.24	0.24	0.24		0.13	0.13	0.03	0.38	0.38	0.01	0.36	0.36
Clearance Time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0		3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	408	413	385		248	211	46	1340	599	22	1292	578
v/s Ratio Prot	c0.15	0.15			c0.10		c0.01	0.13		0.00	0.10	
v/s Ratio Perm			0.11			0.00			0.00			c0.17
v/c Ratio	0.62	0.62	0.46		0.79	0.03	0.46	0.34	0.00	0.32	0.26	0.47
Uniform Delay, d1	34.8	34.8	33.3		43.3	38.9	49.6	22.9	20.0	50.6	23.0	25.1
Progression Factor	1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	6.9	6.7	3.9		15.1	0.1	7.0	0.7	0.0	8.2	0.1	0.6
Delay (s)	41.7	41.5	37.2		58.4	39.0	56.6	23.6	20.0	58.7	23.1	25.7
Level of Service	D	D	D		E	D	E	C	B	E	C	C
Approach Delay (s)		39.0			57.7			25.0			24.7	
Approach LOS		D			E			C			C	
Intersection Summary												
HCM Average Control Delay			34.3				HCM Level of Service			C		
HCM Volume to Capacity ratio			0.57									
Actuated Cycle Length (s)			103.3				Sum of lost time (s)			24.0		
Intersection Capacity Utilization			74.4%				ICU Level of Service			D		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

22: E. HALLANDALE BEACH BLVD & NE 14 AVE





















Beachwalk Traffic Study
AM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  		 					
Volume (vph)	85	1247	223	16	1386	35	244	72	23	115	83	169
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91	1.00	1.00	0.91		0.97	1.00		1.00	1.00	
Frt	1.00	1.00	0.85	1.00	1.00		1.00	0.96		1.00	0.90	
Flt Protected	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1770	5085	1583	1770	5067		3433	1795		1770	1675	
Flt Permitted	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (perm)	1770	5085	1583	1770	5067		3433	1795		1770	1675	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	92	1355	242	17	1507	38	265	78	25	125	90	184
RTOR Reduction (vph)	0	0	126	0	1	0	0	7	0	0	46	0
Lane Group Flow (vph)	92	1355	116	17	1544	0	265	96	0	125	228	0
Turn Type	Prot		Perm	Prot			Prot			Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			4									
Actuated Green, G (s)	11.7	64.5	64.5	4.7	57.5		16.2	50.2		15.2	49.2	
Effective Green, g (s)	11.7	64.5	64.5	4.7	57.5		16.2	50.2		15.2	49.2	
Actuated g/C Ratio	0.07	0.41	0.41	0.03	0.36		0.10	0.32		0.10	0.31	
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	131	2068	644	52	1837		351	568		170	520	
v/s Ratio Prot	c0.05	c0.27		0.01	c0.30		c0.08	0.05		0.07	c0.14	
v/s Ratio Perm			0.07									
v/c Ratio	0.70	0.66	0.18	0.33	0.84		0.75	0.17		0.74	0.44	
Uniform Delay, d1	71.7	38.1	30.1	75.4	46.3		69.3	39.1		69.7	43.7	
Progression Factor	1.00	1.00	1.00	1.00	1.00		1.00	1.00		1.00	1.00	
Incremental Delay, d2	15.7	0.8	0.1	3.7	3.7		8.9	0.6		15.2	2.7	
Delay (s)	87.4	38.8	30.2	79.1	50.0		78.2	39.8		84.9	46.4	
Level of Service	F	D	C	E	D		E	D		F	D	
Approach Delay (s)		40.2			50.3			67.4			58.4	
Approach LOS		D			D			E			E	
Intersection Summary												
HCM Average Control Delay			48.5			HCM Level of Service				D		
HCM Volume to Capacity ratio			0.71									
Actuated Cycle Length (s)			158.6			Sum of lost time (s)			30.0			
Intersection Capacity Utilization			74.0%			ICU Level of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

26: E. HALLANDALE BEACH BLVD & NE 10 AVE

Beachwalk Traffic Study
AM Peak Existing













												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	116	1466	48	136	1687	32	0	2	60	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Lane Util. Factor	1.00	0.91	1.00	0.97	0.91	1.00		0.95	1.00			
Frt	1.00	1.00	0.85	1.00	1.00	0.85		1.00	0.85			
Flt Protected	0.95	1.00	1.00	0.95	1.00	1.00		1.00	1.00			
Satd. Flow (prot)	1770	5085	1583	3433	5085	1583		3539	1583			
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00		1.00	1.00			
Satd. Flow (perm)	1770	5085	1583	3433	5085	1583		3539	1583			
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	126	1593	52	148	1834	35	0	2	65	0	0	0
RTOR Reduction (vph)	0	0	8	0	0	10	0	0	47	0	0	0
Lane Group Flow (vph)	126	1593	44	148	1834	25	0	2	18	0	0	0
Turn Type	Prot		Perm	Prot		Perm	Prot		Perm			
Protected Phases	7	4		3	8		5	2				
Permitted Phases			4			8			2			
Actuated Green, G (s)	15.4	71.5	71.5	11.5	67.6	67.6		37.6	37.6			
Effective Green, g (s)	15.4	71.5	71.5	11.5	67.6	67.6		37.6	37.6			
Actuated g/C Ratio	0.11	0.52	0.52	0.08	0.49	0.49		0.27	0.27			
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0			
Lane Grp Cap (vph)	197	2623	817	285	2480	772		960	429			
v/s Ratio Prot	c0.07	c0.31		0.04	c0.36			0.00				
v/s Ratio Perm			0.03			0.02			c0.01			
v/c Ratio	0.64	0.61	0.05	0.52	0.74	0.03		0.00	0.04			
Uniform Delay, d1	58.9	23.7	16.7	60.9	28.4	18.5		36.8	37.2			
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00		1.00	1.00			
Incremental Delay, d2	6.7	0.4	0.0	1.6	1.2	0.0		0.0	0.2			
Delay (s)	65.6	24.1	16.7	62.5	29.6	18.5		36.8	37.4			
Level of Service	E	C	B	E	C	B		D	D			
Approach Delay (s)		26.8			31.9			37.4			0.0	
Approach LOS		C			C			D			A	
Intersection Summary												
HCM Average Control Delay			29.6			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.54									
Actuated Cycle Length (s)			138.6			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			57.4%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

29: E. HALLANDALE BEACH BLVD & NE 8 AVE

Beachwalk Traffic Study










AM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑↑↑↑	↗	↖	↑↑↑↑			↕		↖	↗	↗
Volume (vph)	0	1739	8	2	1775	0	1	0	12	95	1	185
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Lane Util. Factor		0.91	1.00	1.00	0.91			1.00		0.95	0.95	1.00
Frt		1.00	0.85	1.00	1.00			0.87		1.00	1.00	0.85
Flt Protected		1.00	1.00	0.95	1.00			1.00		0.95	0.95	1.00
Satd. Flow (prot)		5085	1583	1770	5085			1623		1681	1687	1583
Flt Permitted		1.00	1.00	0.06	1.00			0.99		0.67	0.82	1.00
Satd. Flow (perm)		5085	1583	114	5085			1611		1187	1443	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	1890	9	2	1929	0	1	0	13	103	1	201
RTOR Reduction (vph)	0	0	3	0	0	0	0	10	0	0	0	137
Lane Group Flow (vph)	0	1890	6	2	1929	0	0	4	0	51	53	64
Turn Type			Perm	pm+pt			pm+pt			pm+pt		Perm
Protected Phases		4		3	8		5	2		1	6	
Permitted Phases			4	8			2			6		6
Actuated Green, G (s)		59.4	59.4	66.4	66.4			24.1		37.0	37.0	37.0
Effective Green, g (s)		59.4	59.4	66.4	66.4			24.1		37.0	37.0	37.0
Actuated g/C Ratio		0.51	0.51	0.58	0.58			0.21		0.32	0.32	0.32
Clearance Time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Vehicle Extension (s)		3.0	3.0	3.0	3.0			3.0		3.0	3.0	3.0
Lane Grp Cap (vph)		2617	815	80	2926			336		410	477	508
v/s Ratio Prot		c0.37		0.00	c0.38					0.01	0.01	
v/s Ratio Perm			0.00	0.01				0.00		0.03	0.03	c0.04
v/c Ratio		0.72	0.01	0.02	0.66			0.01		0.12	0.11	0.13
Uniform Delay, d1		21.6	13.6	15.8	16.8			36.2		27.6	27.6	27.8
Progression Factor		1.00	1.00	1.00	1.00			1.00		1.00	1.00	1.00
Incremental Delay, d2		1.0	0.0	0.1	0.5			0.0		0.1	0.1	0.5
Delay (s)		22.6	13.6	15.9	17.3			36.2		27.8	27.7	28.3
Level of Service		C	B	B	B			D		C	C	C
Approach Delay (s)		22.6			17.3			36.2			28.1	
Approach LOS		C			B			D			C	
Intersection Summary												
HCM Average Control Delay		20.6		HCM Level of Service		C						
HCM Volume to Capacity ratio		0.52										
Actuated Cycle Length (s)		115.4		Sum of lost time (s)		18.0						
Intersection Capacity Utilization		64.1%		ICU Level of Service		C						
Analysis Period (min)		15										
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis

33: DIANA DR & GOLDEN ISLES DR

Beachwalk Traffic Study
AM Peak Existing























									
Movement	WBL	WBR	NBT	NBR	SBL	SBT			
Lane Configurations									
Volume (veh/h)	48	49	126	67	7	64			
Sign Control	Stop		Free			Free			
Grade	0%		0%			0%			
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92			
Hourly flow rate (vph)	52	53	137	73	8	70			
Pedestrians									
Lane Width (ft)									
Walking Speed (ft/s)									
Percent Blockage									
Right turn flare (veh)									
Median type			None			None			
Median storage veh									
Upstream signal (ft)						345			
pX, platoon unblocked									
vC, conflicting volume	258	173			210				
vC1, stage 1 conf vol									
vC2, stage 2 conf vol									
vCu, unblocked vol	258	173			210				
tC, single (s)	6.4	6.2			4.1				
tC, 2 stage (s)									
tF (s)	3.5	3.3			2.2				
p0 queue free %	93	94			99				
cM capacity (veh/h)	727	870			1361				
Direction, Lane #	WB 1	NB 1	SB 1						
Volume Total	105	210	77						
Volume Left	52	0	8						
Volume Right	53	73	0						
cSH	793	1700	1361						
Volume to Capacity	0.13	0.12	0.01						
Queue Length 95th (ft)	11	0	0						
Control Delay (s)	10.2	0.0	0.8						
Lane LOS	B		A						
Approach Delay (s)	10.2	0.0	0.8						
Approach LOS	B								
Intersection Summary									
Average Delay		2.9							
Intersection Capacity Utilization		23.0%	ICU Level of Service	A					
Analysis Period (min)		15							

HCM Signalized Intersection Capacity Analysis

34: E. HALLANDALE BEACH BLVD & U.S. 1

Beachwalk Traffic Study

AM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	114	1037	410	540	1168	104	305	598	347	240	1108	86
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Lane Util. Factor	1.00	0.91		0.97	0.91		0.97	0.91	1.00	0.97	0.91	
Frt	1.00	0.96		1.00	0.99		1.00	1.00	0.85	1.00	0.99	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1770	4869		3433	5023		3433	5085	1583	3433	5031	
Flt Permitted	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (perm)	1770	4869		3433	5023		3433	5085	1583	3433	5031	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	124	1127	446	587	1270	113	332	650	377	261	1204	93
RTOR Reduction (vph)	0	45	0	0	6	0	0	0	220	0	5	0
Lane Group Flow (vph)	124	1528	0	587	1377	0	332	650	157	261	1292	0
Turn Type	Prot			Prot			Prot		Perm		Prot	
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2			
Actuated Green, G (s)	16.2	44.0		24.0	51.8		19.9	46.8	46.8	17.1	42.0	
Effective Green, g (s)	16.2	44.0		24.0	51.8		19.9	46.8	46.8	17.1	42.0	
Actuated g/C Ratio	0.10	0.28		0.15	0.33		0.13	0.30	0.30	0.11	0.27	
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	184	1374		528	1669		438	1526	475	377	1355	
v/s Ratio Prot	0.07	c0.31		c0.17	0.27		c0.10	c0.13		0.08	c0.26	
v/s Ratio Perm									0.10			
v/c Ratio	0.67	1.11		1.11	0.83		0.76	0.43	0.33	0.69	0.95	
Uniform Delay, d1	67.3	56.0		66.0	47.9		65.7	43.8	42.4	66.9	56.0	
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00	1.00	1.00	
Incremental Delay, d2	9.4	61.3		73.5	3.5		7.4	0.9	1.9	5.4	15.6	
Delay (s)	76.7	117.2		139.4	51.3		73.0	44.6	44.2	72.3	71.6	
Level of Service	E	F		F	D		E	D	D	E	E	
Approach Delay (s)		114.3			77.6			51.5			71.7	
Approach LOS		F			E			D			E	
Intersection Summary												
HCM Average Control Delay			80.3			HCM Level of Service			F			
HCM Volume to Capacity ratio			1.06									
Actuated Cycle Length (s)			155.9			Sum of lost time (s)			32.0			
Intersection Capacity Utilization			98.3%			ICU Level of Service			F			
Analysis Period (min)			15									
c Critical Lane Group												

Intersection Capacity Utilization

8: E. HALLANDALE BEACH BLVD & EB E. Hallandale Beach Blvd

Beachwalk Traffic Study

AM Peak Existing



Movement	EBT	EBR	WBL	WBT	NBL	NBR	NBR2	NWL	NWR
Lane Configurations	↑↑↑↱		↱	↑↑↑			↱		
Volume (vph)	950	4	47	1072	0	0	58	0	0
Pedestrians									
Ped Button									
Pedestrian Timing (s)									
Free Right		No				No	No		No
Ideal Flow	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Green (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Refr Cycle Length (s)	120								
Volume Combined (vph)	954	0	47	1072	0	0	58	0	0
Lane Utilization Factor	0.91	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00
Turning Factor (vph)	1.00	0.85	0.95	1.00	0.95	0.85	0.85	0.95	0.85
Saturated Flow (vph)	5172	0	1805	5176	0	0	1615	0	0
Ped Intf Time (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Frequency (%)	0.00			0.00	0.00			0.00	
Protected Option Allowed	Yes			Yes	No			No	
Reference Time (s)	22.1	0.0	3.1	24.9		0.0	4.3		0.0
Adj Reference Time (s)	26.1	0.0	8.0	28.9		0.0	8.3		0.0
Permitted Option									
Adj Saturation A (vph)	1724		120	1725	0			0	
Reference Time A (s)	22.1		46.9	24.9	0.0			0.0	
Adj Saturation B (vph)	NA		NA	NA	NA			NA	
Reference Time B (s)	NA		NA	NA	NA			NA	
Reference Time (s)	22.1			46.9					
Adj Reference Time (s)	26.1			50.9					
Split Option									
Ref Time Combined (s)	22.1		3.1	24.9	0.0			0.0	
Ref Time Seperate (s)	22.0		3.1	24.9	0.0			0.0	
Reference Time (s)	22.1		24.9	24.9	0.0			0.0	
Adj Reference Time (s)	26.1		28.9	28.9	0.0			0.0	
Summary		EB WB		NB		NW		Combined	
Protected Option (s)		34.1		NA		NA			
Permitted Option (s)		50.9		Err		Err			
Split Option (s)		55.0		0.0		0.0			
Minimum (s)		34.1		0.0		0.0		34.1	
Right Turns		NBR2							
Adj Reference Time (s)		8.3							
Cross Thru Ref Time (s)		0.0							
Oncoming Left Ref Time (s)		26.1							
Combined (s)		34.4							


























Intersection Summary

Intersection Capacity Utilization 28.7% ICU Level of Service A
Reference Times and Phasing Options do not represent an optimized timing plan.

HCM Signalized Intersection Capacity Analysis

3: E. HALLANDALE BEACH BLVD & GOLDEN ISLES DR

Beachwalk Traffic Study
PM Peak Existing




























												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  			 			 	
Volume (vph)	2	1655	83	48	1464	50	130	18	54	53	13	8
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Lane Util. Factor		0.91		1.00	0.91		0.95	0.95	1.00		0.95	
Frt		0.99		1.00	1.00		1.00	1.00	0.85		0.98	
Flt Protected		1.00		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (prot)		5049		1770	5060		1681	1705	1583		3360	
Flt Permitted		0.94		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (perm)		4737		1770	5060		1681	1705	1583		3360	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	2	1799	90	52	1591	54	141	20	59	58	14	9
RTOR Reduction (vph)	0	3	0	0	2	0	0	0	45	0	6	0
Lane Group Flow (vph)	0	1888	0	52	1643	0	80	81	14	0	75	0
Turn Type	Perm			Prot			Split			Perm		Split
Protected Phases		4		3	8		2	2			6	6
Permitted Phases	4								2			
Actuated Green, G (s)		66.1		8.2	80.3		37.1	37.1	37.1		21.0	
Effective Green, g (s)		66.1		8.2	80.3		37.1	37.1	37.1		21.0	
Actuated g/C Ratio		0.42		0.05	0.51		0.24	0.24	0.24		0.13	
Clearance Time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Vehicle Extension (s)		3.0		3.0	3.0		3.0	3.0	3.0		3.0	
Lane Grp Cap (vph)		2002		93	2598		399	404	376		451	
v/s Ratio Prot				0.03	c0.32		c0.05	0.05			c0.02	
v/s Ratio Perm	c0.40								0.01			
v/c Ratio		0.94		0.56	0.63		0.20	0.20	0.04		0.17	
Uniform Delay, d1		43.3		72.3	27.4		47.8	47.8	45.9		59.9	
Progression Factor		1.00		1.00	1.00		1.00	1.00	1.00		1.00	
Incremental Delay, d2		9.7		7.1	0.5		1.1	1.1	0.2		0.8	
Delay (s)		53.1		79.4	27.9		48.9	48.9	46.1		60.7	
Level of Service		D		E	C		D	D	D		E	
Approach Delay (s)		53.1			29.5			48.1			60.7	
Approach LOS		D			C			D			E	
Intersection Summary												
HCM Average Control Delay			42.7			HCM Level of Service			D			
HCM Volume to Capacity ratio			0.61									
Actuated Cycle Length (s)			156.4			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			60.6%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

6: E. HALLANDALE BEACH BLVD & LAYNE BLVD

Beachwalk Traffic Study




PM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  			 			 	
Volume (vph)	98	1585	48	24	1426	31	130	14	58	80	12	71
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Lane Util. Factor	1.00	0.91		1.00	0.91		0.95	0.95	1.00		1.00	1.00
Frt	1.00	1.00		1.00	1.00		1.00	1.00	0.85		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	0.96	1.00		0.96	1.00
Satd. Flow (prot)	1770	5063		1770	5069		1681	1701	1583		1785	1583
Flt Permitted	0.95	1.00		0.95	1.00		0.95	0.68	1.00		0.70	1.00
Satd. Flow (perm)	1770	5063		1770	5069		1681	1208	1583		1297	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	107	1723	52	26	1550	34	141	15	63	87	13	77
RTOR Reduction (vph)	0	1	0	0	1	0	0	0	43	0	0	63
Lane Group Flow (vph)	107	1774	0	26	1583	0	78	78	20	0	100	14
Turn Type	Prot			Prot			Prot		Perm	pm+pt		Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2	6		6
Actuated Green, G (s)	12.3	62.7		4.7	55.1		11.4	39.8	39.8		22.4	22.4
Effective Green, g (s)	12.3	62.7		4.7	55.1		11.4	39.8	39.8		22.4	22.4
Actuated g/C Ratio	0.10	0.50		0.04	0.44		0.09	0.32	0.32		0.18	0.18
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0		3.0	3.0
Lane Grp Cap (vph)	174	2536		66	2231		153	429	503		232	283
v/s Ratio Prot	c0.06	c0.35		0.01	0.31		c0.05	0.02				
v/s Ratio Perm								0.04	0.01		c0.08	0.01
v/c Ratio	0.61	0.70		0.39	0.71		0.51	0.18	0.04		0.43	0.05
Uniform Delay, d1	54.2	24.0		58.9	28.5		54.2	30.9	29.5		45.7	42.6
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00		1.00	1.00
Incremental Delay, d2	6.3	0.9		3.8	1.1		2.7	0.2	0.1		1.3	0.3
Delay (s)	60.5	24.9		62.7	29.6		56.9	31.1	29.6		47.0	42.9
Level of Service	E	C		E	C		E	C	C		D	D
Approach Delay (s)		26.9			30.1			39.9			45.2	
Approach LOS		C			C			D			D	
Intersection Summary												
HCM Average Control Delay			29.8			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.64									
Actuated Cycle Length (s)			125.2			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			61.8%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis9: DIANA DR & SE 26 Avenue

Beachwalk Traffic Study
PM Peak Existing






















Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Sign Control		Stop	Stop		Stop	
Volume (vph)	44	6	1	2	5	61
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	48	7	1	2	5	66
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total (vph)	54	3	72			
Volume Left (vph)	48	0	5			
Volume Right (vph)	0	2	66			
Hadj (s)	0.21	-0.37	-0.51			
Departure Headway (s)	4.2	3.7	3.5			
Degree Utilization, x	0.06	0.00	0.07			
Capacity (veh/h)	828	940	993			
Control Delay (s)	7.5	6.7	6.8			
Approach Delay (s)	7.5	6.7	6.8			
Approach LOS	A	A	A			
Intersection Summary						
Delay			7.1			
HCM Level of Service			A			
Intersection Capacity Utilization			20.1%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

10: E. HALLANDALE BEACH BLVD & DIPLOMAT PKWY

Beachwalk Traffic Study


PM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	106	1733	0	4	1415	42	8	11	12	61	1	52
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91		1.00	0.91			1.00		1.00	1.00	
Frt	1.00	1.00		1.00	1.00			0.95		1.00	0.85	
Flt Protected	0.95	1.00		0.95	1.00			0.99		0.95	1.00	
Satd. Flow (prot)	1770	5085		1770	5063			1744		1770	1588	
Flt Permitted	0.95	1.00		0.95	1.00			0.95		0.73	1.00	
Satd. Flow (perm)	1770	5085		1770	5063			1670		1369	1588	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	115	1884	0	4	1538	46	9	12	13	66	1	57
RTOR Reduction (vph)	0	0	0	0	2	0	0	9	0	0	40	0
Lane Group Flow (vph)	115	1884	0	4	1582	0	0	25	0	66	18	0
Turn Type	Prot			Prot			Perm			Perm		
Protected Phases	7	4		3	8			2			6	
Permitted Phases							2			6		
Actuated Green, G (s)	13.2	70.8		1.1	58.7			37.6		37.6	37.6	
Effective Green, g (s)	13.2	70.8		1.1	58.7			37.6		37.6	37.6	
Actuated g/C Ratio	0.10	0.56		0.01	0.46			0.29		0.29	0.29	
Clearance Time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	183	2824		15	2331			492		404	468	
v/s Ratio Prot	c0.06	c0.37		0.00	0.31						0.01	
v/s Ratio Perm								0.01		c0.05		
v/c Ratio	0.63	0.67		0.27	0.68			0.05		0.16	0.04	
Uniform Delay, d1	54.8	20.0		62.8	27.0			32.2		33.3	32.1	
Progression Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Incremental Delay, d2	6.6	0.6		9.3	0.8			0.2		0.9	0.2	
Delay (s)	61.4	20.6		72.1	27.8			32.4		34.2	32.2	
Level of Service	E	C		E	C			C		C	C	
Approach Delay (s)		23.0			27.9			32.4			33.2	
Approach LOS		C			C			C			C	
Intersection Summary												
HCM Average Control Delay			25.5			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.51									
Actuated Cycle Length (s)			127.5			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			61.9%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

17: E. HALLANDALE BEACH BLVD & 3 ISLANDS BLVD

Beachwalk Traffic Study
PM Peak Existing


























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↰↰	↑↑↑	↑↑↑	↰	↰	↰
Volume (vph)	524	1274	1266	167	205	258
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.97	0.91	0.91	1.00	1.00	1.00
Frt	1.00	1.00	1.00	0.85	1.00	0.85
Flt Protected	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (prot)	3433	5085	5085	1583	1770	1583
Flt Permitted	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (perm)	3433	5085	5085	1583	1770	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	570	1385	1376	182	223	280
RTOR Reduction (vph)	0	0	0	116	0	215
Lane Group Flow (vph)	570	1385	1376	66	223	65
Turn Type	Prot			Perm		custom
Protected Phases	7	4	8			
Permitted Phases				8	6	6
Actuated Green, G (s)	24.1	67.7	37.6	37.6	24.1	24.1
Effective Green, g (s)	24.1	67.7	37.6	37.6	24.1	24.1
Actuated g/C Ratio	0.23	0.65	0.36	0.36	0.23	0.23
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	797	3317	1842	573	411	368
v/s Ratio Prot	c0.17	0.27	c0.27			
v/s Ratio Perm				0.04	c0.13	0.04
v/c Ratio	0.72	0.42	0.75	0.12	0.54	0.18
Uniform Delay, d1	36.7	8.6	28.9	22.0	35.0	31.9
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	3.1	0.1	1.7	0.1	5.1	1.0
Delay (s)	39.8	8.7	30.6	22.1	40.1	33.0
Level of Service	D	A	C	C	D	C
Approach Delay (s)		17.8	29.6		36.1	
Approach LOS		B	C		D	
Intersection Summary						
HCM Average Control Delay			24.7		HCM Level of Service	C
HCM Volume to Capacity ratio			0.68			
Actuated Cycle Length (s)			103.8		Sum of lost time (s)	18.0
Intersection Capacity Utilization			65.8%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

21: WB E. Hallandale Beach Blvd & S. OCEAN DR





























Beachwalk Traffic Study
PM Peak Existing

												
Movement	EBL	EBT	EBR2	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR2
Lane Configurations												
Volume (vph)	642	84	876	12	89	30	22	655	6	17	710	616
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.95	0.95	1.00		1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00
Frt	1.00	1.00	0.85		1.00	0.85	1.00	1.00	0.85	1.00	1.00	0.85
Flt Protected	0.95	0.96	1.00		0.99	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (prot)	1681	1704	1583		1852	1583	1770	3539	1583	1770	3539	1583
Flt Permitted	0.95	0.96	1.00		0.99	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	1681	1704	1583		1852	1583	1770	3539	1583	1770	3539	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	698	91	952	13	97	33	24	712	7	18	772	670
RTOR Reduction (vph)	0	0	686	0	0	0	0	0	4	0	0	0
Lane Group Flow (vph)	391	398	266	0	110	33	24	712	3	18	772	670
Turn Type	Split		Perm	Split		Perm	Prot		Perm	Prot		Perm
Protected Phases	3	3		7	7		5	2		1	6	
Permitted Phases			3			7			2			6
Actuated Green, G (s)	29.1	29.1	29.1		8.7	8.7	3.1	39.4	39.4	2.9	39.2	39.2
Effective Green, g (s)	29.1	29.1	29.1		8.7	8.7	3.1	39.4	39.4	2.9	39.2	39.2
Actuated g/C Ratio	0.28	0.28	0.28		0.08	0.08	0.03	0.38	0.38	0.03	0.38	0.38
Clearance Time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0		3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	470	476	443		155	132	53	1339	599	49	1333	596
v/s Ratio Prot	0.23	c0.23			c0.06		c0.01	0.20		0.01	0.22	
v/s Ratio Perm			0.17			0.02			0.00			c0.42
v/c Ratio	0.83	0.84	0.60		0.71	0.25	0.45	0.53	0.00	0.37	0.58	1.12
Uniform Delay, d1	35.2	35.3	32.5		46.5	44.6	49.7	25.2	20.1	49.7	25.9	32.4
Progression Factor	1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	15.7	15.9	5.9		13.9	1.0	6.0	1.5	0.0	4.6	0.6	76.0
Delay (s)	50.9	51.1	38.4		60.3	45.6	55.7	26.7	20.2	54.3	26.5	108.4
Level of Service	D	D	D		E	D	E	C	C	D	C	F
Approach Delay (s)		44.1			56.9			27.6			64.4	
Approach LOS		D			E			C			E	
Intersection Summary												
HCM Average Control Delay			48.8				HCM Level of Service			D		
HCM Volume to Capacity ratio			0.95									
Actuated Cycle Length (s)			104.1				Sum of lost time (s)			24.0		
Intersection Capacity Utilization			94.2%				ICU Level of Service			F		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

22: E. HALLANDALE BEACH BLVD & NE 14 AVE



























Beachwalk Traffic Study
PM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  		 				 	
Volume (vph)	298	1673	354	58	1777	77	274	139	104	83	119	130
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91	1.00	1.00	0.91		0.97	1.00		1.00	1.00	
Frt	1.00	1.00	0.85	1.00	0.99		1.00	0.94		1.00	0.92	
Flt Protected	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1770	5085	1583	1770	5054		3433	1743		1770	1717	
Flt Permitted	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (perm)	1770	5085	1583	1770	5054		3433	1743		1770	1717	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	324	1818	385	63	1932	84	298	151	113	90	129	141
RTOR Reduction (vph)	0	0	154	0	3	0	0	16	0	0	24	0
Lane Group Flow (vph)	324	1818	231	63	2013	0	298	248	0	90	246	0
Turn Type	Prot		Perm	Prot			Prot			Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			4									
Actuated Green, G (s)	15.0	60.7	60.7	9.6	55.3		17.1	52.8		13.3	49.0	
Effective Green, g (s)	15.0	60.7	60.7	9.6	55.3		17.1	52.8		13.3	49.0	
Actuated g/C Ratio	0.09	0.38	0.38	0.06	0.34		0.11	0.33		0.08	0.31	
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	166	1924	599	106	1742		366	574		147	525	
v/s Ratio Prot	c0.18	c0.36		0.04	c0.40		c0.09	c0.14		0.05	c0.14	
v/s Ratio Perm			0.15									
v/c Ratio	1.95	0.94	0.39	0.59	1.16		0.81	0.43		0.61	0.47	
Uniform Delay, d1	72.7	48.2	36.3	73.5	52.6		70.1	42.1		71.1	45.1	
Progression Factor	1.00	1.00	1.00	1.00	1.00		1.00	1.00		1.00	1.00	
Incremental Delay, d2	449.5	10.3	0.4	8.6	77.1		13.0	2.4		7.3	3.0	
Delay (s)	522.2	58.5	36.7	82.1	129.6		83.1	44.4		78.4	48.1	
Level of Service	F	E	D	F	F		F	D		E	D	
Approach Delay (s)		114.6			128.2			64.9			55.7	
Approach LOS		F			F			E			E	
Intersection Summary												
HCM Average Control Delay			110.8			HCM Level of Service				F		
HCM Volume to Capacity ratio			1.04									
Actuated Cycle Length (s)			160.4			Sum of lost time (s)			36.0			
Intersection Capacity Utilization			94.6%			ICU Level of Service			F			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

26: E. HALLANDALE BEACH BLVD & NE 10 AVE

Beachwalk Traffic Study
PM Peak Existing













												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  		 	  			 				
Volume (vph)	107	1849	74	54	1982	31	0	0	8	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0			6.0			
Lane Util. Factor	1.00	0.91	1.00	0.97	0.91	1.00			1.00			
Frt	1.00	1.00	0.85	1.00	1.00	0.85			0.85			
Flt Protected	0.95	1.00	1.00	0.95	1.00	1.00			1.00			
Satd. Flow (prot)	1770	5085	1583	3433	5085	1583			1583			
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00			1.00			
Satd. Flow (perm)	1770	5085	1583	3433	5085	1583			1583			
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	116	2010	80	59	2154	34	0	0	9	0	0	0
RTOR Reduction (vph)	0	0	9	0	0	9	0	0	7	0	0	0
Lane Group Flow (vph)	116	2010	71	59	2154	25	0	0	2	0	0	0
Turn Type	Prot		Perm	Prot		Perm	Prot		Perm			
Protected Phases	7	4		3	8		5	2				
Permitted Phases			4			8			2			
Actuated Green, G (s)	8.0	82.9	82.9	6.6	81.5	81.5			37.2			
Effective Green, g (s)	8.0	82.9	82.9	6.6	81.5	81.5			37.2			
Actuated g/C Ratio	0.06	0.57	0.57	0.05	0.56	0.56			0.26			
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0			6.0			
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0			3.0			
Lane Grp Cap (vph)	98	2913	907	157	2864	892			407			
v/s Ratio Prot	c0.07	0.40		0.02	c0.42							
v/s Ratio Perm			0.04			0.02			c0.00			
v/c Ratio	1.18	0.69	0.08	0.38	0.75	0.03			0.01			
Uniform Delay, d1	68.4	21.8	13.8	67.0	23.9	14.0			40.0			
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00			1.00			
Incremental Delay, d2	148.5	0.7	0.0	1.5	1.2	0.0			0.0			
Delay (s)	216.9	22.5	13.9	68.6	25.1	14.0			40.0			
Level of Service	F	C	B	E	C	B			D			
Approach Delay (s)		32.4			26.1			40.0			0.0	
Approach LOS		C			C			D			A	
Intersection Summary												
HCM Average Control Delay			29.3			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.56									
Actuated Cycle Length (s)			144.7			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			54.2%			ICU Level of Service			A			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

29: E. HALLANDALE BEACH BLVD & NE 8 AVE

Beachwalk Traffic Study










PM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑↑↑↑	↗	↖	↑↑↑↑			↕		↖	↗	↗
Volume (vph)	0	1996	12	2	1883	0	7	0	38	102	5	160
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Lane Util. Factor		0.91	1.00	1.00	0.91			1.00		0.95	0.95	1.00
Frt		1.00	0.85	1.00	1.00			0.89		1.00	1.00	0.85
Flt Protected		1.00	1.00	0.95	1.00			0.99		0.95	0.96	1.00
Satd. Flow (prot)		5085	1583	1770	5085			1639		1681	1692	1583
Flt Permitted		1.00	1.00	0.05	1.00			0.96		0.66	0.78	1.00
Satd. Flow (perm)		5085	1583	96	5085			1584		1161	1372	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	2170	13	2	2047	0	8	0	41	111	5	174
RTOR Reduction (vph)	0	0	4	0	0	0	0	33	0	0	0	124
Lane Group Flow (vph)	0	2170	9	2	2047	0	0	16	0	58	58	50
Turn Type			Perm	pm+pt			pm+pt			pm+pt		Perm
Protected Phases		4		3	8		5	2		1	6	
Permitted Phases			4	8			2			6		6
Actuated Green, G (s)		71.4	71.4	78.4	78.4			23.4		36.9	36.9	36.9
Effective Green, g (s)		71.4	71.4	78.4	78.4			23.4		36.9	36.9	36.9
Actuated g/C Ratio		0.56	0.56	0.62	0.62			0.18		0.29	0.29	0.29
Clearance Time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Vehicle Extension (s)		3.0	3.0	3.0	3.0			3.0		3.0	3.0	3.0
Lane Grp Cap (vph)		2852	888	72	3132			291		367	417	459
v/s Ratio Prot		c0.43		0.00	c0.40					c0.01	0.01	
v/s Ratio Perm			0.01	0.02				0.01		c0.04	0.03	0.03
v/c Ratio		0.76	0.01	0.03	0.65			0.05		0.16	0.14	0.11
Uniform Delay, d1		21.4	12.3	17.1	15.7			42.8		33.4	33.4	33.2
Progression Factor		1.00	1.00	1.00	1.00			1.00		1.00	1.00	1.00
Incremental Delay, d2		1.2	0.0	0.2	0.5			0.1		0.2	0.2	0.5
Delay (s)		22.6	12.3	17.3	16.2			42.9		33.6	33.6	33.6
Level of Service		C	B	B	B			D		C	C	C
Approach Delay (s)		22.6			16.2			42.9			33.6	
Approach LOS		C			B			D			C	
Intersection Summary												
HCM Average Control Delay		20.7		HCM Level of Service		C						
HCM Volume to Capacity ratio		0.58										
Actuated Cycle Length (s)		127.3		Sum of lost time (s)		18.0						
Intersection Capacity Utilization		64.6%		ICU Level of Service		C						
Analysis Period (min)		15										
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis

33: DIANA DR & GOLDEN ISLES DR























Beachwalk Traffic Study
PM Peak Existing

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Volume (veh/h)	66	101	109	55	24	104
Sign Control	Stop		Free			Free
Grade	0%		0%			0%
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	72	110	118	60	26	113
Pedestrians						
Lane Width (ft)						
Walking Speed (ft/s)						
Percent Blockage						
Right turn flare (veh)						
Median type			None			None
Median storage (veh)						
Upstream signal (ft)						345
pX, platoon unblocked						
vC, conflicting volume	314	148			178	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	314	148			178	
tC, single (s)	6.4	6.2			4.1	
tC, 2 stage (s)						
tF (s)	3.5	3.3			2.2	
p0 queue free %	89	88			98	
cM capacity (veh/h)	666	898			1398	
Direction, Lane #	WB 1	NB 1	SB 1			
Volume Total	182	178	139			
Volume Left	72	0	26			
Volume Right	110	60	0			
cSH	790	1700	1398			
Volume to Capacity	0.23	0.10	0.02			
Queue Length 95th (ft)	22	0	1			
Control Delay (s)	10.9	0.0	1.6			
Lane LOS	B		A			
Approach Delay (s)	10.9	0.0	1.6			
Approach LOS	B					
Intersection Summary						
Average Delay		4.4				
Intersection Capacity Utilization		35.8%		ICU Level of Service		A
Analysis Period (min)		15				

HCM Signalized Intersection Capacity Analysis

34: E. HALLANDALE BEACH BLVD & U.S. 1

Beachwalk Traffic Study
PM Peak Existing

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	205	970	390	626	1348	168	599	1339	625	350	977	119
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Lane Util. Factor	1.00	0.91		0.97	0.91		0.97	0.91	1.00	0.97	0.91	
Frt	1.00	0.96		1.00	0.98		1.00	1.00	0.85	1.00	0.98	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1770	4866		3433	5001		3433	5085	1583	3433	5003	
Flt Permitted	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (perm)	1770	4866		3433	5001		3433	5085	1583	3433	5003	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	223	1054	424	680	1465	183	651	1455	679	380	1062	129
RTOR Reduction (vph)	0	46	0	0	9	0	0	0	211	0	10	0
Lane Group Flow (vph)	223	1432	0	680	1639	0	651	1455	468	380	1181	0
Turn Type	Prot			Prot			Prot		Perm	Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2			
Actuated Green, G (s)	22.7	44.0		24.0	45.3		24.0	46.2	46.2	21.8	42.0	
Effective Green, g (s)	22.7	44.0		24.0	45.3		24.0	46.2	46.2	21.8	42.0	
Actuated g/C Ratio	0.14	0.28		0.15	0.28		0.15	0.29	0.29	0.14	0.26	
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	251	1338		515	1416		515	1468	457	468	1313	
v/s Ratio Prot	0.13	0.29		c0.20	c0.33		c0.19	0.29		0.11	0.24	
v/s Ratio Perm									c0.30			
v/c Ratio	0.89	1.07		1.32	1.16		1.26	0.99	1.03	0.81	0.90	
Uniform Delay, d1	67.4	58.0		68.0	57.4		68.0	56.7	56.9	67.1	57.0	
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00	1.00	1.00	
Incremental Delay, d2	29.2	45.9		157.4	79.1		133.7	21.5	48.6	10.3	10.1	
Delay (s)	96.6	103.9		225.4	136.5		201.7	78.2	105.5	77.4	67.0	
Level of Service	F	F		F	F		F	E	F	E	E	
Approach Delay (s)		102.9			162.4			113.7			69.5	
Approach LOS		F			F			F			E	
Intersection Summary												
HCM Average Control Delay			116.8			HCM Level of Service			F			
HCM Volume to Capacity ratio			1.09									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			12.0			
Intersection Capacity Utilization			105.6%			ICU Level of Service			G			
Analysis Period (min)			15									
c Critical Lane Group												

Intersection Capacity Utilization

8: E. HALLANDALE BEACH BLVD & EB E. Hallandale Beach Blvd

Beachwalk Traffic Study

PM Peak Existing



Movement	EBT	EBR	WBL	WBT	NBL	NBR	NBR2	NWL	NWR
Lane Configurations	↑↑↑↵		↵	↑↑↑			↵		
Volume (vph)	1555	7	74	1404	0	0	52	0	0
Pedestrians									
Ped Button									
Pedestrian Timing (s)									
Free Right	No				No		No	No	
Ideal Flow	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Green (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Refr Cycle Length (s)	120								
Volume Combined (vph)	1562	0	74	1404	0	0	52	0	0
Lane Utilization Factor	0.91	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00
Turning Factor (vph)	1.00	0.85	0.95	1.00	0.95	0.85	0.85	0.95	0.85
Saturated Flow (vph)	5172	0	1805	5176	0	0	1615	0	0
Ped Intf Time (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Frequency (%)	0.00			0.00	0.00			0.00	
Protected Option Allowed	Yes			Yes	No			No	
Reference Time (s)	36.2	0.0	4.9	32.6	0.0		3.9	0.0	
Adj Reference Time (s)	40.2	0.0	8.9	36.6	0.0		8.0	0.0	
Permitted Option									
Adj Saturation A (vph)	1724	120		1725	0			0	
Reference Time A (s)	36.2	73.8		32.6	0.0			0.0	
Adj Saturation B (vph)	NA	NA		NA	NA			NA	
Reference Time B (s)	NA	NA		NA	NA			NA	
Reference Time (s)	36.2			73.8					
Adj Reference Time (s)	40.2			77.8					
Split Option									
Ref Time Combined (s)	36.2	4.9		32.6	0.0			0.0	
Ref Time Seperate (s)	36.1	4.9		32.6	0.0			0.0	
Reference Time (s)	36.2	32.6		32.6	0.0			0.0	
Adj Reference Time (s)	40.2	36.6		36.6	0.0			0.0	
Summary		EB WB		NB		NW		Combined	
Protected Option (s)		49.2		NA		NA			
Permitted Option (s)		77.8		Err		Err			
Split Option (s)		76.8		0.0		0.0			
Minimum (s)		49.2		0.0		0.0		49.2	
Right Turns		NBR2							
Adj Reference Time (s)		8.0							
Cross Thru Ref Time (s)		0.0							
Oncoming Left Ref Time (s)		40.2							
Combined (s)		48.2							

Intersection Summary

Intersection Capacity Utilization 41.0% ICU Level of Service A
 Reference Times and Phasing Options do not represent an optimized timing plan.


APPENDIX – F

Committed Development Data –

Wal-Mart Expansion TIS



Beachwalk Development - Committed Traffic AM (1 of 2)



Beachwalk Development

Committed Traffic AM
Figure xxx

LEGEND

0

Project Trip Turning Movement Volume

10%

Project Trip Turning Movement Percentage

250

Total Approach Volume


250

Total Exit Volume


PSCF

EAST-A1A TO US11.20

Beachwalk Development - Committed Traffic AM (2 of 2)



Beachwalk Development - Committed Traffic PM (1 of 2)



Beachwalk Development

Committed Traffic PM
Figure xxx

LEGEND

0

10%

250

250

Project Trip Turning Movement Volume

Project Trip Turning Movement Percentage

Total Approach Volume

Total Exit Volume

PSCF

EAST-A1A TO US1

1.20

Beachwalk Development - Committed Traffic PM (2 of 2)




TABLE K-1
TOTAL(2012) PM PEAK-HOUR, PEAK-SEASON TURNING-MOVEMENT VOLUMES
WALMART EXPANSION TRAFFIC IMPACT STUDY

INTERSECTION													
		EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Hallandale Beach Boulevard at Federal Highway	Collected Count (05/19/08)	148	797	189	658	1,062	193	456	1,131	690	211	749	83
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	1.06	1.06	1.06	1.15	1.15	1.15	1.11	1.11	1.11	1.11	1.11	1.11
	2008 Peak-Season Count	157	845	200	757	1,221	222	506	1,255	766	234	831	92
	CGR	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	2009 Peak-Season Count	159	853	202	765	1,233	224	511	1,268	774	236	839	93
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	Committed Development Trips	0	209	172	85	224	174	236	107	101	184	86	0
	2012 Background Traffic	164	1,088	380	873	1,494	405	762	1,413	898	427	950	96
	Project IN/OUT Movement		IN		OUT	OUT	OUT			IN	IN		
	Project Distribution		10.00%		14.00%	10.00%	15.00%			13.00%	13.00%		
Hallandale Beach Boulevard at NE 8th Avenue	2012 Project Trips	0	4	0	5	4	5	0	0	5	5	0	0
	2012 Total Traffic	164	1,092	380	878	1,498	410	762	1,413	903	432	950	96
	Collected Count (04/14/09)	0	1,029	15	13	1,556	0	2	0	21	75	4	136
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05
	2009 Peak-Season Count	0	1,080	16	14	1,634	0	2	0	22	79	4	143
	CGR	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
	2009 Peak-Season Count	0	1,847	16	14	1,634	0	2	0	22	79	4	143
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	Committed Development Trips	0	257	184	84	256	0	232	7	0	0	7	7
	2012 Background Traffic	0	2,160	200	98	1,940	0	234	7	23	81	11	154
Hallandale Beach Boulevard at NE 10th Avenue	Project IN/OUT Movement		IN			OUT					IN		
	Project Distribution		36.00%			39.00%					4.00%		
	2012 Project Trips	0	14	0	0	14	0	0	0	0	1	0	0
	2012 Total Traffic	0	2,174	200	98	1,954	0	234	7	23	82	11	154
	Collected Count (04/14/09)	53	1,351	39	33	1,500	67	19	9	60	0	0	0
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05
	2009 Peak-Season Count	56	1,419	41	35	1,575	70	20	9	63	0	0	0
	CGR	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
	2009 Peak-Season Count	56	1,419	41	35	1,575	70	20	9	63	0	0	0
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
Hallandale Beach Boulevard at NE 14th Avenue	Committed Development Trips	0	243	67	50	240	0	86	7	140	0	0	0
	2012 Background Traffic	58	1,705	109	86	1,863	72	107	16	205	0	0	0
	Project IN/OUT Movement		IN			OUT	OUT						
	Project Distribution		40.00%			39.00%	3.00%						
	2012 Project Trips	0	15	0	0	14	1	0	0	0	0	0	0
	2012 Total Traffic	58	1,720	109	86	1,877	73	107	16	205	0	0	0
	Collected Count (09/23/09)	187	1,253	296	47	1,216	77	222	109	71	61	95	106
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	1.30	1.30	1.30	1.30	1.30	1.30	1.30	1.30	1.30	1.30	1.30	1.30
	2009 Peak-Season Count	243	1,629	385	61	1,581	100	289	142	92	79	124	138
	CGR	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
Hallandale Beach Boulevard at Diplomat Parkway	2009 Peak-Season Count	243	1,629	385	61	1,581	100	289	142	92	79	124	138
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	Committed Development Trips	23	360	0	0	231	10	0	0	0	14	0	15
	2012 Background Traffic	273	2,038	397	63	1,860	113	298	146	95	95	128	157
	Project IN/OUT Movement		IN			OUT	OUT				IN		
	Project Distribution		40.00%			42.00%	5.00%				6.00%		
	2012 Project Trips	0	15	0	0	15	2	0	0	0	2	0	0
	2012 Total Traffic	273	2,053	397	63	1,875	115	298	146	95	97	128	157
	Collected Count (03/23/10)	79	1,383	8	2	1,133	39	16	18	19	41	3	47
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01	1.01
Hallandale Beach Boulevard at Diplomat Parkway	2010 Peak-Season Count	80	1,397	8	2	1,144	39	16	18	19	41	3	47
	CGR	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
	2010 Peak-Season Count	80	1,397	8	2	1,144	39	16	18	19	41	3	47
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	Committed Development Trips	85	275	2	0	171	7	0	0	0	9	0	65
	2012 Background Traffic	167	1,700	10	2	1,338	47	16	18	19	51	3	113
	Project IN/OUT Movement		IN			OUT	OUT				IN		
	Project Distribution		46.00%			47.00%	3.00%				4.00%		
	2012 Project Trips	0	17	0	0	17	1	0	0	0	1	0	0
	2012 Total Traffic	167	1,717	10	2	1,355	48	16	18	19	52	3	113

TABLE K-1
TOTAL(2012) PM PEAK-HOUR, PEAK-SEASON TURNING-MOVEMENT VOLUMES
WALMART EXPANSION TRAFFIC IMPACT STUDY

INTERSECTION													
		EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Hallandale Beach Boulevard at Three Islands Boulevard	Collected Count (04/15/09)	408	914	0	0	971	81	0	0	0	192	0	210
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05
	2009 Peak-Season Count	428	960	0	0	1,020	85	0	0	0	202	0	221
	CGR	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
	2009 Peak-Season Count	478	960	0	0	964	85	0	0	0	211	0	221
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	Committed Development Trips	23	220	0	0	156	147	0	0	0	126	0	22
	2012 Background Traffic	515	1,209	0	0	1,149	235	0	0	0	343	0	250
	Project IN/OUT Movement	IN				OUT	IN				OUT		OUT
	Project Distribution	50.00%				25.00%	5.00%				25.00%		25.00%
	2012 Project Trips	18	0	0	0	9	2	0	0	0	9	0	9
	2012 Total Traffic	533	1,209	0	0	1,158	237	0	0	0	352	0	259
Hallandale Beach Boulevard at Driveway Connection	Collected Count (04/15/09)	0	829	0	0	1,064	124	0	0	0	0	0	141
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05
	2009 Peak-Season Count	0	870	0	0	1,117	130	0	0	0	0	0	148
	CGR	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
	2009 Peak-Season Count	0	870	0	0	901	130	0	0	0	0	0	148
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	Committed Development Trips	0	263	0	0	303	0	0	0	0	0	0	0
	2012 Background Traffic	0	1,159	0	0	1,231	134	0	0	0	0	0	152
	Project IN/OUT Movement		OUT			IN	IN						OUT
	Project Distribution		25.00%			5.00%	20.00%						25.00%
	2012 Project Trips	0	9	0	0	2	7	0	0	0	0	0	9
	2012 Total Traffic	0	1,168	0	0	1,233	141	0	0	0	0	0	161
Hallandale Beach Boulevard at South Ocean Drive	Collected Count (02/25/08)	658	96	849	20	63	45	34	726	8	73	693	647
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97	0.97
	2008 Peak-Season Count	638	93	824	19	61	44	33	704	8	71	672	628
	CGR	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	2009 Peak-Season Count	644	94	832	19	62	44	48	711	8	72	679	921
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	Committed Development Trips	88	0	175	0	0	0	195	44	0	0	43	108
	2012 Background Traffic	752	97	1,032	20	64	45	244	777	8	74	743	1,057
	Project IN/OUT Movement		OUT	OUT				IN					IN
	Project Distribution	15.00%		10.00%				10.00%					15.00%
	2012 Project Trips	5	0	4	0	0	0	4	0	0	0	0	5
	2012 Total Traffic	757	97	1,036	20	64	45	248	777	8	74	743	1,062
Three Islands Boulevard at Driveway Connection	Collected Count (04/15/09)	0	0	0	189	0	92	0	361	175	80	223	0
	Peak-Season Conversion Factor (PSCF) ⁽¹⁾	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05	1.05
	2009 Peak-Season Count	0	0	0	198	0	97	0	379	184	84	234	0
	CGR	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
	2009 Peak-Season Count	0	0	0	198	0	97	0	379	184	84	234	0
	Growth Rate	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%	1.00%
	Committed Development Trips	0	0	0	2	0	0	2	36	0	0	35	0
	2012 Background Traffic	0	0	0	206	0	100	2	426	190	87	276	0
	Project IN/OUT Movement				OUT		OUT			IN	IN		
	Project Distribution				50.00%		25.00%			55.00%	25.00%		
	2012 Project Trips	0	0	0	18	0	9	0	0	20	9	0	0
	2012 Total Traffic	0	0	0	224	0	109	2	426	210	96	276	0

NOTES:

1. PEAK SEASON CONVERSION FACTOR (PSCF) OBTAINED FROM 2008 FDOT TRANSPORTATION DVD.

BALANCED VOLUMES



**COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY**

Intersection: Hallandale Beach Boulevard at US-1

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	15	0	19	15	20	0	0	19	20	0	0
Village at Gulfstream Park	0	39	129	7	50	36	164	71	7	28	56	0
The European Club	0	10	0	7	6	7	0	0	25	25	0	0
Millennium Tower	0	3	0	1	1	2	0	0	4	4	0	0
Regency SPA	0	3	0	4	3	5	0	0	4	4	0	0
Oasis	0	44	0	40	57	16	0	0	32	13	0	0
Park Central	0	1	1	0	1	0	0	4	0	0	6	0
Hallandale Square	0	94	18	0	91	88	36	7	0	90	7	0
Domus Hallandale	0	0	24	7	0	0	36	25	10	0	17	0
Total	0	209	172	85	224	174	236	107	101	184	86	0

**COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY**

Intersection: Hallandale Beach Boulevard at NE 8th Avenue

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	54	0	0	54	0	0	0	0	0	0	0
Village at Gulfstream Park	0	74	0	0	93	0	0	0	0	0	0	0
The European Club	0	60	0	0	20	0	0	0	0	0	0	0
Millennium Tower	0	11	0	0	4	0	0	0	0	0	0	0
Regency SPA	0	11	0	0	12	0	0	0	0	0	0	0
Oasis	0	89	0	0	113	0	0	0	0	0	0	0
Park Central	0	1	0	0	1	0	0	0	0	0	0	0
Hallandale Square	0	-53	184	84	-48	0	232	7	0	0	7	0
Domus Hallandale	0	10	0	0	7	0	0	0	0	0	0	7
Total	0	257	184	84	256	0	232	7	0	0	7	7

COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY

Intersection: Hallandale Beach Boulevard at NE 10th Avenue

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	54	0	0	54	0	0	0	0	0	0	0
Village at Gulfstream Park	0	7	67	50	0	0	86	0	64	0	0	0
The European Club	0	60	0	0	20	0	0	0	0	0	0	0
Millennium Tower	0	11	0	0	4	0	0	0	0	0	0	0
Regency SPA	0	11	0	0	12	0	0	0	0	0	0	0
Oasis	0	89	0	0	113	0	0	0	0	0	0	0
Park Central	0	1	0	0	1	0	0	0	0	0	0	0
Hallandale Square	0	0	0	0	29	0	0	7	76	0	0	0
Domus Hallandale	0	10	0	0	7	0	0	0	0	0	0	0
Total	0	243	67	50	240	0	86	7	140	0	0	0

COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY

Intersection: Hallandale Beach Boulevard at NE 14th Avenue

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	54	0	0	54	6	0	0	0	6	0	0
Village at Gulfstream Park	0	71	0	0	50	0	0	0	0	0	0	0
The European Club	0	60	0	0	20	2	0	0	0	6	0	0
Millennium Tower	0	11	0	0	4	1	0	0	0	1	0	0
Regency SPA	0	11	0	0	12	1	0	0	0	1	0	0
Oasis	8	81	0	0	63	0	0	0	0	0	0	6
Park Central	1	0	0	0	0	0	0	0	0	0	0	1
Hallandale Square	8	68	0	0	26	0	0	0	0	0	0	3
Domus Hallandale	6	4	0	0	2	0	0	0	0	0	0	5
Total	23	360	0	0	231	10	0	0	0	14	0	15

COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY

Intersection: Hallandale Beach Boulevard at Diplomat Parkway

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	60	0	0	60	7	0	0	0	8	0	0
Village at Gulfstream Park	7	64	0	0	45	0	0	0	0	0	0	5
The European Club	1	63	2	0	22	0	0	0	0	1	0	0
Millennium Tower	0	0	0	0	0	0	0	0	0	0	0	0
Regency SPA	0	12	0	0	13	0	0	0	0	0	0	0
Oasis	77	4	0	0	3	0	0	0	0	0	0	60
Park Central	0	0	0	0	0	0	0	0	0	0	0	0
Hallandale Square	0	68	0	0	26	0	0	0	0	0	0	0
Domus Hallandale	0	4	0	0	2	0	0	0	0	0	0	0
Total	85	275	2	0	171	7	0	0	0	9	0	65

COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY

Intersection: Hallandale Beach Boulevard at Three Islands Boulevard

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	68	0	0	67	8	0	0	0	8	0	0
Village at Gulfstream Park	0	64	0	0	45	0	0	0	0	0	0	0
The European Club	23	0	0	0	0	139	0	0	0	118	0	22
Millennium Tower	0	0	0	0	0	0	0	0	0	0	0	0
Regency SPA	0	12	0	0	13	0	0	0	0	0	0	0
Oasis	0	4	0	0	3	0	0	0	0	0	0	0
Park Central	0	0	0	0	0	0	0	0	0	0	0	0
Hallandale Square	0	68	0	0	26	0	0	0	0	0	0	0
Domus Hallandale	0	4	0	0	2	0	0	0	0	0	0	0
Total	23	220	0	0	156	147	0	0	0	126	0	22

COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY

Intersection: Hallandale Beach Boulevard at Driveway Connection

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	76	0	0	75	0	0	0	0	0	0	0
Village at Gulfstream Park	0	64	0	0	45	0	0	0	0	0	0	0
The European Club	0	35	0	0	139	0	0	0	0	0	0	0
Millennium Tower	0	0	0	0	0	0	0	0	0	0	0	0
Regency SPA	0	12	0	0	13	0	0	0	0	0	0	0
Oasis	0	4	0	0	3	0	0	0	0	0	0	0
Park Central	0	0	0	0	0	0	0	0	0	0	0	0
Hallandale Square	0	68	0	0	26	0	0	0	0	0	0	0
Domus Hallandale	0	4	0	0	2	0	0	0	0	0	0	0
Total	0	263	0	0	303	0	0	0	0	0	0	0

COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY

Intersection: Hallandale Beach Boulevard at South Ocean Drive

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	0	76	0	0	0	75	38	0	0	37	0
Village at Gulfstream Park	32	0	32	0	0	0	23	0	0	0	0	22
The European Club	18	0	17	0	0	0	69	0	0	0	0	70
Millennium Tower	0	0	0	0	0	0	0	0	0	0	0	0
Regency SPA	0	0	12	0	0	0	13	6	0	0	6	0
Oasis	2	0	2	0	0	0	1	0	0	0	0	2
Park Central	0	0	0	0	0	0	0	0	0	0	0	0
Hallandale Square	34	0	34	0	0	0	13	0	0	0	0	13
Domus Hallandale	2	0	2	0	0	0	1	0	0	0	0	1
Total	88	0	175	0	0	0	195	44	0	0	43	108

COMMITTED DEVELOPMENT
WALMART EXPANSION TRAFFIC STUDY


Intersection: Three Islands Boulevard at Driveway Connection

Committed Development	EBLT	EBTH	EBRT	WBLT	WBTH	WBRT	NBLT	NBTH	NBRT	SBLT	SBTH	SBRT
Ocean Marine Yacht Club	0	0	0	0	0	0	0	8	0	0	8	0
Village at Gulfstream Park	0	0	0	0	0	0	0	0	0	0	0	0
The European Club	0	0	0	2	0	0	2	28	0	0	27	0
Millennium Tower	0	0	0	0	0	0	0	0	0	0	0	0
Regency SPA	0	0	0	0	0	0	0	0	0	0	0	0
Oasis	0	0	0	0	0	0	0	0	0	0	0	0
Park Central	0	0	0	0	0	0	0	0	0	0	0	0
Hallandale Square	0	0	0	0	0	0	0	0	0	0	0	0
Domus Hallandale	0	0	0	0	0	0	0	0	0	0	0	0
Total	0	0	0	2	0	0	2	36	0	0	35	0

IMPACT ANALYSIS
FOR

OCEAN MARINE YACHT CLUB

HALLANDALE, FLORIDA



OWNER

OCEAN MARINE YACHT CLUB, INC.

DeSanti & Associates, Inc.
9055 Ibis Blvd.
West Palm Beach, Fl 33412
(561) 630-4877

PalmeriDesign
44 Ironwood Way
Palm Beach Gardens, Fl 33418
(561) 242-2428

Carnahan Proctor & Cross, Inc.
6101 W. Atlantic Blvd.
Margate, Fl. 33063
(954) 972-3959

3/07/03 Submittal
City Council Meeting

#PH-17



TRAFFIC IMPACT ANALYSIS


OCEAN MARINE YACHT CLUB HALLANDALE, FL

Prepared for:
Security Management Corporation
Hallandale, Florida

040987000
January 2002
Revised February 2003
© Kimley-Horn and Associates, Inc.
4431 Embarcadero Drive
West Palm Beach, Florida 33407
561/845-0665 TEL
561/882-3703 FAX



Kimley-Horn
and Associates, Inc.



LEGEND

151 PM PEAK HOUR PROJECT TRAFFIC
50% PERCENT PROJECT ASSIGNMENT

FIGURE 2
OCEAN MARINE YACHT CLUB
PROJECT TRAFFIC ASSIGNMENT

NOT TO SCALE

THE EUROPEAN CLUB
MIXED-USE DEVELOPMENT

**TRAFFIC IMPACT
AND OPERATIONS REPORT**

June 20, 2005

Prepared for:
Architectura Group

By:



Calvin, Giordano & Associates, Inc.

Engineers Surveyors Planners

1800 Eller Drive, Suite 600


Fort Lauderdale, Florida 33316

Phone: (954) 921-7781 Fax: (954) 921-8807

Scott Brunner
6-20-2005

Scott Brunner, P.E.
Florida P.E. #47612

Figure 1: Site Location Map



PROJECT LOCATION & ACCESS

There are four (4) project access driveways anticipated to serve the site. The access points configurations are as follows (numbers are keyed to Figure 1):

Access #1: Right-out-only driveway onto Hallandale Beach Boulevard centered approximately 185 feet west of the west right-of-way line of Three Islands Boulevard. This vehicular access connection has preliminary approval from the Florida Department of Transportation as part of the permit pre-application process. (This connection is currently right-in/right-out, and therefore the new access configuration will bring the access connection into full conformance with FDOT access management standards)

Access #2: Right-in-only driveway from southbound Three Islands Boulevard centered approximately 125 feet north of the north right-of-way line of Hallandale Beach Boulevard. This connection will expand into three one-way westbound valet/drop-off lanes once it becomes internal to the site. (This new configuration will eliminate outbound traffic from entering onto Three Islands Boulevard within close proximity to the signalized intersection at Hallandale Beach Boulevard, and therefore adheres to Broward County Traffic Engineering policy of discouraging access onto intersection approaches within 200 feet of a signalized intersection).

Access #3: Right-in/right-out only driveway on Three Islands Boulevard centered approximately 355 feet north of the north right-of-way of Hallandale Beach Boulevard.

Access #4: In-only driveway from Three Islands Boulevard centered approximately 400 feet north of the north right-of-way line of Hallandale Beach Boulevard. This connection will expand into three one-way westbound bank drive-thru lanes once it becomes internal to the site. (This new configuration will eliminate outbound left turns from the site onto westbound Three Islands Boulevard, thus eliminating some existing potential turning movement conflicts.

Access

EXISTING TRANSPORTATION SYSTEM CHARACTERISTICS

Roadway Classification and Permitting Authority

The *European Club* project site is served by several vicinity roadways. On the project south limits is Hallandale Beach Boulevard, which is a six-lane-divided east/west roadway that is Functionally Classified as a State Principal Arterial, the highest classification of non-expressway roadways. Hallandale Beach Boulevard is part of the State Highway System (SR-858), and therefore FDOT is the primary permitting authority. Traffic control devices, such as traffic signals are maintained by the Broward County Traffic Engineering Division (BCTED).

TABLE 2 - TRIP GENERATION ANALYSIS

Land Use	ITE Land Use Code	Intensity		ITE 7th Edition Equation	Daily Trips	AM Peak Hour of Adjacent Street					PM Peak Hour of Adjacent Street				
						Trips	%	In	%	Out	Trips	%	In	%	Out
EXISTING USES															
Drive-in Bank	912 912 912 912	10,000	sq. ft.	$T = 37.08 (X)$ $T = 45.74 (X)$ $T = 12.34 (X)$ $T = 182.34(X) + 256.87$											
SUBTOTAL					2,080	123	56%	69	44%	54	457	50%	229	50%	229
General Office	710 BC* 710 710	9,375	sq. ft.	$\ln(T) = 0.81 \ln(X) - 0.12$ $\ln(T) = 0.737 \ln(X) + 1.831$ $\ln(T) = 0.80 \ln(X) + 1.55$ $T = 11.01(X)$											
SUBTOTAL					103	28	88%	25	12%	3	32	17%	6	83%	27
EXISTING TOTAL NUMBER OF TRIPS					103	28		25		3	32		6		27
					2,183	152		94		57	490		235		256
PROPOSED USES															
Drive-in Bank	912 912 912 912	8,129	sq. ft.	$T = 37.08 (X)$ $T = 45.74 (X)$ $T = 12.34 (X)$ $T = 182.34(X) + 256.87$											
SUBTOTAL					1,739	100	56%	56	44%	44	372	50%	186	50%	186
General Office	710 BC* 710 710	72,092	sq. ft.	$\ln(T) = 0.81 \ln(X) - 0.12$ $\ln(T) = 0.737 \ln(X) + 1.831$ $\ln(T) = 0.80 \ln(X) + 1.55$ $T = 11.01(X)$											
Internalization		15%			794	144	88%	127	12%	17	146	17%	25	83%	121
SUBTOTAL					119	22		19		3	22		4		18
Specialty Retail	814 814 814 814	6,009	sq. ft.	N/A $T = 2.40(X) + 21.48$											
Internalization		15%			295	0		0		0	36	44%	16	56%	20
SUBTOTAL					44	0		0		0	5		2		3
Gym / Spa	492 BC* 492 492	34,732	sq. ft.	$T = 2.60 (X)$ $T = 4.73 (X)$ $T = 1.21 (X)$ $T = 32.93 (X)$											
Internalization		25%			1144	42	42%	18	58%	24	164	51%	84	49%	80
SUBTOTAL					286	11		5		6	41		21		20
Hotel	310 BC* 310 310	155	rooms	$T = 0.69 (X) + 4.32$ $T = 0.62 (X)$ $\ln(T) = 1.24 \ln(X) - 2.00$ $T = 8.95 (X) - 373.16$											
Internalization		25%			1014	70	61%	43	39%	27	96	53%	51	47%	45
SUBTOTAL					254	18		11		7	24		13		11
High-Rise Residential Condomi	232 BC* 232 232	118	units	$T = 0.35 (X)$ $T = 0.36 (X)$ $T = 0.34 (X)$ $T = 4.18 (X)$											
Internalization		15%			493	40	19%	8	81%	32	42	62%	26	38%	16
SUBTOTAL					74	6		1		5	6		4		2
Ballroom	NA	4,839	sq. ft.												
Restaurant	932 BC* 932 932	4,839	sq. ft.	$T = 20.00 (X)$ $T = 9.59 (X)$ $T = 11.52 (X)$ $T = 127.15 (X)$											
Internalization		25%			615	56	52%	29	48%	27	46	61%	28	39%	18
SUBTOTAL					154	14		7		7	12		7		5
Transit/Taxi/Walk Trip Reduction					461	42		22		20	35		21		14
PROPOSED TOTAL NUMBER OF TRIPS					516	36		22		13	77		35		42
NET NEW TRIPS GENERATED:					2,463	196		122		74	226		95		129

*(BC) Using Broward County Rates and Equations

Mart/Fire Station is operating in an isolated fashion (off-system), and therefore local controller timings were obtained for this signal. (As indicated earlier in the report, the signal timing data provided by BCTED has been included in **Appendix D**).

Hallandale Beach Boulevard @ Diplomat Parkway

The operational analysis of this intersection is summarized in **Tables 4A** and **4B** for future Year 2007 conditions during the AM and PM peak periods, respectively. The first set of columns reflects Year 2007 exiting-plus-background traffic only (no project). The second set of columns reflects Year 2007 total traffic conditions with the project. (The first and second sets of analysis were performed using existing signal timing parameters). The third set of columns reflects Year 2007 total traffic conditions with modifications to the signal system, such as signal timing and phasing changes in order to better re-balance and optimize operations with the new project traffic.

As be seen from the tables, the future Year 2007 conditions *with or without* the project operate at **LOS C** or **LOS D** under the existing signal timing parameters. However, under a revised, more optimized signal operations plan, the level of service can potentially be improved to **LOS B** during the AM peak hour. During the PM peak hour, the potential benefit of signal optimization is more limited, however, overall vehicle delay may be able to be improved by approximately 5 seconds.

Hallandale Beach Boulevard @ Three Islands Boulevard

The operational analysis of this intersection is summarized in **Tables 5A** and **5B** for future Year 2007 conditions during the AM and PM peak periods, respectively. As be seen from the tables, the future Year 2007 conditions *with or without* the project operate at **LOS F** during the PM peak period under the existing signal timing parameters. This poor operational conditions should be somewhat expected due to the fact that systems coordination needs to be re-evaluated every several years, and such an evaluation has not been performed recently, and will certainly be necessary in the future. However, under a revised, more optimized signal operations plan, the level of service can potentially be improved back up to **LOS C** with the project.

Signalized Intersection Capacity Analysis

5: Sea Walk Pointe/Wal Mart & Three Islands Blvd.

AM Future (EXISTING + BACKUP)

Future w/o Site Traffic-A.M. Peak Hour

6/17/2005

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBU	NBL	NBT	NBR	SBU	SBL	SBT	SBR
Lane Configurations														
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)				4.0	4.0				4.0	4.0		4.0	4.0	
Lane Util. Factor				0.97	1.00				0.91	1.00		1.00	0.91	
Flt Protected				1.00	0.85				1.00	0.85		1.00	1.00	
Satd. Flow (prot)				0.95	1.00				1.00	1.00		0.95	1.00	
Flt Permitted				3433	1583				5080	1583		1770	5085	
Satd. Flow (perm)				0.95	1.00				0.91	1.00		0.35	1.00	
Volume (vph)	0	0	0	272	0	82	8	0	402	270	16	120	1018	0
Peak-hour factor, PHF	0.25	0.25	0.25	0.86	0.86	0.86	0.80	0.80	0.80	0.80	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	0	0	316	0	95	10	0	502	338	17	130	1107	0
RTOR Reduction (vph)	0	0	0	0	54	0	0	0	0	239	0	0	0	0
Lane Group Flow (vph)	0	0	0	316	41	0	0	0	512	99	0	147	1107	0
Turn Type	Perm			Perm			Perm							
Protected Phases		4			3				2		1	1	6	
Permitted Phases	4			3			2			2	6	6		
Actuated Green, G (s)				24.2	24.2				15.7	15.7		24.8	24.8	
Effective Green, g (s)				26.2	26.2				17.7	17.7		26.3	26.3	
Actuated g/C Ratio				0.43	0.43				0.29	0.29		0.43	0.43	
Clearance Time (s)				6.0	6.0				6.0	6.0		4.0	5.5	
Vehicle Extension (s)				3.0	3.0				3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)				1487	686				1348	463		368	2211	
v/s Ratio Prot					0.03							0.03	0.22	
v/s Ratio Perm				0.09					0.11	0.06		0.14		
v/c Ratio				0.21	0.06				0.38	0.21		0.40	0.50	
Uniform Delay, d1				10.7	10.0				17.0	16.1		10.8	12.4	
Progression Factor				1.00	1.00				1.00	1.00		1.00	1.00	
Incremental Delay, d2				0.1	0.0				0.2	0.2		0.7	0.2	
Delay (s)				10.8	10.0				17.2	16.4		11.5	12.5	
Level of Service				B	B				B	B		B	B	
Approach Delay (s)		0.0												
Approach LOS		A												

5: Sea Walk Pointe/Wal Mart & Three Islands Blvd.
Calvin Giordano

1 .. Signalized Intersection Capacity Analysis

5: Sea Walk Pointer/Wal Mart & Three Islands Blvd.

AM TOTAL TRAFFIC W/ PROTE


















6/17/2005

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBU	NBL	NBT	NBR	SBU	SBL	SBT	SBR
Lane Configurations														
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Lane Util. Factor	0.97	1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00	0.85	1.00	1.00	0.91	1.00
Flt Protected														
Satd. Flow (prot)	3433	1583	1583	3433	1583	1583	3433	1583	1583	1583	1770	5085	1770	5085
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00	0.85	1.00	1.00	0.91	1.00
Satd. Flow (perm)	3433	1583	1583	3433	1583	1583	3433	1583	1583	1583	1770	5085	1770	5085
Volume (vph)	0	0	0	282	0	82	8	0	414	270	16	120	1018	0
Peak-hour factor, PHF	0.25	0.25	0.25	0.86	0.86	0.86	0.80	0.80	0.80	0.80	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	0	0	328	0	95	10	0	518	338	17	130	1107	0
RTOR Reduction (vph)	0	0	0	0	54	0	0	0	0	238	0	0	0	0
Lane Group Flow (vph)	0	0	0	328	41	0	0	0	528	100	0	147	1107	0
Turn Type	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	pm+pt	pm+pt	pm+pt	pm+pt
Protected Phases	4	4	4	3	3	3	2	2	2	2	1	1	1	1
Permitted Phases	4	4	4	3	3	3	2	2	2	2	6	6	6	6
Actuated Green, G (s)				24.2	24.2	24.2			16.0	16.0			25.1	25.1
Effective Green, g (s)				26.2	26.2	26.2			18.0	18.0			26.6	26.6
Actuated g/C Ratio				0.43	0.43	0.43			0.30	0.30			0.44	0.44
Clearance Time (s)				6.0	6.0	6.0			6.0	6.0			5.5	5.5
Vehicle Extension (s)				3.0	3.0	3.0			3.0	3.0			3.0	3.0
Lane Grp Cap (vph)				1479	682	682			1365	469			364	2225
v/s Ratio Prot				0.03	0.03	0.03			0.11	0.06			0.03	0.22
v/s Ratio Perm				c0.10					0.39	0.21			0.15	
Uniform Delay, d1				0.22	0.06	0.06			17.0	16.1			0.40	0.50
Progression Factor				10.9	10.1	10.1			1.00	1.00			10.8	12.3
Incremental Delay, d2				1.00	1.00	1.00			0.2	0.2			1.00	1.00
Delay (s)				0.1	0.0	0.0			17.2	16.3			0.7	0.2
Level of Service				B	B	B			B	B			B	B
Approach Delay (s)				0.0					11.5	12.5			11.5	12.5
Approach LOS				A					B	B			B	B

AM 2007 Project
Calvin Giordano

HCM Signalized Intersection Capacity Analysis
4: Hallandale Beach Blvd. & Three Islands Blvd.

Future w/o Site Traffic-A.M. Peak Hour
6/19/2005

												
Movement	EBU	EBL	EBT	EBR	WBU	WBL	WBT	WBR	NBL	NBT	NBR	SBU
Lane Configurations												
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.0	4.0			4.0	4.0	4.0				
Lane Util. Factor		0.97	0.91			1.00	0.91	1.00				
Frt		1.00	1.00			1.00	1.00	0.85				
Flt Protected		0.95	1.00			0.95	1.00	1.00				
Satd. Flow (prot)		3433	5085			1770	5085	1583				
Flt Permitted		0.95	1.00			0.95	1.00	1.00				
Satd. Flow (perm)		3433	5085			1770	5085	1583				
Volume (vph)	6	521	1475	0	2	0	1481	185	0	0	0	4
Peak-hour factor, PHF	0.92	0.95	0.95	0.95	0.92	0.93	0.93	0.93	0.25	0.25	0.25	0.92
Adj. Flow (vph)	7	548	1553	0	2	0	1592	199	0	0	0	4
RTOR Reduction (vph)	0	0	0	0	0	0	0	80	0	0	0	0
Lane Group Flow (vph)	0	555	1553	0	0	2	1592	119	0	0	0	0
Turn Type	Prot	Prot			Prot	Prot		Perm				Perm
Protected Phases	11	1	6		5	5	2					
Permitted Phases												
Actuated Green, G (s)		26.0	119.7			1.3	95.0	95.0				4
Effective Green, g (s)		27.0	120.7			2.3	96.0	96.0				
Actuated g/C Ratio		0.17	0.75			0.01	0.60	0.60				
Clearance Time (s)		5.0	5.0			5.0	5.0	5.0				
Vehicle Extension (s)		3.0	3.0			3.0	3.0	3.0				
Lane Grp Cap (vph)		579	3836			25	3051	950				
v/s Ratio Prot		c0.16	0.31			0.00	c0.31					
v/s Ratio Perm												
v/c Ratio		0.96	0.40			0.08	0.52	0.13				
Uniform Delay, d1		65.9	6.9			77.8	18.6	13.8				
Progression Factor		0.93	1.06			1.00	1.00	1.00				
Incremental Delay, d2		23.0	0.2			1.4	0.6	0.3				
Delay (s)		84.3	7.6			79.2	19.3	14.1				
Level of Service		F	A			E	B	B				
Approach Delay (s)			27.8				18.8					
Approach LOS			C				B			0.0		
										A		

Intersection Summary

HCM Average Control Delay	49.4	HCM Level of Service	D
HCM Volume to Capacity ratio	0.71		
Actuated Cycle Length (s)	160.0	Sum of lost time (s)	8.0
Intersection Capacity Utilization	81.8%	ICU Level of Service	D
Analysis Period (min)	15		

! Phase conflict between lane groups.

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
4: Hallandale Beach Blvd. & Three Islands Blvd.

TOTAL TRAFFIC W/PROJECT

6/19/2005

	EBU	EBL	EBT	EBR	WBU	WBL	WBT	WBR	NBL	NBT	NBR	SBU
Movement												
Lane Configurations		↖↗	↖↖↗			↖	↖↖↗	↗				
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.0	4.0			4.0	4.0	4.0				
Lane Util. Factor		0.97	0.91			1.00	0.91	1.00				
Frt		1.00	1.00			1.00	1.00	0.85				
Flt Protected		0.95	1.00			0.95	1.00	1.00				
Satd. Flow (prot)		3433	5085			1770	5085	1583				
Flt Permitted		0.95	1.00			0.95	1.00	1.00				
Satd. Flow (perm)		3433	5085			1770	5085	1583				
Volume (vph)	6	541	1475	0	2	0	1443	278	0	0	0	25
Peak-hour factor, PHF	0.92	0.95	0.95	0.95	0.92	0.93	0.93	0.93	0.25	0.25	0.25	0.92
Adj. Flow (vph)	7	569	1553	0	2	0	1552	299	0	0	0	27
RTOR Reduction (vph)	0	0	0	0	0	0	0	120	0	0	0	0
Lane Group Flow (vph)	0	576	1553	0	0	2	1552	179	0	0	0	0
Turn Type	Prot	Prot			Prot	Prot		Perm				
Protected Phases	11	1	6		5	5	2					Perm
Permitted Phases												
Actuated Green, G (s)		26.0	119.7			1.3	95.0	95.0				4
Effective Green, g (s)		27.0	120.7			2.3	96.0	96.0				
Actuated g/C Ratio		0.17	0.75			0.01	0.60	0.60				
Clearance Time (s)		5.0	5.0			5.0	5.0	5.0				
Vehicle Extension (s)		3.0	3.0			3.0	3.0	3.0				
Lane Grp Cap (vph)		579	3836			25	3051	950				
v/s Ratio Prot		c0.17	0.31			0.00	c0.31					
v/s Ratio Perm												
v/c Ratio		0.99	0.40			0.08	0.51	0.19				
Uniform Delay, d1		66.4	6.9			77.8	18.4	14.4				
Progression Factor		0.93	1.07			1.00	1.00	1.00				
Incremental Delay, d2		31.3	0.2			1.4	0.6	0.4				
Delay (s)		93.0	7.7			79.2	19.0	14.9				
Level of Service		F	A			E	B	B				
Approach Delay (s)			30.8				18.4					
Approach LOS			C				B			0.0		
										A		
Intersection Summary												
HCM Average Control Delay		57.0			HCM Level of Service			E				
HCM Volume to Capacity ratio		0.73										
Actuated Cycle Length (s)		160.0			Sum of lost time (s)			8.0				
Intersection Capacity Utilization		82.8%			ICU Level of Service			E				
Analysis Period (min)		15										
! Phase conflict between lane groups.												
c Critical Lane Group												

ICM Signalized Intersection Capacity Analysis
7: Hallandale Beach Blvd. & Diplomat Pkwy.

AM Future (EXISTING + D...)
Future w/o Site Traffic-A.M. Peak Hour
6/17/2005

Movement	EBU	EBL	EBT	EBR	WBU	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Lane Util. Factor	1.00	1.00	0.91	1.00	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Fit Protected	1.00	1.00	0.99	1.00	1.00	1.00	0.99	1.00	1.00	0.88	1.00	1.00	0.89	1.00
Satd. Flow (prot)	0.95	0.95	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	0.95	1.00	0.95	1.00
Fit Permitted	1770	1770	5053	1770	1770	1770	5055	1770	1770	1637	1770	1770	1655	1655
Satd. Flow (perm)	0.04	0.04	1.00	0.06	1.00	0.06	1.00	0.67	0.67	1.00	0.95	1.00	1.00	1.00
Volume (vph)	37	161	1879	84	4	27	1852	76	27	4	16	107	31	89
Peak-hour factor, PHF	0.86	0.86	0.86	0.86	0.95	0.95	0.95	0.95	0.64	0.64	0.64	0.83	0.83	0.83
Adj. Flow (vph)	43	187	2185	98	4	28	1949	80	42	6	25	129	37	107
RTOR Reduction (vph)	0	0	2	0	0	0	2	0	0	23	0	0	82	0
Lane Group Flow (vph)	0	230	2281	0	0	32	2027	0	42	8	0	129	62	0
Turn Type	Prot	pm+pt	Prot	pm+pt	Prot	pm+pt	Perm	Perm	Prot	pm+pt	Prot	pm+pt	Prot	pm+pt
Protected Phases	1	1	6	5	5	5	2	2	4	4	4	3	8	8
Permitted Phases	6	6	109.2	88.9	88.9	88.9	84.8	84.8	9.3	9.3	9.3	13.4	28.7	28.7
Actuated Green, G (s)	119.3	119.3	111.2	92.9	92.9	92.9	86.8	86.8	11.3	11.3	11.3	15.4	30.7	30.7
Effective Green, g (s)	121.3	121.3	111.2	92.9	92.9	92.9	86.8	86.8	11.3	11.3	11.3	15.4	30.7	30.7
Actuated g/C Ratio	0.76	0.76	0.70	0.58	0.58	0.58	0.54	0.54	0.07	0.07	0.07	0.10	0.19	0.19
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	384	3512	3512	127	2742	127	2742	127	2742	116	116	170	318	318
v/s Ratio Prot	c0.11	c0.45	c0.45	0.01	c0.40	0.01	c0.40	0.01	c0.40	0.00	0.00	c0.07	0.04	0.04
v/s Ratio Perm	0.34	0.34	0.34	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14	0.14
v/c Ratio	0.60	0.60	0.65	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25
Uniform Delay, d1	45.0	45.0	13.6	15.1	15.1	15.1	28.0	28.0	71.5	69.4	69.4	70.5	54.3	54.3
Progression Factor	1.00	1.00	1.00	1.06	1.06	1.06	1.27	1.27	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	2.5	2.5	0.9	0.8	0.8	0.8	1.4	1.4	4.0	0.2	0.2	17.5	0.3	0.3
Delay (s)	47.5	47.5	14.5	16.8	16.8	16.8	37.0	37.0	75.5	69.7	69.7	88.0	54.6	54.6
Level of Service	D	D	B	B	B	B	D	D	E	E	E	F	D	D
Approach Delay (s)	17.5	17.5	17.5	36.7	36.7	36.7	36.7	36.7	73.1	73.1	73.1	70.4	70.4	70.4
Approach LOS	B	B	B	D	D	D	D	D	E	E	E	F	D	D

7: Hallandale Beach Blvd. & Diplomat Pkwy.
Calvin Giordano

AM Signalized Intersection Capacity Analysis
7: Hallandale Beach Blvd. & Diplomat Pkwy.

AM TOTAL TRAFFIC W/P1

6/17/2005

Movement	EBU	EBL	EBT	EBR	WBU	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Ideal Flow (vphpl)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Total Lost time (s)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Lane Util. Factor	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95
Frt	1770	5053	5053	5053	1770	5053	5053	5053	1770	1637	1637	1770	1655	1655
Satd. Flow (prot)	0.04	1.00	1.00	1.00	0.06	1.00	1.00	1.00	0.67	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	82	5053	5053	5053	105	5053	5053	5053	1239	1637	1637	1770	1655	1655
Volume (vph)	37	161	1898	84	4	28	1853	77	27	4	16	108	31	89
Peak-hour factor, PHF	0.86	0.86	0.86	0.86	0.95	0.95	0.95	0.95	0.64	0.64	0.64	0.83	0.83	0.83
Adj. Flow (vph)	43	187	2207	98	4	29	1951	81	42	6	25	130	37	107
RTOR Reduction (vph)	0	0	2	0	0	0	2	0	0	23	0	0	82	0
Lane Group Flow (vph)	0	230	2303	0	0	33	2030	0	42	8	0	130	62	0
Turn Type	Prot	pm+pt	pm+pt	Prot	pm+pt	Perm	Perm	Perm	Perm	Prot	Prot	Prot	Prot	Prot
Protected Phases	1	1	6	5	5	2	2	2	4	4	4	3	8	8
Permitted Phases	6	6	6	2	2	2	2	2	4	4	4	3	8	8
Actuated Green, G (s)	119.2	109.0	111.0	88.9	84.7	84.7	84.7	84.7	9.3	9.3	9.3	13.5	28.8	28.8
Effective Green, g (s)	121.2	111.0	111.0	92.9	86.7	86.7	86.7	86.7	11.3	11.3	11.3	15.5	30.8	30.8
Actuated g/C Ratio	0.76	0.69	0.69	0.58	0.54	0.54	0.54	0.54	0.07	0.07	0.07	0.10	0.19	0.19
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	384	3506	3506	125	2739	2739	2739	2739	88	116	116	171	319	319
v/s Ratio Prot	c0.11	c0.46	c0.46	0.01	c0.40	c0.40	c0.40	c0.40	c0.03	0.00	0.00	c0.07	0.04	0.04
v/s Ratio Perm	0.34	0.60	0.66	0.26	0.74	0.74	0.74	0.74	0.48	0.07	0.07	0.76	0.20	0.20
Uniform Delay, d1	45.0	13.8	13.8	15.3	28.1	28.1	28.1	28.1	71.5	69.4	69.4	70.4	54.2	54.2
Progression Factor	1.00	1.00	1.00	1.01	1.28	1.28	1.28	1.28	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	2.5	1.0	1.0	0.9	1.4	1.4	1.4	1.4	4.0	0.2	0.2	17.9	0.3	0.3
Delay (s)	47.5	14.8	14.8	16.4	37.4	37.4	37.4	37.4	75.5	69.7	69.7	88.3	54.5	54.5
Level of Service	D	B	B	B	D	D	D	D	E	E	E	F	D	D
Approach Delay (s)	17.7	17.7	17.7	37.1	37.1	37.1	37.1	37.1	73.1	73.1	73.1	70.5	70.5	70.5
Approach LOS	B	B	B	D	D	D	D	D	E	E	E	F	D	D

1 Signalized Intersection Capacity Analysis

Sea Walk Pointe/Wal Mart & Three Islands Blvd.

PM FUTURE (EXISTING + BACK-ND)
Future w/o Site Traffic-P.M. Peak Hour

6/17/2005

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBU	NBL	NBT	NBR	SBU	SBL	SBT	SBR
Lane Configurations														
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Flt Protected	0.93	0.93	0.93	1.00	0.85	0.85	1.00	0.85	1.00	0.85	1.00	0.85	1.00	0.91
Satd. Flow (prot)	0.98	0.98	0.98	0.95	1.00	1.00	0.95	1.00	1.00	0.85	1.00	0.95	1.00	1.00
Flt Permitted	1695	1695	1695	3433	1583	1583	3433	1583	1583	1583	1770	1583	1770	1583
Satd. Flow (perm)	0.75	0.75	0.75	0.50	1.00	1.00	0.50	1.00	1.00	0.94	1.00	0.13	1.00	1.00
Volume (vph)	2	0	2	472	0	212	2	4	944	464	37	122	639	2
Peak-hour factor, PHF	0.25	0.25	0.25	0.86	0.86	0.86	0.80	0.80	0.80	0.80	0.92	0.92	0.92	0.92
Adj. Flow (vph)	8	0	8	549	0	247	2	5	1180	580	40	133	695	2
RTOR Reduction (vph)	0	8	0	0	171	0	0	0	0	354	0	0	0	0
Lane Group Flow (vph)	0	8	0	549	76	0	0	0	1187	226	0	173	697	0
Turn Type	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm
Protected Phases	4	4	4	3	3	3	2	2	2	2	1	1	1	1
Permitted Phases	4	4	4	3	3	3	2	2	2	2	1	1	1	1
Actuated Green, G (s)	2.5	2.5	2.5	24.8	24.8	24.8	31.9	31.9	31.9	31.9	42.6	42.6	42.6	42.6
Effective Green, g (s)	4.0	4.0	4.0	26.8	26.8	26.8	33.9	33.9	33.9	33.9	44.1	44.1	44.1	44.1
Actuated g/C Ratio	0.05	0.05	0.05	0.31	0.31	0.31	0.39	0.39	0.39	0.39	0.51	0.51	0.51	0.51
Clearance Time (s)	5.5	5.5	5.5	6.0	6.0	6.0	6.0	6.0	6.0	6.0	4.0	4.0	4.0	4.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	60	60	60	557	488	488	1855	618	1855	618	228	2580	2580	2580
v/s Ratio Prot														
v/s Ratio Perm														
v/c Ratio	c0.01	c0.01	c0.01	c0.30	0.05	0.05	0.25	0.14	0.25	0.14	c0.05	0.14	0.14	0.14
Uniform Delay, d1	0.14	0.14	0.14	0.99	0.16	0.16	0.64	0.37	0.64	0.37	c0.33	0.37	0.37	0.37
Progression Factor	39.8	39.8	39.8	29.9	21.8	21.8	21.5	18.9	21.5	18.9	14.5	12.2	12.2	12.2
Incremental Delay, d2	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Delay (s)	1.1	1.1	1.1	34.2	0.2	0.2	0.7	0.4	0.7	0.4	13.5	0.1	0.1	0.1
Level of Service	D	D	D	E	C	C	C	B	C	B	C	B	B	B
Approach Delay (s)	40.9	40.9	40.9	64.0	22.0	22.0	22.3	19.2	22.3	19.2	27.9	12.3	12.3	12.3
Approach LOS	D	D	D	D	D	D	D	D	D	D	D	D	D	D

5: Sea Walk Pointe/Wal Mart & Three Islands Blvd.
Calvin Giordano

Signalized Intersection Capacity Analysis

Sea Walk Pointe/Wal Mart & Three Islands Blvd.

PM FUTURE ~~EXISTING~~ - BAY

Future with Site Traffic-P.M. Peak Hour

TOTAL TRAFFIC w/ PROJECT 6/17/2005

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBU	NBL	NBT	NBR	SBU	SBL	SBT	SBR
Lane Configurations	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Ideal Flow (vphpl)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Total Lost time (s)	1.00	0.93	0.98	1.00	0.97	1.00	1.00	0.91	1.00	1.00	1.00	1.00	0.91	1.00
Lane Util. Factor	0.93	0.98	0.95	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	0.95	1.00	1.00
Flt Protected	1695	3433	1583	5084	1583	5084	1583	5084	1583	1770	5083	1770	5083	1770
Satd. Flow (prot)	0.75	0.50	1.00	0.94	1.00	0.94	1.00	0.94	1.00	0.94	1.00	0.94	1.00	0.94
Flt Permitted	1303	1807	1583	4756	1583	4756	1583	4756	1583	220	5083	220	5083	220
Satd. Flow (perm)	0.25	0.25	0.25	0.86	0.86	0.86	0.80	0.80	0.80	0.80	0.80	0.80	0.80	0.80
Volume (vph)	2	0	2	474	0	212	2	4	972	464	37	122	666	2
Peak-hour factor, PHF	0.25	0.25	0.25	0.86	0.86	0.86	0.80	0.80	0.80	0.80	0.92	0.92	0.92	0.92
Adj. Flow (vph)	8	0	8	551	0	247	2	5	1215	580	40	133	724	2
RTOR Reduction (vph)	0	8	0	0	171	0	0	0	0	351	0	0	0	0
Lane Group Flow (vph)	0	8	0	551	76	0	0	0	1222	229	0	173	726	0
Turn Type	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm	Perm
Protected Phases	4	4	3	3	3	3	2	2	2	2	1	1	6	6
Permitted Phases	4	4	3	3	3	3	2	2	2	2	1	1	6	6
Actuated Green, G (s)	2.5	2.5	24.7	24.7	24.7	24.7	2	2	32.4	32.4	1	1	43.1	43.1
Effective Green, g (s)	4.0	4.0	26.7	26.7	26.7	26.7	2	2	34.4	34.4	1	1	44.6	44.6
Actuated g/C Ratio	0.05	0.05	0.31	0.31	0.31	0.31	0.39	0.39	0.39	0.39	0.51	0.51	0.51	0.51
Clearance Time (s)	5.5	5.5	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	4.0	4.0	5.5	5.5
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	60	553	484	1874	624	1874	624	624	222	2597	222	2597	222	2597
v/s Ratio Prot	c0.01	c0.30	c0.30	c0.30	c0.30	c0.30	c0.30	c0.30	c0.06	c0.14	c0.06	c0.14	c0.06	c0.14
v/s Ratio Perm	0.14	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.26	0.14	0.26	0.14	0.26	0.14
Uniform Delay, d1	40.0	30.3	30.3	30.3	30.3	30.3	30.3	30.3	0.65	0.37	0.65	0.37	0.65	0.37
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	21.6	18.7	21.6	18.7	21.6	18.7
Incremental Delay, d2	1.1	37.1	37.1	37.1	37.1	37.1	37.1	37.1	1.00	1.00	1.00	1.00	1.00	1.00
Delay (s)	41.1	67.3	67.3	67.3	67.3	67.3	67.3	67.3	0.8	0.4	0.8	0.4	0.8	0.4
Level of Service	D	E	E	E	E	E	E	E	C	B	C	B	C	B
Approach Delay (s)	41.1	41.1	41.1	41.1	41.1	41.1	41.1	41.1	22.4	19.1	22.4	19.1	22.4	19.1
Approach LOS	D	D	D	D	D	D	D	D	C	B	C	B	C	B

PM 2007 Project
Calvin Giordano

Future with Site Traffic-P.M. Peak Hour
6/19/2005

© 2007 Project
Calvin Giordano

Signalized Intersection Capacity Analysis
7: Hallandale Beach Blvd. & Diplomat Pkwy.

PM FUTURE (EXISTING + BACKGRO)
Future w/o Site Traffic-P.M. Peak Hour
6/17/2005

Movement	EBU	EBL	EBT	EBR	WBU	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Ideal Flow (vphpl)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Total Lost time (s)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Lane Util. Factor	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95	0.95
Flt Protected	1770	5075	5075	5075	1770	5036	5036	1770	1770	1700	1700	1770	1593	1593
Satd. Flow (prot)	0.05	1.00	1.00	1.00	0.05	1.00	1.00	0.05	0.66	1.00	1.00	0.95	1.00	1.00
Flt Permitted	99	5075	5075	5075	91	5036	5036	1232	1232	1700	1700	1770	1593	1593
Satd. Flow (perm)	84	183	2248	31	2	25	1626	111	49	19	27	144	4	120
Volume (vph)	0.86	0.86	0.86	0.86	0.95	0.95	0.95	0.95	0.64	0.64	0.64	0.83	0.83	0.83
Peak-hour factor, PHF	98	213	2614	36	2	26	1712	117	77	30	42	173	5	145
Adj. Flow (vph)	0	0	1	0	0	0	3	0	0	37	0	0	112	0
RTOR Reduction (vph)	0	311	2649	0	0	28	1826	0	77	35	0	173	38	0
Lane Group Flow (vph)	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt	Prot pm+pt
Turn Type	1	1	6	5	5	5	2	4	4	4	4	3	8	8
Protected Phases	113.3	102.7	84.9	80.3	14.7	14.7	16.7	16.7	16.7	16.7	16.7	16.7	16.7	16.7
Permitted Phases	115.3	104.7	88.9	82.3	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10
Actuated Green, G (s)	0.72	0.65	0.56	0.51	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Effective Green, g (s)	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Actuated g/C Ratio	374	3321	120	2590	129	177	177	177	177	177	177	177	177	177
Clearance Time (s)	c0.15	0.52	0.01	0.36	c0.06	c0.06	c0.06	c0.06	c0.06	c0.06	c0.06	c0.06	c0.06	c0.06
Vehicle Extension (s)	c0.45	0.80	0.12	0.23	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60
Lane Grp Cap (vph)	0.83	0.80	0.23	0.70	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60
v/s Ratio Prot	49.6	20.0	21.6	29.6	68.4	68.4	68.4	68.4	68.4	68.4	68.4	68.4	68.4	68.4
v/s Ratio Perm	1.00	1.00	1.61	1.75	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
v/c Ratio	14.5	2.1	0.9	1.4	7.2	7.2	7.2	7.2	7.2	7.2	7.2	7.2	7.2	7.2
Uniform Delay, d1	64.2	22.1	35.4	53.3	E	E	E	E	E	E	E	E	E	E
Progression Factor	E	C	D	D	D	D	D	D	D	D	D	D	D	D
Incremental Delay, d2	26.5	C	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0
Delay (s)	26.5	C	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0
Level of Service	E	C	D	D	D	D	D	D	D	D	D	D	D	D
Approach Delay (s)	26.5	C	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0	53.0
Approach LOS	E	C	D	D	D	D	D	D	D	D	D	D	D	D

7: Hallandale Beach Blvd. & Diplomat Pkwy.
Calvin Giordano

H Signalized Intersection Capacity Analysis
 7: Mallandale Beach Blvd. & Diplomat Pkwy.

PM TOTAL TRAFFIC w/PROT
 Future with Site Traffic-P.M. Peak Hour
 6/17/2005


Movement	EBU	EBL	EBT	EBR	WBU	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations														
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Lane Util. Factor	1.00	1.00	0.91	1.00	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Flt Protected	1.00	1.00	1.00	1.00	1.00	1.00	0.99	1.00	1.00	0.91	1.00	1.00	1.00	1.00
Satd. Flow (prot)	0.95	1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00	0.95	1.00	0.86	1.00
Flt Permitted	1770	5075	5075	1770	5037	5037	1770	5037	1770	1700	1770	1770	1593	1593
Satd. Flow (perm)	0.05	1.00	1.00	0.05	1.00	1.00	0.66	1.00	0.66	1.00	0.95	1.00	0.95	1.00
Volume (vph)	84	183	2270	31	2	26	1689	113	49	19	27	145	4	120
Peak-hour factor, PHF	0.86	0.86	0.86	0.86	0.95	0.95	0.95	0.95	0.64	0.64	0.64	0.83	0.83	0.83
Adj. Flow (vph)	98	213	2840	36	2	27	1778	119	77	30	42	175	5	145
RTOR Reduction (vph)	0	0	1	0	0	0	3	0	0	37	0	0	112	0
Lane Group Flow (vph)	0	311	2675	0	0	29	1894	0	77	35	0	175	38	0
Turn Type	Prot	pm+pt			Prot	pm+pt			Perm			Prot		
Protected Phases	1	1	6		5	5	2			4		3	8	
Permitted Phases		6			2				4					
Actuated Green, G (s)	113.3	102.7			84.9	80.3			14.7	14.7		14.0	34.7	
Effective Green, g (s)	115.3	104.7			88.9	82.3			16.7	16.7		16.0	36.7	
Actuated g/C Ratio	0.72	0.65			0.56	0.51			0.10	0.10		0.10	0.23	
Clearance Time (s)	6.0	6.0			6.0	6.0			6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0			3.0	3.0			3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	367	3321			120	2591			129	177		177	365	
v/s Ratio Prot	c0.15	0.53			0.01	0.38			c0.06	0.02		c0.10	0.02	
v/s Ratio Perm	c0.46				0.13									
v/c Ratio	0.85	0.81			0.24	0.73			0.60	0.20		0.99	0.10	
Uniform Delay, d1	51.8	20.2			22.0	30.2			68.4	65.5		71.9	48.7	
Progression Factor	1.00	1.00			1.58	1.69			1.00	1.00		1.00	1.00	
Incremental Delay, d2	16.4	2.2			0.9	1.6			7.2	0.6		63.7	0.1	
Delay (s)	68.1	22.4			35.5	52.6			75.7	66.1		135.6	48.8	
Level of Service	E	C			D	D			E	E		F	D	
Approach Delay (s)	27.2	C			52.4	D			71.0	E		95.5	F	
Approach LOS	C				D				E			F		

PM 2007 Project
 Calvin Giordano

IMPACT ANALYSIS
FOR
MILLENNIUM HALLANDALE
HALLANDALE BEACH, FLORIDA


OWNER:

2500 HALLANDALE BEACH, LLC



GELLER, GELLER, FISHER AND GARFINKEL, LLP
2411 Hollywood Blvd.
Hollywood, FL 33020
Phs: (954) 920-2300/(305) 949-6600
Fax: (954) 920-6885

Traffic Impact Study



Millennium Tower - Hallandale December 2005

Est. 1985



Tinter Associates, Inc. Transportation Engineers
3303 West Commercial Blvd. • Ste 201 • Ft. Lauderdale, FL 33309
(954) 484-3633 • Fax (954) 484-9612 • www.tinter.com




Figure 5 – Future Background Traffic Volumes

Future Total Traffic

Future total traffic volumes for the study area roadway network were calculated by combining project traffic volumes with future background traffic volumes. Resulting A.M. and P.M. peak hour future total traffic volumes are shown in Figure 6.




Figure 6 – Total Traffic Volumes

TRAFFIC IMPACT STUDY

FOR

REGENCY SPA

CITY OF HALLANDALE

Prepared for

REGENCY HOUSE HEALTH SPA


August 30, 2002

HUGHES HUGHES INC.

TRANSPORTATION ENGINEERS & PLANNERS

**2101 N. Andrews Avenue, Suite 406 ■ Fort Lauderdale, FL 33311-3949
954/563-1121 ■ Fax/954/563-9790 ■ www.HughesHughesInc.com**

C:\dgn\0204\DOV\figure2.dgn 08/27/02 02:00:48 PM



to the project location. Trip assignments were based on the assumption that drivers seek the most direct routes to the desired destinations. The actual distribution percentages were determined to be 1.2% to/from the south on S.R. A-1-A, 98.8% to/from the north on S.R. A-1-A, 33.4% of the traffic north of the project was assumed to continue north of Hallandale Beach Boulevard while 65.4% was assumed to be oriented to Hallandale Beach Boulevard west of S.R. A-1-A. Trips associated with the project were assigned to the adjacent roadway network assuming that drivers generally seek the most direct routes to the desired destination.

Figure 2 illustrates the driveway volumes expected to occur at the entrances to the proposed Riviera Club.

Table 3
Regency Spa
Trip Generation

Proposed Land Use (Code)	Scale	AM Peak-Hour			PM Peak-Hour			Daily		
		Entering	Exiting	Total	Entering	Exiting	Total	Entering	Exiting	Total
Existing Land Use										
Hotel (310)	70 D.U	14	10	25	18	19	38	312	312	624
Proposed Land Use										
Hotel (310)	130 D.U	42	30	72	38	39	77	580	580	1,160
Net New Trips		27	20	47	19	20	39	268	268	536

Notes: Institute of Transportation Engineers' (ITE) Trip Generation manual, 6th Edition trip rates:

Hotel (310)

AM Peak-Hour Rate: $T = 0.782(X)^{-29.797}$

trips per dwelling unit

PM Peak-Hour Rate: $\ln(T) = 1.150 \ln(X) - 1.255$


trips per dwelling unit

Daily Rate: $T = 8.92(X)$

trips per dwelling unit

Oasis

traffic study



prepared for:
Beacon Investment Properties, LLC

Traf Tech
ENGINEERING, INC.

March 2006

ROADWAY SEGMENT	TRIPS LINK	Roadway Type	LOS D Capacity	Total Background	Oasis Project (2) % LOS D	Significant Yes/No	Total Traffic	Total V/C
Hallandale Beach Boulevard								
I-95 to NW 8th Avenue	921	A6LD	4,550	7,091	42	No	7,133	1.57
NW 8th Avenue to Dixie Hwy	922	A6LD	4,550	7,155	42	No	7,197	1.58
Dixie Hwy to NE 3rd Ave	923	A6LD	4,550	5,273	56	No	5,329	1.17
NE 3rd Ave to US 1	924	A6LD	4,550	5,232	56	No	5,288	1.16
US 1 to NE 10th Ave	925	A6LD	3,980	5,260	82	No	5,342	1.34
NE 10th Ave to Diplomat Pkwy	926	A6LD	3,980	4,969	116	No	5,085	1.28
Diplomat Pkwy to SR A-1-A	927	A6LD	3,980	4,864	7	No	4,871	1.22
Dixie Highway								
Pembroke Rd to NW 3rd Street	903	A4LD	2,560	1,179	0	No	1,179	0.46
NW 3rd Street to Hallandale	904	A4LD	2,560	1,373	6	No	1,379	0.54
Hallandale to SW 3rd Street	932	A4LD	2,560	1,148	8	No	1,156	0.45
SW 3rd Street to Miami-Dade	933	A4LD	2,560	516	3	No	519	0.20
Federal Highway (US 1)								
NE 9th Street to NE 3rd Street	901	A4LD	2,560	3,465	12	No	3,477	1.36
NE 3rd Street to Hallandale	902	A4LD	2,560	2,904	21	No	2,925	1.14
Hallandale to SE 3rd Street	930	A6LD	4,550	4,751	6	No	4,757	1.05
SE 3rd Street to Miami-Dade	931	A6LD	4,550	4,926	6	No	4,932	1.08
SR A-1-A								
Iris Terrace to Hallandale	860	A6LD	3,980	3,271	4	No	3,275	0.82
Hallandale to 0.3 miles south	928	A6LD	4,550	4,492	4	No	4,496	0.99
0.3 miles south to Miami-Dade	929	A6LD	4,550	3,530	2	No	3,532	0.78

Source: Broward County TRIPS Model, Hallandale Beach, and Traf Tech Engineering, Inc.

(2) Trips based on Broward TRIPS model (Proposed Project minus Existing Development)




FIGURE 4
PM Peak Hour Project Traffic
 Oasis
 Hallandale Beach, Florida

TRIP DISTRIBUTION AND TRAFFIC ASSIGNMENT

The project trip distribution was based on a review of the existing transportation network located in the vicinity of the project site, the existing traffic patterns as obtained from the traffic counts, and the existing land uses located within the study area. The following project distribution and assignment was assumed for the Oasis mixed-use development:

- 44% of the project traffic was assigned to Hallandale Beach Boulevard east of the project site. Of the 44%, 4% was assigned to NE 14th Avenue and the remaining 40% was assumed to continue east onto SR A-1-A.
- 56 % of the project traffic was assigned to Hallandale Beach Boulevard west of the project site. Of the 56%, 28% was assumed to continue west on Hallandale Beach Boulevard, 20% was assumed to head south along US 1, and 8% was assigned to the north via Federal Highway.

Using the above trip distribution and traffic assignment, the new project-related trips were assigned to the study area. The resulting project traffic assignment is summarized in Figure 4.

**PARK CENTRAL
TRAFFIC IMPACT ANALYSIS
DRC Case #**

Prepared for

**HALLANDALE PARK CENTRAL DEVELOPMENT, LLC
425 North Federal Highway
Hallandale, Florida 33009**

by

**Jackson M. Ahlstedt, P.E.
46 N.W. 94th Street
Miami Shores, Florida 33150
(305) 754-8695**

AUGUST 2006

**Jackson M. Ahlstedt, P.E.
Florida Registration #28258**

**TABLE 19
PEAK HOUR PROJECT TRAFFIC ASSIGNMENT**

ROADWAY	FROM	TO	PEAK HOUR CONDITIONS			
			AM		PM	
			NB/EB	SB/WB	NB/EB	SB/WB
DIXIE HIGHWAY	DADE COUNTY LINE	HALLANDALE BEACH BLVD	8	12	6	4
	HALLANDALE BEACH BLVD	PEMBROKE ROAD	53	32	18	26
	PEMBROKE ROAD	HOLLYWOOD BOULEVARD	29	18	10	14
US-1	DADE COUNTY LINE	HALLANDALE BEACH BLVD	5	8	4	7
	HALLANDALE BEACH BLVD	PEMBROKE ROAD	12	7	4	6
	PEMBROKE ROAD	HOLLYWOOD BOULEVARD	12	7	4	6
HALLANDALE BEACH BLVD	I-95	US-1	35	57	28	19
	US-1	DIPLOMAT PARKWAY	2	1	1	1
	DIPLOMAT PARKWAY	A-1-A	2	1	1	1
PEMBROKE ROAD	I-95	US-1	14	23	12	8
HOLLYWOOD BLVD	I-95	DIXIE HIGHWAY	3	2	1	1
	DIXIE HIGHWAY	US-1	0	0	0	0
	US-1	A-1-A	1	1	0	1

Note: Volumes are in vehicles per hour and represent the net additional traffic due to the proposed project.

TABLE 16
FINAL EXTERNAL PROJECT TRAFFIC

TIME	VEHICLE TRIPS							TOTALS	
	CONDOMINIUMS		RETAIL		EXISTING MOBILE HOME PARK				
	ITE (230)		ITE (814)		ITE (240)				
	AUTO	98.00%	AUTO	98.00%	AUTO	98.00%			
AM PEAK HOUR OF ADJACENT STREET									
IN	25		81		(16)			90	VPD
OUT	120		88		(63)			146	VPD
TOTAL	145		169		(78)			235	VPD
PM PEAK HOUR OF ADJACENT STREET									
IN	116		29		(74)			72	VPH
OUT	57		37		(45)			49	VPH
TOTAL	173		67		(119)			121	VPH

As can be seen from Table 16, the estimated number of new vehicle trips entering the site during the AM peak hour is 90 vph. The estimated number of new vehicle trips leaving the site during the AM peak hour is 146 vph.

The estimated number of new vehicle trips entering the site during the PM peak hour is 72 vph. The estimated number of new vehicle trips leaving the site during the PM peak hour is 49 vph.




FIGURE 3
LANE CONFIGURATIONS AT INTERSECTIONS

*Traffic Impact Analysis
for Submittal to the City of
Hallandale Beach*

**Hallandale Square
Mixed-Use Development
Hallandale Beach, Florida**

Prepared for:

600 Hallandale, LLC
Bay Harbor, Florida

Prepared by:

Kimley-Horn and Associates, Inc.
Fort Lauderdale, Florida

©2008 Kimley-Horn and Associates, Inc.
January 2008
144157000



John J. McWilliams, P.E.
Florida Registration Number 62541
Kimley-Horn and Associates, Inc.
5200 NW 33rd Avenue, Suite 109
Fort Lauderdale, FL 33309
CA # 00000696

EXECUTIVE SUMMARY

600 Hallandale, LLC is proposing a retail development (Hallandale Square) in Hallandale Beach, Florida. The project consists of 347,708 sq. ft. of retail space and a seven (7) screen movie theater. The project site is located on the southeast corner of Hallandale Beach Boulevard and Federal Highway (US 1). The site is currently occupied by 60,609 sq. ft. of retail space. Construction is expected to be completed and the project opened by the year 2009. The project is expected to generate a total of 119 net new A.M. peak hour trips and 711 net new P.M. peak hour trips.

Access to the project is proposed via five (5) access points. Direct access to Federal Highway will be provided via a right-in/right-out driveway located south of Hallandale Beach Boulevard and via Hibiscus Street. Direct signalized access to Hallandale Beach Boulevard will be provided via a public roadway aligning with NE 8th Avenue south of Hallandale Beach Boulevard consistent with the Citywide Masterplan. Additionally, a right-in only project driveway is proposed west of NE 8th Avenue for delivery vehicles only. Furthermore, the proposed development is expected to have interconnectivity with the roadway network at the Village of Gulfstream Park via a public roadway network proposed as part of the Citywide Masterplan.

A traffic impact analysis was conducted for intersections in the vicinity of the project site consistent with City of Hallandale Beach's impact evaluation submission requirements (City Code Section 32-788(g)). Intersection capacity analyses were conducted for the existing conditions and for future conditions after the opening of the project. All study intersections are expected to operate at LOS D or better under future total traffic conditions during the peak hour periods with the exception of Hallandale Beach Boulevard and Federal Highway. The subject intersection is expected to operate at LOS F with or without the proposed development. In order to mitigate the additional delay generated by the proposed development, the applicant is proposing two (2) geometric improvements at the intersection.

- Construct an additional northbound right-turn lane on Federal Highway providing for dual northbound right-turn movements at the intersection along with the installation of a northbound right-turn overlap. Dedication of additional right-of-way along the proposed development's frontage will be required in order to construct this improvement.
- Contribute to the City an amount equal to the cost to construct a westbound right-turn lane along Hallandale Beach Boulevard at the intersection of Hallandale Beach Boulevard and Federal Highway (US 1). Once the City completes its Citywide Transportation Study, the City can either proceed to acquire the necessary right-of-way and use these funds to construct this improvement or utilize these funds for other transportation improvements which the Citywide Study recommends equivalent to the construction cost of the westbound right-turn lane to the City of Hallandale Beach to be used towards alternative transportation-related improvements in the area.

In conclusion, the proposed development is not expected to have a significant impact on the adjacent street network with the geometric improvements proposed at the intersection of Hallandale Beach Boulevard and Federal Highway.

Net New External Trips

The resulting net new external trips are presented in Table 2. These trips were then adjusted for the existing land use (57,579 sq. ft. of retail space) to account for traffic being produced by the existing land uses. Table 3 presents the external trips after the existing land use adjustments.

Table 3 External Trip Adjustment

External Trips	In	Out	Total
A.M. Peak Hour			
Project External Vehicular Trips	109	70	179
Existing Retail External Vehicular Trips	42	18	60
Net New External Vehicular Trips	67	52	119
P.M. Peak Hour			
Project External Vehicular Trips	471	477	948
Existing Retail External Vehicular Trips	110	127	237
Net New External Vehicular Trips	361	350	711

Trip Distribution and Assignment

An informational Traffic Review and Impact Planning System (TRIPS) model run was performed to determine the project trip distribution and assignment for the Hallandale Square project in accordance with City Code. This informational TRIPS model run was used as a basis for developing the trip distribution and assignment for the subject project. It should be noted that the TRIPS analysis does not include local roadways in the study area. As a result, the model did not assign trips to the residential streets located around the project site. Furthermore, the analysis does not take into account internalization or pass-by reductions. Therefore, only the cardinal distribution from the TRIPS analysis was utilized. It was also noted that the TRIPS analysis does not accurately estimate the attraction of project trips to/from Miami-Dade County as. However, the project site is adjacent to Miami-Dade County and to the City of Aventura (approximately 0.75 miles). Therefore, a significant percentage of project trips will originate to/from Miami-Dade County. Therefore, the project trip assignment was adjusted to account for the expected attraction into/from Miami-Dade County. The TRIPS analysis output for the current project is included in Appendix C.

- Legend**
- Study Roadway
 - Study Intersection
 - Site
 - 000 Entering Project Distribution
 - (000) Exiting Project Distribution

NOT TO SCALE





Figure 2
Project Trip Distribution
Hallandale Square
City of Hallandale Beach, Florida



Kimley-Horn
and Associates, Inc.

© 2007

Figure 4
Project Traffic Assignment P.M. Peak Hour
Hallandale Square
City of Hallandale Beach, Florida

Preliminary
Traffic Impact Study

Domus Hallandale
Hallandale Beach, Florida

Prepared For:

RLC Architects
137 West Royal Palm Road
Boca Raton, Florida 33432

Prepared By:

Carter & Burgess, Inc.
6363 NW 6th Way, Suite 300
Fort Lauderdale, Florida 33309
Phone: (954) 315-1020
Fax: (954) 315-1040
E-mail: karl.peterson@c-b.com
<http://www.c-b.com>

APPENDIX – G

Trip Generation Analysis



Trip Generation - AM Peak Hour																	
Land Uses	ITE Land Use Code	Description	Unit	Total Units	Rate/Unit	Trips	Driveway Volumes				Passerby Rate		Total Trips	Directional Distribution			
							Entering		Exiting		%	Trips		Entering		Exiting	
EXISTING																	
Lodging	311	All Suites Hotel	Rooms	216	0.38	82	55.0%	45	45.0%	37	0%	0	82	55.0%	45	45.0%	37
Lodging	310	Hotel	Rooms	216	0.56	121	58.0%	70	42.0%	51	0%	0	121	55.0%	67	45.0%	54
Lodging	232	High-Rise Condominium	Dwelling Units	84	0.34	29	19.0%	5	81.0%	23	0%	0	29	19.0%	5	81.0%	23
Total													Entering	117	Exiting	115	

Trip Generation - PM Peak Hour																	
Land Uses	ITE Land Use Code	Description	Unit	Total Units	Rate/Unit	Trips	Driveway Volumes				Passerby Rate		Total Trips	Directional Distribution			
							Entering		Exiting		%	Trips		Entering		Exiting	
EXISTING																	
Lodging	311	All Suites Hotel	Rooms	216	0.4	86	45.0%	39	55.0%	48	0%	0	86	45.0%	39	55.0%	48
Lodging	310	Hotel	Rooms	216	0.59	127	49.0%	62	51.0%	65	0%	0	127	45.0%	57	55.0%	70
Lodging	232	High-Rise Condominium	Dwelling Units	84	0.38	32	62.0%	20	38.0%	12	0%	0	32	62.0%	20	38.0%	12
Total													Entering	116	Exiting	130	

Trip Generation - Daily																	
Land Uses	ITE Land Use Code	Description	Unit	Total Units	Rate/Unit	Trips	Driveway Volumes				Passerby Rate		Total Trips	Directional Distribution			
							Entering		Exiting		%	Trips		Entering		Exiting	
EXISTING																	
Lodging	311	All Suites Hotel	Rooms	216	4.9	1058	50.0%	529	50.0%	529	0%	0	1058	50.0%	529	50.0%	529
Lodging	310	Hotel	Rooms	216	8.17	1765	50.0%	882	50.0%	882	0%	0	1765	50.0%	882	50.0%	882
Lodging	232	High-Rise Condominium	Dwelling Units	84	4.18	351	50.0%	176	50.0%	176	0%	0	351	50.0%	176	50.0%	176
Total													Entering	1587	Exiting	1587	

APPENDIX – H

Synchro Output Sheets – Future (2015)



Synchro Output Sheets – Future (2015)























Future Background Traffic - AM



HCM Signalized Intersection Capacity Analysis

3: E. HALLANDALE BEACH BLVD & GOLDEN ISLES DR



























Beachwalk Traffic Study
Future (2015) Background - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	14	1271	63	44	1671	37	178	17	115	13	5	2
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Lane Util. Factor		0.91		1.00	0.91		0.95	0.95	1.00		0.95	
Frt		0.99		1.00	1.00		1.00	1.00	0.85		0.99	
Flt Protected		1.00		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (prot)		5047		1770	5069		1681	1699	1583		3376	
Flt Permitted		0.88		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (perm)		4458		1770	5069		1681	1699	1583		3376	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	15	1382	68	48	1816	40	193	18	125	14	5	2
RTOR Reduction (vph)	0	4	0	0	2	0	0	0	94	0	2	0
Lane Group Flow (vph)	0	1461	0	48	1854	0	104	107	31	0	19	0
Turn Type	Perm			Prot			Split			Perm	Split	
Protected Phases		4		3	8		2	2			6	6
Permitted Phases	4								2			
Actuated Green, G (s)		61.6		7.3	74.9		37.2	37.2	37.2		21.1	
Effective Green, g (s)		61.6		7.3	74.9		37.2	37.2	37.2		21.1	
Actuated g/C Ratio		0.41		0.05	0.50		0.25	0.25	0.25		0.14	
Clearance Time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Vehicle Extension (s)		3.0		3.0	3.0		3.0	3.0	3.0		3.0	
Lane Grp Cap (vph)		1816		85	2511		414	418	389		471	
v/s Ratio Prot				0.03	c0.37		0.06	c0.06			c0.01	
v/s Ratio Perm	c0.33								0.02			
v/c Ratio	0.80			0.56	0.74		0.25	0.26	0.08		0.04	
Uniform Delay, d1	39.5			70.4	30.4		45.8	45.9	43.8		56.3	
Progression Factor	1.00			1.00	1.00		1.00	1.00	1.00		1.00	
Incremental Delay, d2	2.7			8.3	1.2		1.5	1.5	0.4		0.2	
Delay (s)	42.2			78.7	31.5		47.3	47.3	44.2		56.5	
Level of Service	D			E	C		D	D	D		E	
Approach Delay (s)	42.2				32.7			46.2			56.5	
Approach LOS	D				C			D			E	
Intersection Summary												
HCM Average Control Delay		37.8					HCM Level of Service		D			
HCM Volume to Capacity ratio		0.53										
Actuated Cycle Length (s)		151.2					Sum of lost time (s)		24.0			
Intersection Capacity Utilization		58.6%					ICU Level of Service		B			
Analysis Period (min)		15										
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

6: E. HALLANDALE BEACH BLVD & LAYNE BLVD

Beachwalk Traffic Study
Future (2015) Background - AM Peak




												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  			 				
Volume (vph)	80	1257	105	28	1829	83	104	15	50	21	5	76
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Lane Util. Factor	1.00	0.91		1.00	0.91		0.95	0.95	1.00		1.00	1.00
Frt	1.00	0.99		1.00	0.99		1.00	1.00	0.85		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	0.96	1.00		0.96	1.00
Satd. Flow (prot)	1770	5027		1770	5052		1681	1705	1583		1789	1583
Flt Permitted	0.95	1.00		0.95	1.00		0.95	0.78	1.00		0.78	1.00
Satd. Flow (perm)	1770	5027		1770	5052		1681	1382	1583		1448	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	87	1366	114	30	1988	90	113	16	54	23	5	83
RTOR Reduction (vph)	0	5	0	0	3	0	0	0	38	0	0	68
Lane Group Flow (vph)	87	1475	0	30	2075	0	64	65	16	0	28	15
Turn Type	Prot			Prot			Prot		Perm	pm+pt		Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2	6		6
Actuated Green, G (s)	11.4	73.8		5.2	67.6		9.1	39.9	39.9		24.8	24.8
Effective Green, g (s)	11.4	73.8		5.2	67.6		9.1	39.9	39.9		24.8	24.8
Actuated g/C Ratio	0.08	0.54		0.04	0.49		0.07	0.29	0.29		0.18	0.18
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0		3.0	3.0
Lane Grp Cap (vph)	147	2710		67	2495		112	424	461		262	287
v/s Ratio Prot	c0.05	c0.29		0.02	c0.41		c0.04	0.01				
v/s Ratio Perm								c0.03	0.01		0.02	0.01
v/c Ratio	0.59	0.54		0.45	0.83		0.57	0.15	0.03		0.11	0.05
Uniform Delay, d1	60.5	20.6		64.4	29.8		62.0	36.0	34.7		46.8	46.3
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00		1.00	1.00
Incremental Delay, d2	6.3	0.2		4.7	2.5		6.9	0.2	0.1		0.2	0.3
Delay (s)	66.8	20.8		69.1	32.3		68.9	36.1	34.8		47.0	46.7
Level of Service	E	C		E	C		E	D	C		D	D
Approach Delay (s)		23.4			32.8			47.2			46.8	
Approach LOS		C			C			D			D	
Intersection Summary												
HCM Average Control Delay			30.1			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.64									
Actuated Cycle Length (s)			136.9			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			66.6%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis

9: DIANA DR & SE 26 Avenue

Beachwalk Traffic Study
Future (2015) Background - AM Peak





























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Sign Control		Stop	Stop		Stop	
Volume (vph)	69	1	2	0	1	51
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	75	1	2	0	1	55
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total (vph)	76	2	57			
Volume Left (vph)	75	0	1			
Volume Right (vph)	0	0	55			
Hadj (s)	0.23	0.03	-0.55			
Departure Headway (s)	4.2	4.1	3.5			
Degree Utilization, x	0.09	0.00	0.06			
Capacity (veh/h)	833	855	988			
Control Delay (s)	7.7	7.1	6.7			
Approach Delay (s)	7.7	7.1	6.7			
Approach LOS	A	A	A			
Intersection Summary						
Delay			7.3			
HCM Level of Service			A			
Intersection Capacity Utilization			20.5%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

10: E. HALLANDALE BEACH BLVD & DIPLOMAT PKWY

Beachwalk Traffic Study
Future (2015) Background - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  			 			 	
Volume (vph)	115	1175	16	15	1609	50	11	1	5	50	23	149
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91		1.00	0.91			1.00		1.00	1.00	
Frt	1.00	1.00		1.00	1.00			0.96		1.00	0.87	
Flt Protected	0.95	1.00		0.95	1.00			0.97		0.95	1.00	
Satd. Flow (prot)	1770	5075		1770	5062			1735		1770	1621	
Flt Permitted	0.95	1.00		0.95	1.00			0.82		0.75	1.00	
Satd. Flow (perm)	1770	5075		1770	5062			1474		1389	1621	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	125	1277	17	16	1749	54	12	1	5	54	25	162
RTOR Reduction (vph)	0	1	0	0	2	0	0	4	0	0	119	0
Lane Group Flow (vph)	125	1293	0	16	1801	0	0	14	0	54	68	0
Turn Type	Prot			Prot			Perm			Perm		
Protected Phases	7	4		3	8			2			6	
Permitted Phases							2			6		
Actuated Green, G (s)	14.4	81.9		2.9	70.4			37.6		37.6	37.6	
Effective Green, g (s)	14.4	81.9		2.9	70.4			37.6		37.6	37.6	
Actuated g/C Ratio	0.10	0.58		0.02	0.50			0.27		0.27	0.27	
Clearance Time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	182	2960		37	2538			395		372	434	
v/s Ratio Prot	c0.07	0.25		0.01	c0.36						c0.04	
v/s Ratio Perm								0.01		0.04		
v/c Ratio	0.69	0.44		0.43	0.71			0.04		0.15	0.16	
Uniform Delay, d1	60.8	16.4		67.9	27.1			38.0		39.2	39.3	
Progression Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Incremental Delay, d2	10.3	0.1		7.9	0.9			0.2		0.8	0.8	
Delay (s)	71.1	16.5		75.8	28.0			38.2		40.0	40.1	
Level of Service	E	B		E	C			D		D	D	
Approach Delay (s)		21.3			28.4			38.2			40.0	
Approach LOS		C			C			D			D	
Intersection Summary												
HCM Average Control Delay			26.4			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.54									
Actuated Cycle Length (s)			140.4			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			64.1%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

17: E. HALLANDALE BEACH BLVD & 3 Islands Drive

Beachwalk Traffic Study
Future (2015) Background - AM Peak


























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	←←	↑↑↑	↑↑↑	↑	↑	↑
Volume (vph)	224	925	1265	158	364	368
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.97	0.91	0.91	1.00	1.00	1.00
Frt	1.00	1.00	1.00	0.85	1.00	0.85
Flt Protected	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (prot)	3433	5085	5085	1583	1770	1583
Flt Permitted	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (perm)	3433	5085	5085	1583	1770	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	243	1005	1375	172	396	400
RTOR Reduction (vph)	0	0	0	105	0	215
Lane Group Flow (vph)	243	1005	1375	67	396	185
Turn Type	Prot			Perm		custom
Protected Phases	7	4	8			
Permitted Phases				8	6	6
Actuated Green, G (s)	12.7	53.4	34.7	34.7	24.2	24.2
Effective Green, g (s)	12.7	53.4	34.7	34.7	24.2	24.2
Actuated g/C Ratio	0.14	0.60	0.39	0.39	0.27	0.27
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	487	3031	1969	613	478	428
v/s Ratio Prot	c0.07	0.20	c0.27			
v/s Ratio Perm				0.04	c0.22	0.12
v/c Ratio	0.50	0.33	0.70	0.11	0.83	0.43
Uniform Delay, d1	35.5	9.1	23.1	17.6	30.7	27.0
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	0.8	0.1	1.1	0.1	15.2	3.2
Delay (s)	36.3	9.2	24.2	17.6	45.9	30.2
Level of Service	D	A	C	B	D	C
Approach Delay (s)		14.5	23.4		38.0	
Approach LOS		B	C		D	
Intersection Summary						
HCM Average Control Delay			23.6		HCM Level of Service	C
HCM Volume to Capacity ratio			0.71			
Actuated Cycle Length (s)			89.6		Sum of lost time (s)	18.0
Intersection Capacity Utilization			66.0%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

21: WB E. Hallandale Beach Blvd & S. OCEAN DR



























Beachwalk Traffic Study
Future (2015) Background - AM Peak

												
Movement	EBL	EBT	EBR2	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR2
Lane Configurations												
Volume (vph)	551	37	880	6	176	6	199	474	6	6	362	346
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.95	0.95	1.00		1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00
Frt	1.00	1.00	0.85		1.00	0.85	1.00	1.00	0.85	1.00	1.00	0.85
Flt Protected	0.95	0.96	1.00		1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (prot)	1681	1695	1583		1859	1583	1770	3539	1583	1770	3539	1583
Flt Permitted	0.95	0.96	1.00		1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	1681	1695	1583		1859	1583	1770	3539	1583	1770	3539	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	599	40	957	7	191	7	216	515	7	7	393	376
RTOR Reduction (vph)	0	0	731	0	0	0	0	0	4	0	0	0
Lane Group Flow (vph)	317	322	226	0	198	7	216	515	3	7	393	376
Turn Type	Split		Perm	Split		Perm	Prot		Perm	Prot		Perm
Protected Phases	3	3		7	7		5	2		1	6	
Permitted Phases			3			7			2			6
Actuated Green, G (s)	25.1	25.1	25.1		13.9	13.9	7.0	42.0	42.0	1.3	36.3	36.3
Effective Green, g (s)	25.1	25.1	25.1		13.9	13.9	7.0	42.0	42.0	1.3	36.3	36.3
Actuated g/C Ratio	0.24	0.24	0.24		0.13	0.13	0.07	0.40	0.40	0.01	0.34	0.34
Clearance Time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0		3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	397	400	374		243	207	117	1398	625	22	1209	541
v/s Ratio Prot	0.19	c0.19			c0.11		c0.12	c0.15		0.00	0.11	
v/s Ratio Perm			0.14			0.00			0.00			c0.24
v/c Ratio	0.80	0.80	0.60		0.81	0.03	1.85	0.37	0.00	0.32	0.33	0.70
Uniform Delay, d1	38.2	38.3	36.2		44.9	40.3	49.6	22.8	19.5	52.1	25.9	30.2
Progression Factor	1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	15.4	15.8	7.1		18.6	0.1	411.8	0.7	0.0	8.2	0.2	3.9
Delay (s)	53.6	54.0	43.2		63.5	40.4	461.5	23.5	19.5	60.2	26.1	34.1
Level of Service	D	D	D		E	D	F	C	B	E	C	C
Approach Delay (s)		47.5			62.7			151.7			30.3	
Approach LOS		D			E			F			C	
Intersection Summary												
HCM Average Control Delay			67.6				HCM Level of Service			E		
HCM Volume to Capacity ratio			0.88									
Actuated Cycle Length (s)			106.3				Sum of lost time (s)			30.0		
Intersection Capacity Utilization			89.1%				ICU Level of Service			E		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

22: E. HALLANDALE BEACH BLVD & NE 14 AVE



























Beachwalk Traffic Study
Future (2015) Background - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  		 					
Volume (vph)	102	1518	228	16	1789	52	249	73	23	130	84	196
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91	1.00	1.00	0.91		0.97	1.00		1.00	1.00	
Frt	1.00	1.00	0.85	1.00	1.00		1.00	0.96		1.00	0.89	
Flt Protected	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1770	5085	1583	1770	5064		3433	1796		1770	1667	
Flt Permitted	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (perm)	1770	5085	1583	1770	5064		3433	1796		1770	1667	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	111	1650	248	17	1945	57	271	79	25	141	91	213
RTOR Reduction (vph)	0	0	105	0	2	0	0	7	0	0	52	0
Lane Group Flow (vph)	111	1650	143	17	2000	0	271	97	0	141	252	0
Turn Type	Prot		Perm	Prot			Prot			Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			4									
Actuated Green, G (s)	12.4	67.1	67.1	4.8	59.5		16.5	49.3		16.2	49.0	
Effective Green, g (s)	12.4	67.1	67.1	4.8	59.5		16.5	49.3		16.2	49.0	
Actuated g/C Ratio	0.08	0.42	0.42	0.03	0.37		0.10	0.31		0.10	0.30	
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	136	2114	658	53	1867		351	549		178	506	
v/s Ratio Prot	c0.06	c0.32		0.01	c0.39		0.08	0.05		c0.08	c0.15	
v/s Ratio Perm			0.09									
v/c Ratio	0.82	0.78	0.22	0.32	1.07		0.77	0.18		0.79	0.50	
Uniform Delay, d1	73.4	40.8	30.3	76.7	51.0		70.6	41.2		71.0	46.1	
Progression Factor	1.00	1.00	1.00	1.00	1.00		1.00	1.00		1.00	1.00	
Incremental Delay, d2	30.0	1.9	0.2	3.5	42.9		10.1	0.7		21.0	3.5	
Delay (s)	103.4	42.7	30.5	80.2	93.9		80.7	41.9		91.9	49.6	
Level of Service	F	D	C	F	F		F	D		F	D	
Approach Delay (s)		44.6			93.7			69.9			63.0	
Approach LOS		D			F			E			E	
Intersection Summary												
HCM Average Control Delay			68.7			HCM Level of Service				E		
HCM Volume to Capacity ratio			0.85									
Actuated Cycle Length (s)			161.4			Sum of lost time (s)			30.0			
Intersection Capacity Utilization			84.9%			ICU Level of Service			E			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

26: E. HALLANDALE BEACH BLVD & NE 10 AVE













Beachwalk Traffic Study
Future (2015) Background - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  		 	  			 				
Volume (vph)	119	1750	135	278	1979	33	67	2	111	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Lane Util. Factor	1.00	0.91	1.00	0.97	0.91	1.00		0.95	1.00			
Frt	1.00	1.00	0.85	1.00	1.00	0.85		1.00	0.85			
Flt Protected	0.95	1.00	1.00	0.95	1.00	1.00		0.95	1.00			
Satd. Flow (prot)	1770	5085	1583	3433	5085	1583		3375	1583			
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00		0.95	1.00			
Satd. Flow (perm)	1770	5085	1583	3433	5085	1583		3375	1583			
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	129	1902	147	302	2151	36	73	2	121	0	0	0
RTOR Reduction (vph)	0	0	19	0	0	8	0	0	91	0	0	0
Lane Group Flow (vph)	129	1902	128	302	2151	28	0	75	30	0	0	0
Turn Type	Prot		Perm	Prot		Perm	Prot		Perm			
Protected Phases	7	4		3	8		5	2				
Permitted Phases			4			8			2			
Actuated Green, G (s)	16.4	80.3	80.3	15.7	79.6	79.6		37.2	37.2			
Effective Green, g (s)	16.4	80.3	80.3	15.7	79.6	79.6		37.2	37.2			
Actuated g/C Ratio	0.11	0.53	0.53	0.10	0.53	0.53		0.25	0.25			
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0			
Lane Grp Cap (vph)	192	2701	841	356	2677	833		830	389			
v/s Ratio Prot	0.07	0.37		c0.09	c0.42							
v/s Ratio Perm			0.08			0.02		0.02	0.02			
v/c Ratio	0.67	0.70	0.15	0.85	0.80	0.03		0.09	0.08			
Uniform Delay, d1	64.8	26.6	18.1	66.6	29.4	17.3		44.0	43.8			
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00		1.00	1.00			
Incremental Delay, d2	8.9	0.9	0.1	16.9	1.8	0.0		0.0	0.4			
Delay (s)	73.7	27.4	18.2	83.4	31.2	17.3		44.0	44.2			
Level of Service	E	C	B	F	C	B		D	D			
Approach Delay (s)		29.5			37.3			44.1			0.0	
Approach LOS		C			D			D			A	
Intersection Summary												
HCM Average Control Delay			34.1			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.61									
Actuated Cycle Length (s)			151.2			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			63.5%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

29: E. HALLANDALE BEACH BLVD & NE 8 AVE

Beachwalk Traffic Study
Future (2015) Background - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑↑↑	↑	↑	↑↑↑			↑↓		↑	↑	↑
Volume (vph)	0	2044	241	2	2082	0	192	0	96	97	8	189
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Lane Util. Factor		0.91	1.00	1.00	0.91			1.00		0.95	0.95	1.00
Frt		1.00	0.85	1.00	1.00			0.96		1.00	1.00	0.85
Flt Protected		1.00	1.00	0.95	1.00			0.97		0.95	0.96	1.00
Satd. Flow (prot)		5085	1583	1770	5085			1722		1681	1698	1583
Flt Permitted		1.00	1.00	0.05	1.00			0.76		0.66	0.74	1.00
Satd. Flow (perm)		5085	1583	87	5085			1357		1165	1306	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	2222	262	2	2263	0	209	0	104	105	9	205
RTOR Reduction (vph)	0	0	72	0	0	0	0	12	0	0	0	44
Lane Group Flow (vph)	0	2222	190	2	2263	0	0	301	0	57	57	161
Turn Type			Perm	pm+pt			pm+pt			pm+pt		Perm
Protected Phases		4		3	8		5	2		1	6	
Permitted Phases			4	8			2			6		6
Actuated Green, G (s)		79.4	79.4	86.5	86.5			23.3		36.9	36.9	36.9
Effective Green, g (s)		79.4	79.4	86.5	86.5			23.3		36.9	36.9	36.9
Actuated g/C Ratio		0.59	0.59	0.64	0.64			0.17		0.27	0.27	0.27
Clearance Time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Vehicle Extension (s)		3.0	3.0	3.0	3.0			3.0		3.0	3.0	3.0
Lane Grp Cap (vph)		2982	928	69	3249			234		346	378	431
v/s Ratio Prot		c0.44		0.00	c0.45					0.01	0.01	
v/s Ratio Perm			0.12	0.02				c0.22		0.04	0.03	c0.10
v/c Ratio		0.75	0.21	0.03	0.70			1.28		0.16	0.15	0.37
Uniform Delay, d1		20.6	13.2	16.8	15.9			56.0		39.5	37.4	39.9
Progression Factor		1.00	1.00	1.00	1.00			1.00		1.00	1.00	1.00
Incremental Delay, d2		1.0	0.1	0.2	0.7			156.5		0.2	0.2	2.5
Delay (s)		21.6	13.3	17.0	16.6			212.5		39.7	37.5	42.4
Level of Service		C	B	B	B			F		D	D	D
Approach Delay (s)		20.7			16.6			212.5			41.0	
Approach LOS		C			B			F			D	










Intersection Summary

HCM Average Control Delay	31.3	HCM Level of Service	C
HCM Volume to Capacity ratio	0.87		
Actuated Cycle Length (s)	135.4	Sum of lost time (s)	24.0
Intersection Capacity Utilization	83.4%	ICU Level of Service	E
Analysis Period (min)	15		
c Critical Lane Group			

HCM Unsignalized Intersection Capacity Analysis

33: DIANA DR & GOLDEN ISLES DR























Beachwalk Traffic Study
Future (2015) Background - AM Peak

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Volume (veh/h)	49	70	241	69	12	70
Sign Control	Stop		Free			Free
Grade	0%		0%			0%
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	53	76	262	75	13	76
Pedestrians						
Lane Width (ft)						
Walking Speed (ft/s)						
Percent Blockage						
Right turn flare (veh)						
Median type			None			None
Median storage veh						
Upstream signal (ft)						345
pX, platoon unblocked						
vC, conflicting volume	402	299			337	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	402	299			337	
tC, single (s)	6.4	6.2			4.1	
tC, 2 stage (s)						
tF (s)	3.5	3.3			2.2	
p0 queue free %	91	90			99	
cM capacity (veh/h)	598	740			1222	
Direction, Lane #	WB 1	NB 1	SB 1			
Volume Total	129	337	89			
Volume Left	53	0	13			
Volume Right	76	75	0			
cSH	674	1700	1222			
Volume to Capacity	0.19	0.20	0.01			
Queue Length 95th (ft)	18	0	1			
Control Delay (s)	11.6	0.0	1.2			
Lane LOS	B		A			
Approach Delay (s)	11.6	0.0	1.2			
Approach LOS	B					
Intersection Summary						
Average Delay		2.9				
Intersection Capacity Utilization		30.6%		ICU Level of Service	A	
Analysis Period (min)		15				

HCM Signalized Intersection Capacity Analysis

34: E. HALLANDALE BEACH BLVD & U.S. 1

Beachwalk Traffic Study
Future (2015) Background - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	116	1286	655	657	1404	296	483	696	444	424	1237	88
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Lane Util. Factor	1.00	0.91		0.97	0.91		0.97	0.91	1.00	0.97	0.91	
Frt	1.00	0.95		1.00	0.97		1.00	1.00	0.85	1.00	0.99	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1770	4828		3433	4952		3433	5085	1583	3433	5034	
Flt Permitted	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (perm)	1770	4828		3433	4952		3433	5085	1583	3433	5034	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	126	1398	712	714	1526	322	525	757	483	461	1345	96
RTOR Reduction (vph)	0	57	0	0	19	0	0	0	209	0	5	0
Lane Group Flow (vph)	126	2053	0	714	1829	0	525	757	274	461	1436	0
Turn Type	Prot			Prot			Prot		Perm		Prot	
Protected Phases	7	4		3	8		5	2			1	6
Permitted Phases									2			
Actuated Green, G (s)	16.7	44.0		24.0	51.3		24.0	44.4	44.4	23.6	42.0	
Effective Green, g (s)	16.7	44.0		24.0	51.3		24.0	44.4	44.4	23.6	42.0	
Actuated g/C Ratio	0.10	0.28		0.15	0.32		0.15	0.28	0.28	0.15	0.26	
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	185	1328		515	1588		515	1411	439	506	1321	
v/s Ratio Prot	0.07	c0.43		c0.21	c0.37		c0.15	0.15		0.13	c0.29	
v/s Ratio Perm									0.17			
v/c Ratio	0.68	1.55		1.39	1.15		1.02	0.54	0.62	0.91	1.09	
Uniform Delay, d1	69.1	58.0		68.0	54.4		68.0	49.1	50.5	67.2	59.0	
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00	1.00	1.00	
Incremental Delay, d2	9.9	249.4		185.6	76.0		44.6	1.5	6.6	20.6	51.9	
Delay (s)	79.0	307.4		253.6	130.4		112.6	50.5	57.1	87.8	110.9	
Level of Service	E	F		F	F		F	D	E	F	F	
Approach Delay (s)		294.5			164.7			70.8			105.3	
Approach LOS		F			F			E			F	
Intersection Summary												
HCM Average Control Delay			166.1			HCM Level of Service			F			
HCM Volume to Capacity ratio			1.34									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			32.0			
Intersection Capacity Utilization			119.5%			ICU Level of Service			H			
Analysis Period (min)			15									
c Critical Lane Group												

Intersection Capacity Utilization

Beachwalk Traffic Study

8: E. HALLANDALE BEACH BLVD & EB E. Hallandale Beach Blvd

Future (2015) Background - AM Peak



Movement	EBT	EBR	WBL	WBT	NBL	NBR	NBR2	NWL	NWR
Lane Configurations	↑↑↑↱		↱	↑↑↑			↱		
Volume (vph)	1282	4	48	1448	0	0	59	0	0
Pedestrians									
Ped Button									
Pedestrian Timing (s)									
Free Right		No				No	No		No
Ideal Flow	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Green (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Refr Cycle Length (s)	120								
Volume Combined (vph)	1286	0	48	1448	0	0	59	0	0
Lane Utilization Factor	0.91	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00
Turning Factor (vph)	1.00	0.85	0.95	1.00	0.95	0.85	0.85	0.95	0.85
Saturated Flow (vph)	5173	0	1805	5176	0	0	1615	0	0
Ped Intf Time (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Frequency (%)	0.00			0.00	0.00			0.00	
Protected Option Allowed	Yes			Yes	No			No	
Reference Time (s)	29.8	0.0	3.2	33.6		0.0	4.4		0.0
Adj Reference Time (s)	33.8	0.0	8.0	37.6		0.0	8.4		0.0
Permitted Option									
Adj Saturation A (vph)	1724		120	1725	0			0	
Reference Time A (s)	29.8		47.9	33.6	0.0			0.0	
Adj Saturation B (vph)	NA		NA	NA	NA			NA	
Reference Time B (s)	NA		NA	NA	NA			NA	
Reference Time (s)	29.8			47.9					
Adj Reference Time (s)	33.8			51.9					
Split Option									
Ref Time Combined (s)	29.8		3.2	33.6	0.0			0.0	
Ref Time Seperate (s)	29.7		3.2	33.6	0.0			0.0	
Reference Time (s)	29.8		33.6	33.6	0.0			0.0	
Adj Reference Time (s)	33.8		37.6	37.6	0.0			0.0	
Summary		EB WB		NB		NW		Combined	
Protected Option (s)		41.8		NA		NA			
Permitted Option (s)		51.9		Err		Err			
Split Option (s)		71.4		0.0		0.0			
Minimum (s)		41.8		0.0		0.0		41.8	
Right Turns		NBR2							
Adj Reference Time (s)		8.4							
Cross Thru Ref Time (s)		0.0							
Oncoming Left Ref Time (s)		33.8							
Combined (s)		42.2							

Intersection Summary

Intersection Capacity Utilization 35.2% ICU Level of Service A
Reference Times and Phasing Options do not represent an optimized timing plan.

Synchro Output Sheets – Future (2015)





















Future Background Traffic – PM



HCM Signalized Intersection Capacity Analysis

3: E. HALLANDALE BEACH BLVD & GOLDEN ISLES DR






















Beachwalk Traffic Study
Future (2015) Background - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	10	2047	146	119	1677	51	142	18	55	74	13	9
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Lane Util. Factor		0.91		1.00	0.91		0.95	0.95	1.00		0.95	
Frt		0.99		1.00	1.00		1.00	1.00	0.85		0.99	
Flt Protected		1.00		0.95	1.00		0.95	0.96	1.00		0.96	
Satd. Flow (prot)		5033		1770	5063		1681	1704	1583		3359	
Flt Permitted		0.91		0.95	1.00		0.95	0.96	1.00		0.96	
Satd. Flow (perm)		4604		1770	5063		1681	1704	1583		3359	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	11	2225	159	129	1823	55	154	20	60	80	14	10
RTOR Reduction (vph)	0	5	0	0	2	0	0	0	46	0	5	0
Lane Group Flow (vph)	0	2390	0	129	1876	0	86	88	14	0	99	0
Turn Type	Perm			Prot			Split			Perm	Split	
Protected Phases	4			3			2			2	6	
Permitted Phases	4									2		
Actuated Green, G (s)	66.0			12.0			37.0			37.0	21.0	
Effective Green, g (s)	66.0			12.0			37.0			37.0	21.0	
Actuated g/C Ratio	0.41			0.08			0.23			0.23	0.13	
Clearance Time (s)	6.0			6.0			6.0			6.0	6.0	
Vehicle Extension (s)	3.0			3.0			3.0			3.0	3.0	
Lane Grp Cap (vph)	1899			133			389			394	366	
v/s Ratio Prot				c0.07			0.05			c0.05		
v/s Ratio Perm	c0.52									0.01		
v/c Ratio	1.26			0.97			0.22			0.22	0.04	
Uniform Delay, d1	47.0			73.8			49.8			49.9	47.7	
Progression Factor	1.00			1.00			1.00			1.00	1.00	
Incremental Delay, d2	120.9			67.9			1.3			1.3	0.2	
Delay (s)	167.9			141.7			51.1			51.2	47.9	
Level of Service	F			F			D			D	D	
Approach Delay (s)	167.9			36.8			50.3				63.4	
Approach LOS	F			D			D				E	
Intersection Summary												
HCM Average Control Delay			104.3			HCM Level of Service			F			
HCM Volume to Capacity ratio			0.79									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			102.6%			ICU Level of Service			G			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

6: E. HALLANDALE BEACH BLVD & LAYNE BLVD

Beachwalk Traffic Study
Future (2015) Background - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	125	1978	54	24	1647	32	167	15	59	142	12	102
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Lane Util. Factor	1.00	0.91		1.00	0.91		0.95	0.95	1.00		1.00	1.00
Frt	1.00	1.00		1.00	1.00		1.00	1.00	0.85		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	0.96	1.00		0.96	1.00
Satd. Flow (prot)	1770	5065		1770	5071		1681	1698	1583		1781	1583
Flt Permitted	0.95	1.00		0.95	1.00		0.95	0.41	1.00		0.67	1.00
Satd. Flow (perm)	1770	5065		1770	5071		1681	733	1583		1245	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	136	2150	59	26	1790	35	182	16	64	154	13	111
RTOR Reduction (vph)	0	1	0	0	1	0	0	0	45	0	0	93
Lane Group Flow (vph)	136	2208	0	26	1824	0	98	100	19	0	167	18
Turn Type	Prot			Prot			Prot		Perm	pm+pt		Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2	6		6
Actuated Green, G (s)	13.6	72.3		4.9	63.6		13.2	41.4	41.4		22.2	22.2
Effective Green, g (s)	13.6	72.3		4.9	63.6		13.2	41.4	41.4		22.2	22.2
Actuated g/C Ratio	0.10	0.53		0.04	0.47		0.10	0.30	0.30		0.16	0.16
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0		3.0	3.0
Lane Grp Cap (vph)	176	2681		63	2361		162	315	480		202	257
v/s Ratio Prot	c0.08	c0.44		0.01	0.36		c0.06	0.03				
v/s Ratio Perm								0.07	0.01		c0.13	0.01
v/c Ratio	0.77	0.82		0.41	0.77		0.60	0.32	0.04		0.83	0.07
Uniform Delay, d1	60.0	26.8		64.4	30.5		59.2	36.7	33.6		55.3	48.5
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00		1.00	1.00
Incremental Delay, d2	18.7	2.2		4.3	1.6		6.2	0.6	0.2		23.3	0.5
Delay (s)	78.7	29.0		68.8	32.1		65.4	37.3	33.7		78.6	49.0
Level of Service	E	C		E	C		E	D	C		E	D
Approach Delay (s)		31.9			32.6			47.0			66.8	
Approach LOS		C			C			D			E	
Intersection Summary												
HCM Average Control Delay			35.0			HCM Level of Service				D		
HCM Volume to Capacity ratio			0.82									
Actuated Cycle Length (s)			136.6			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			72.9%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis

9: DIANA DR & SE 26 Avenue

Beachwalk Traffic Study
Future (2015) Background - PM Peak





























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↰	↱		↰	↱
Sign Control		Stop	Stop		Stop	
Volume (vph)	45	6	1	2	5	62
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	49	7	1	2	5	67
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total (vph)	55	3	73			
Volume Left (vph)	49	0	5			
Volume Right (vph)	0	2	67			
Hadj (s)	0.21	-0.37	-0.51			
Departure Headway (s)	4.3	3.7	3.5			
Degree Utilization, x	0.07	0.00	0.07			
Capacity (veh/h)	828	939	993			
Control Delay (s)	7.6	6.7	6.8			
Approach Delay (s)	7.6	6.7	6.8			
Approach LOS	A	A	A			
Intersection Summary						
Delay			7.1			
HCM Level of Service			A			
Intersection Capacity Utilization			20.3%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

10: E. HALLANDALE BEACH BLVD & DIPLOMAT PKWY


Beachwalk Traffic Study
Future (2015) Background - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  			 			 	
Volume (vph)	193	2060	2	4	1631	51	9	11	12	72	1	118
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91		1.00	0.91			1.00		1.00	1.00	
Frt	1.00	1.00		1.00	1.00			0.95		1.00	0.85	
Flt Protected	0.95	1.00		0.95	1.00			0.99		0.95	1.00	
Satd. Flow (prot)	1770	5085		1770	5062			1744		1770	1585	
Flt Permitted	0.95	1.00		0.95	1.00			0.92		0.73	1.00	
Satd. Flow (perm)	1770	5085		1770	5062			1631		1368	1585	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	210	2239	2	4	1773	55	10	12	13	78	1	128
RTOR Reduction (vph)	0	0	0	0	2	0	0	10	0	0	96	0
Lane Group Flow (vph)	210	2241	0	4	1826	0	0	25	0	78	33	0
Turn Type	Prot			Prot			Perm			Perm		
Protected Phases	7	4		3	8			2			6	
Permitted Phases							2			6		
Actuated Green, G (s)	19.1	92.5		1.2	74.6			37.2		37.2	37.2	
Effective Green, g (s)	19.1	92.5		1.2	74.6			37.2		37.2	37.2	
Actuated g/C Ratio	0.13	0.62		0.01	0.50			0.25		0.25	0.25	
Clearance Time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	227	3159		14	2536			407		342	396	
v/s Ratio Prot	c0.12	c0.44		0.00	0.36						0.02	
v/s Ratio Perm								0.02		c0.06		
v/c Ratio	0.93	0.71		0.29	0.72			0.06		0.23	0.08	
Uniform Delay, d1	64.2	19.1		73.4	29.0			42.6		44.4	42.8	
Progression Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Incremental Delay, d2	39.4	0.7		10.9	1.0			0.3		1.5	0.4	
Delay (s)	103.6	19.8		84.4	30.0			42.8		46.0	43.2	
Level of Service	F	B		F	C			D		D	D	
Approach Delay (s)		27.0			30.1			42.8			44.2	
Approach LOS		C			C			D			D	
Intersection Summary												
HCM Average Control Delay			29.2			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.59									
Actuated Cycle Length (s)			148.9			Sum of lost time (s)			12.0			
Intersection Capacity Utilization			69.0%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

17: E. HALLANDALE BEACH BLVD & 3 ISLANDS BLVD

Beachwalk Traffic Study
Future (2015) Background - PM Peak


























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	←←	↑↑↑	↑↑↑	↑	←	↑
Volume (vph)	576	1520	1457	319	344	294
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.97	0.91	0.91	1.00	1.00	1.00
Frt	1.00	1.00	1.00	0.85	1.00	0.85
Flt Protected	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (prot)	3433	5085	5085	1583	1770	1583
Flt Permitted	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (perm)	3433	5085	5085	1583	1770	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	626	1652	1584	347	374	320
RTOR Reduction (vph)	0	0	0	202	0	196
Lane Group Flow (vph)	626	1652	1584	145	374	124
Turn Type	Prot			Perm		custom
Protected Phases	7	4	8			
Permitted Phases				8	6	6
Actuated Green, G (s)	24.1	77.8	47.7	47.7	24.1	24.1
Effective Green, g (s)	24.1	77.8	47.7	47.7	24.1	24.1
Actuated g/C Ratio	0.21	0.68	0.42	0.42	0.21	0.21
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	726	3473	2130	663	375	335
v/s Ratio Prot	c0.18	0.32	c0.31			
v/s Ratio Perm				0.09	c0.21	0.08
v/c Ratio	0.86	0.48	0.74	0.22	1.00	0.37
Uniform Delay, d1	43.3	8.5	27.9	21.2	44.9	38.4
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	10.3	0.1	1.4	0.2	45.8	3.1
Delay (s)	53.6	8.6	29.4	21.4	90.7	41.5
Level of Service	D	A	C	C	F	D
Approach Delay (s)		21.0	27.9		68.0	
Approach LOS		C	C		E	
Intersection Summary						
HCM Average Control Delay			30.4		HCM Level of Service	C
HCM Volume to Capacity ratio			0.84			
Actuated Cycle Length (s)			113.9		Sum of lost time (s)	18.0
Intersection Capacity Utilization			78.6%		ICU Level of Service	D
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

21: WB E. Hallandale Beach Blvd & S. OCEAN DR



























Beachwalk Traffic Study
Future (2015) Background - PM Peak

												
Movement	EBL	EBT	EBR2	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR2
Lane Configurations												
Volume (vph)	748	86	1073	12	91	31	221	712	6	17	768	741
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.95	0.95	1.00		1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00
Frt	1.00	1.00	0.85		1.00	0.85	1.00	1.00	0.85	1.00	1.00	0.85
Flt Protected	0.95	0.96	1.00		0.99	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (prot)	1681	1702	1583		1852	1583	1770	3539	1583	1770	3539	1583
Flt Permitted	0.95	0.96	1.00		0.99	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	1681	1702	1583		1852	1583	1770	3539	1583	1770	3539	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	813	93	1166	13	99	34	240	774	7	18	835	805
RTOR Reduction (vph)	0	0	789	0	0	0	0	0	4	0	0	0
Lane Group Flow (vph)	447	459	377	0	112	34	240	774	3	18	835	805
Turn Type	Split		Perm	Split		Perm	Prot		Perm	Prot		Perm
Protected Phases	3	3		7	7		5	2		1	6	
Permitted Phases			3			7			2			6
Actuated Green, G (s)	29.0	29.0	29.0		8.8	8.8	9.0	48.5	48.5	3.1	42.6	42.6
Effective Green, g (s)	29.0	29.0	29.0		8.8	8.8	9.0	48.5	48.5	3.1	42.6	42.6
Actuated g/C Ratio	0.26	0.26	0.26		0.08	0.08	0.08	0.43	0.43	0.03	0.38	0.38
Clearance Time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0		3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	430	435	405		144	123	140	1514	677	48	1329	595
v/s Ratio Prot	0.27	c0.27			c0.06		c0.14	c0.22		0.01	0.24	
v/s Ratio Perm			0.24			0.02			0.00			c0.51
v/c Ratio	1.04	1.06	0.93		0.78	0.28	1.71	0.51	0.00	0.38	0.63	1.35
Uniform Delay, d1	42.2	42.2	41.2		51.3	49.3	52.2	23.8	18.6	54.2	28.9	35.4
Progression Factor	1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	54.0	58.4	30.3		22.7	1.2	349.8	1.2	0.0	4.9	0.9	169.7
Delay (s)	96.2	100.6	71.6		74.1	50.5	402.0	25.0	18.6	59.1	29.9	205.1
Level of Service	F	F	E		E	D	F	C	B	E	C	F
Approach Delay (s)		83.3			68.6			113.6			115.3	
Approach LOS		F			E			F			F	
Intersection Summary												
HCM Average Control Delay			100.0				HCM Level of Service			F		
HCM Volume to Capacity ratio			1.30									
Actuated Cycle Length (s)			113.4				Sum of lost time (s)			30.0		
Intersection Capacity Utilization			108.1%				ICU Level of Service			G		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

22: E. HALLANDALE BEACH BLVD & NE 14 AVE



























Beachwalk Traffic Study
Future (2015) Background - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  		 					
Volume (vph)	327	2082	361	59	2059	90	279	142	107	100	121	147
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91	1.00	1.00	0.91		0.97	1.00		1.00	1.00	
Frt	1.00	1.00	0.85	1.00	0.99		1.00	0.94		1.00	0.92	
Flt Protected	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1770	5085	1583	1770	5053		3433	1743		1770	1710	
Flt Permitted	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (perm)	1770	5085	1583	1770	5053		3433	1743		1770	1710	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	355	2263	392	64	2238	98	303	154	116	109	132	160
RTOR Reduction (vph)	0	0	126	0	3	0	0	16	0	0	27	0
Lane Group Flow (vph)	355	2263	266	64	2333	0	303	254	0	109	265	0
Turn Type	Prot		Perm	Prot			Prot			Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			4									
Actuated Green, G (s)	15.0	60.6	60.6	9.6	55.2		17.2	51.7		14.5	49.0	
Effective Green, g (s)	15.0	60.6	60.6	9.6	55.2		17.2	51.7		14.5	49.0	
Actuated g/C Ratio	0.09	0.38	0.38	0.06	0.34		0.11	0.32		0.09	0.31	
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	166	1921	598	106	1739		368	562		160	522	
v/s Ratio Prot	c0.20	c0.45		0.04	c0.46		c0.09	c0.15		0.06	c0.15	
v/s Ratio Perm			0.17									
v/c Ratio	2.14	1.18	0.45	0.60	1.34		0.82	0.45		0.68	0.51	
Uniform Delay, d1	72.7	49.9	37.3	73.5	52.6		70.1	43.1		70.7	45.8	
Progression Factor	1.00	1.00	1.00	1.00	1.00		1.00	1.00		1.00	1.00	
Incremental Delay, d2	532.0	85.9	0.5	9.3	157.8		13.8	2.6		11.3	3.5	
Delay (s)	604.7	135.8	37.9	82.9	210.4		83.9	45.7		82.0	49.3	
Level of Service	F		D	F	F		F	D		F	D	
Approach Delay (s)		178.3			207.0			65.9			58.2	
Approach LOS		F			F			E			E	
Intersection Summary												
HCM Average Control Delay			171.5			HCM Level of Service				F		
HCM Volume to Capacity ratio			1.16									
Actuated Cycle Length (s)			160.4			Sum of lost time (s)			36.0			
Intersection Capacity Utilization			103.2%			ICU Level of Service			G			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

26: E. HALLANDALE BEACH BLVD & NE 10 AVE













Beachwalk Traffic Study
Future (2015) Background - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  		 	  			 				
Volume (vph)	109	2144	143	105	2276	33	86	7	149	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Lane Util. Factor	1.00	0.91	1.00	0.97	0.91	1.00		0.95	1.00			
Frt	1.00	1.00	0.85	1.00	1.00	0.85		1.00	0.85			
Flt Protected	0.95	1.00	1.00	0.95	1.00	1.00		0.96	1.00			
Satd. Flow (prot)	1770	5085	1583	3433	5085	1583		3383	1583			
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00		0.96	1.00			
Satd. Flow (perm)	1770	5085	1583	3433	5085	1583		3383	1583			
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	118	2330	155	114	2474	36	93	8	162	0	0	0
RTOR Reduction (vph)	0	0	15	0	0	8	0	0	86	0	0	0
Lane Group Flow (vph)	118	2330	140	114	2474	28	0	101	76	0	0	0
Turn Type	Prot		Perm	Prot		Perm	Prot		Perm			
Protected Phases	7	4		3	8		5	2				
Permitted Phases			4			8			2			
Actuated Green, G (s)	8.0	87.6	87.6	10.5	90.1	90.1		37.0	37.0			
Effective Green, g (s)	8.0	87.6	87.6	10.5	90.1	90.1		37.0	37.0			
Actuated g/C Ratio	0.05	0.57	0.57	0.07	0.59	0.59		0.24	0.24			
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0			
Lane Grp Cap (vph)	92	2910	906	235	2993	932		818	383			
v/s Ratio Prot	c0.07	0.46		0.03	c0.49							
v/s Ratio Perm			0.09			0.02		0.03	c0.05			
v/c Ratio	1.28	0.80	0.15	0.49	0.83	0.03		0.12	0.20			
Uniform Delay, d1	72.6	25.9	15.4	68.7	25.2	13.2		45.4	46.2			
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00		1.00	1.00			
Incremental Delay, d2	187.4	1.7	0.1	1.6	2.0	0.0		0.1	1.2			
Delay (s)	260.0	27.5	15.5	70.3	27.2	13.2		45.4	47.4			
Level of Service	F	C	B	E	C	B		D	D			
Approach Delay (s)		37.3			28.9			46.7			0.0	
Approach LOS		D			C			D			A	
Intersection Summary												
HCM Average Control Delay			33.8			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.65									
Actuated Cycle Length (s)			153.1			Sum of lost time (s)			12.0			
Intersection Capacity Utilization			69.8%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

29: E. HALLANDALE BEACH BLVD & NE 8 AVE










Beachwalk Traffic Study
Future (2015) Background - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑↑↑	↑	↑	↑↑↑			↑↓		↑	↑	↑
Volume (vph)	0	2307	196	86	2191	0	246	0	39	105	12	170
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Lane Util. Factor		0.91	1.00	1.00	0.91			1.00		0.95	0.95	1.00
Frt		1.00	0.85	1.00	1.00			0.98		1.00	1.00	0.85
Flt Protected		1.00	1.00	0.95	1.00			0.96		0.95	0.96	1.00
Satd. Flow (prot)		5085	1583	1770	5085			1753		1681	1702	1583
Flt Permitted		1.00	1.00	0.05	1.00			0.71		0.84	0.88	1.00
Satd. Flow (perm)		5085	1583	96	5085			1294		1485	1554	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	2508	213	93	2382	0	267	0	42	114	13	185
RTOR Reduction (vph)	0	0	58	0	0	0	0	4	0	0	0	29
Lane Group Flow (vph)	0	2508	155	93	2382	0	0	305	0	63	64	156
Turn Type		Perm		pm+pt			pm+pt			pm+pt		Perm
Protected Phases		4		3	8		5	2		1	6	
Permitted Phases			4	8			2			6		6
Actuated Green, G (s)		71.8	71.8	86.5	86.5			22.8		36.8	36.8	36.8
Effective Green, g (s)		71.8	71.8	86.5	86.5			22.8		36.8	36.8	36.8
Actuated g/C Ratio		0.53	0.53	0.64	0.64			0.17		0.27	0.27	0.27
Clearance Time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Vehicle Extension (s)		3.0	3.0	3.0	3.0			3.0		3.0	3.0	3.0
Lane Grp Cap (vph)		2698	840	169	3251			218		415	431	431
v/s Ratio Prot		c0.49		0.04	c0.47					0.01	0.01	
v/s Ratio Perm			0.10	0.32				c0.24		0.03	0.03	c0.10
v/c Ratio		0.93	0.18	0.55	0.73			1.40		0.15	0.15	0.36
Uniform Delay, d1		29.4	16.5	28.2	16.6			56.3		39.5	37.4	39.8
Progression Factor		1.00	1.00	1.00	1.00			1.00		1.00	1.00	1.00
Incremental Delay, d2		6.4	0.1	3.8	0.9			204.7		0.2	0.2	2.3
Delay (s)		35.8	16.6	32.1	17.4			260.9		39.7	37.5	42.1
Level of Service		D	B	C	B			F		D	D	D
Approach Delay (s)		34.3			18.0			260.9			40.7	
Approach LOS		C			B			F			D	
Intersection Summary												
HCM Average Control Delay			39.7			HCM Level of Service				D		
HCM Volume to Capacity ratio			1.00									
Actuated Cycle Length (s)			135.3			Sum of lost time (s)				24.0		
Intersection Capacity Utilization			87.0%			ICU Level of Service				E		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis

33: DIANA DR & GOLDEN ISLES DR























Beachwalk Traffic Study
Future (2015) Background - PM Peak

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Volume (veh/h)	67	108	116	56	44	219
Sign Control	Stop		Free			Free
Grade	0%		0%			0%
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	73	117	126	61	48	238
Pedestrians						
Lane Width (ft)						
Walking Speed (ft/s)						
Percent Blockage						
Right turn flare (veh)						
Median type			None			None
Median storage veh						
Upstream signal (ft)						345
pX, platoon unblocked						
vC, conflicting volume	490	157			187	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	490	157			187	
tC, single (s)	6.4	6.2			4.1	
tC, 2 stage (s)						
tF (s)	3.5	3.3			2.2	
p0 queue free %	86	87			97	
cM capacity (veh/h)	519	889			1387	
Direction, Lane #	WB 1	NB 1	SB 1			
Volume Total	190	187	286			
Volume Left	73	0	48			
Volume Right	117	61	0			
cSH	698	1700	1387			
Volume to Capacity	0.27	0.11	0.03			
Queue Length 95th (ft)	28	0	3			
Control Delay (s)	12.1	0.0	1.5			
Lane LOS	B		A			
Approach Delay (s)	12.1	0.0	1.5			
Approach LOS	B					
Intersection Summary						
Average Delay			4.1			
Intersection Capacity Utilization			43.8%	ICU Level of Service		A
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

34: E. HALLANDALE BEACH BLVD & U.S. 1

Beachwalk Traffic Study
Future (2015) Background - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	209	1202	570	729	1603	350	847	1473	744	546	1082	121
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Lane Util. Factor	1.00	0.91		0.97	0.91		0.97	0.91	1.00	0.97	0.91	
Frt	1.00	0.95		1.00	0.97		1.00	1.00	0.85	1.00	0.98	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1770	4840		3433	4949		3433	5085	1583	3433	5008	
Flt Permitted	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (perm)	1770	4840		3433	4949		3433	5085	1583	3433	5008	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	227	1307	620	792	1742	380	921	1601	809	593	1176	132
RTOR Reduction (vph)	0	54	0	0	22	0	0	0	207	0	9	0
Lane Group Flow (vph)	227	1873	0	792	2100	0	921	1601	602	593	1299	0
Turn Type	Prot			Prot			Prot		Perm	Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2			
Actuated Green, G (s)	23.0	44.0		24.0	45.0		24.0	44.0	44.0	24.0	42.0	
Effective Green, g (s)	23.0	44.0		24.0	45.0		24.0	44.0	44.0	24.0	42.0	
Actuated g/C Ratio	0.14	0.28		0.15	0.28		0.15	0.28	0.28	0.15	0.26	
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	254	1331		515	1392		515	1398	435	515	1315	
v/s Ratio Prot	0.13	0.39		c0.23	c0.42		c0.27	0.31		0.17	0.26	
v/s Ratio Perm									c0.38			
v/c Ratio	0.89	1.41		1.54	1.51		1.79	1.15	1.38	1.15	0.99	
Uniform Delay, d1	67.3	58.0		68.0	57.5		68.0	58.0	58.0	68.0	58.7	
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00	1.00	1.00	
Incremental Delay, d2	30.1	187.9		251.7	232.8		362.5	74.3	186.2	88.6	22.1	
Delay (s)	97.4	245.9		319.7	290.3		430.5	132.3	244.2	156.6	80.9	
Level of Service	F	F		F	F		F	F	F	F	F	
Approach Delay (s)		230.3			298.3			241.9			104.5	
Approach LOS		F			F			F			F	
Intersection Summary												
HCM Average Control Delay			230.1			HCM Level of Service			F			
HCM Volume to Capacity ratio			1.47									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			126.2%			ICU Level of Service			H			
Analysis Period (min)			15									
c Critical Lane Group												

Intersection Capacity Utilization

Beachwalk Traffic Study

8: E. HALLANDALE BEACH BLVD & EB E. Hallandale Beach Blvd Future (2015) Background - PM Peak



Movement	EBT	EBR	WBL	WBT	NBL	NBR	NBR2	NWL	NWR
Lane Configurations	↑↑↑↵		↵	↑↑↑			↗		
Volume (vph)	1942	7	76	1744	0	0	53	0	0
Pedestrians									
Ped Button									
Pedestrian Timing (s)									
Free Right	No				No		No	No	
Ideal Flow	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Green (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Refr Cycle Length (s)	120								
Volume Combined (vph)	1949	0	76	1744	0	0	53	0	0
Lane Utilization Factor	0.91	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00
Turning Factor (vph)	1.00	0.85	0.95	1.00	0.95	0.85	0.85	0.95	0.85
Saturated Flow (vph)	5173	0	1805	5176	0	0	1615	0	0
Ped Intf Time (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Frequency (%)	0.00			0.00	0.00			0.00	
Protected Option Allowed	Yes			Yes	No			No	
Reference Time (s)	45.2	0.0	5.1	40.4	0.0		3.9	0.0	
Adj Reference Time (s)	49.2	0.0	9.1	44.4	0.0		8.0	0.0	
Permitted Option									
Adj Saturation A (vph)	1724	120		1725	0			0	
Reference Time A (s)	45.2	75.8		40.4	0.0			0.0	
Adj Saturation B (vph)	NA	NA		NA	NA			NA	
Reference Time B (s)	NA	NA		NA	NA			NA	
Reference Time (s)	45.2			75.8					
Adj Reference Time (s)	49.2			79.8					
Split Option									
Ref Time Combined (s)	45.2	5.1		40.4	0.0			0.0	
Ref Time Seperate (s)	45.1	5.1		40.4	0.0			0.0	
Reference Time (s)	45.2	40.4		40.4	0.0			0.0	
Adj Reference Time (s)	49.2	44.4		44.4	0.0			0.0	
Summary	EB WB		NB		NW		Combined		
Protected Option (s)	58.3		NA		NA				
Permitted Option (s)	79.8		Err		Err				
Split Option (s)	93.6		0.0		0.0				
Minimum (s)	58.3		0.0		0.0		58.3		
Right Turns	NBR2								
Adj Reference Time (s)	8.0								
Cross Thru Ref Time (s)	0.0								
Oncoming Left Ref Time (s)	49.2								
Combined (s)	57.2								

Intersection Summary

Intersection Capacity Utilization 48.6% ICU Level of Service A
Reference Times and Phasing Options do not represent an optimized timing plan.























**Synchro Output Sheets – Future (2015)
Future Background Traffic plus project traffic
– AM Peak**



HCM Signalized Intersection Capacity Analysis

3: E. HALLANDALE BEACH BLVD & GOLDEN ISLES DR






















Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	14	1351	63	44	1671	37	263	18	123	14	5	2
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Lane Util. Factor		0.91		1.00	0.91		0.95	0.95	1.00		0.95	
Frt		0.99		1.00	1.00		1.00	1.00	0.85		0.99	
Flt Protected		1.00		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (prot)		5049		1770	5069		1681	1696	1583		3376	
Flt Permitted		0.89		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (perm)		4476		1770	5069		1681	1696	1583		3376	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	15	1468	68	48	1816	40	286	20	134	15	5	2
RTOR Reduction (vph)	0	3	0	0	1	0	0	0	101	0	2	0
Lane Group Flow (vph)	0	1548	0	48	1855	0	152	154	33	0	20	0
Turn Type	Perm			Prot			Split			Perm	Split	
Protected Phases		4		3	8		2	2			6	6
Permitted Phases	4								2			
Actuated Green, G (s)		63.5		7.3	76.8		37.2	37.2	37.2		21.1	
Effective Green, g (s)		63.5		7.3	76.8		37.2	37.2	37.2		21.1	
Actuated g/C Ratio		0.41		0.05	0.50		0.24	0.24	0.24		0.14	
Clearance Time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Vehicle Extension (s)		3.0		3.0	3.0		3.0	3.0	3.0		3.0	
Lane Grp Cap (vph)		1856		84	2543		408	412	385		465	
v/s Ratio Prot				0.03	c0.37		0.09	c0.09			c0.01	
v/s Ratio Perm		c0.35							0.02			
v/c Ratio		0.83		0.57	0.73		0.37	0.37	0.08		0.04	
Uniform Delay, d1		40.1		71.4	30.0		48.2	48.3	44.8		57.2	
Progression Factor		1.00		1.00	1.00		1.00	1.00	1.00		1.00	
Incremental Delay, d2		3.4		9.1	1.1		2.6	2.6	0.4		0.2	
Delay (s)		43.5		80.4	31.1		50.8	50.8	45.2		57.4	
Level of Service		D		F	C		D	D	D		E	
Approach Delay (s)		43.5			32.3			49.1			57.4	
Approach LOS		D			C			D			E	
Intersection Summary												
HCM Average Control Delay			38.8			HCM Level of Service			D			
HCM Volume to Capacity ratio			0.59									
Actuated Cycle Length (s)			153.1			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			61.7%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

6: E. HALLANDALE BEACH BLVD & LAYNE BLVD




Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	80	1333	105	29	1911	84	104	15	53	22	5	76
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Lane Util. Factor	1.00	0.91		1.00	0.91		0.95	0.95	1.00		1.00	1.00
Frt	1.00	0.99		1.00	0.99		1.00	1.00	0.85		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	0.96	1.00		0.96	1.00
Satd. Flow (prot)	1770	5030		1770	5053		1681	1705	1583		1789	1583
Flt Permitted	0.95	1.00		0.95	1.00		0.95	0.78	1.00		0.77	1.00
Satd. Flow (perm)	1770	5030		1770	5053		1681	1381	1583		1440	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	87	1449	114	32	2077	91	113	16	58	24	5	83
RTOR Reduction (vph)	0	4	0	0	3	0	0	0	41	0	0	68
Lane Group Flow (vph)	87	1559	0	32	2165	0	64	65	17	0	29	15
Turn Type	Prot			Prot			Prot		Perm	pm+pt		Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2	6		6
Actuated Green, G (s)	11.4	73.7		5.3	67.6		9.1	39.9	39.9		24.8	24.8
Effective Green, g (s)	11.4	73.7		5.3	67.6		9.1	39.9	39.9		24.8	24.8
Actuated g/C Ratio	0.08	0.54		0.04	0.49		0.07	0.29	0.29		0.18	0.18
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0		3.0	3.0
Lane Grp Cap (vph)	147	2708		69	2495		112	424	461		261	287
v/s Ratio Prot	c0.05	c0.31		0.02	c0.43		c0.04	0.01				
v/s Ratio Perm								c0.03	0.01		0.02	0.01
v/c Ratio	0.59	0.58		0.46	0.87		0.57	0.15	0.04		0.11	0.05
Uniform Delay, d1	60.5	21.1		64.4	30.7		62.0	36.0	34.7		46.8	46.3
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00		1.00	1.00
Incremental Delay, d2	6.3	0.3		4.9	3.5		6.9	0.2	0.1		0.2	0.3
Delay (s)	66.8	21.4		69.3	34.2		68.9	36.1	34.9		47.0	46.7
Level of Service	E	C		E	C		E	D	C		D	D
Approach Delay (s)		23.8			34.7			47.0			46.8	
Approach LOS		C			C			D			D	
Intersection Summary												
HCM Average Control Delay			31.2			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.67									
Actuated Cycle Length (s)			136.9			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			68.2%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis 9: DIANA DR & SE 26 Avenue

Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak






















Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Sign Control		Stop	Stop		Stop	
Volume (vph)	69	1	2	0	1	142
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	75	1	2	0	1	154
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total (vph)	76	2	155			
Volume Left (vph)	75	0	1			
Volume Right (vph)	0	0	154			
Hadj (s)	0.23	0.03	-0.56			
Departure Headway (s)	4.4	4.3	3.5			
Degree Utilization, x	0.09	0.00	0.15			
Capacity (veh/h)	783	799	992			
Control Delay (s)	7.9	7.3	7.2			
Approach Delay (s)	7.9	7.3	7.2			
Approach LOS	A	A	A			
Intersection Summary						
Delay			7.4			
HCM Level of Service			A			
Intersection Capacity Utilization			26.1%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

10: E. HALLANDALE BEACH BLVD & DIPLOMAT PKWY

Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	116	1260	17	15	1609	50	11	1	5	51	23	149
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91		1.00	0.91			1.00		1.00	1.00	
Frt	1.00	1.00		1.00	1.00			0.96		1.00	0.87	
Flt Protected	0.95	1.00		0.95	1.00			0.97		0.95	1.00	
Satd. Flow (prot)	1770	5075		1770	5062			1735		1770	1621	
Flt Permitted	0.95	1.00		0.95	1.00			0.82		0.75	1.00	
Satd. Flow (perm)	1770	5075		1770	5062			1474		1389	1621	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	126	1370	18	16	1749	54	12	1	5	55	25	162
RTOR Reduction (vph)	0	1	0	0	2	0	0	4	0	0	119	0
Lane Group Flow (vph)	126	1387	0	16	1801	0	0	14	0	55	68	0
Turn Type	Prot			Prot			Perm			Perm		
Protected Phases	7	4		3	8			2			6	
Permitted Phases							2			6		
Actuated Green, G (s)	14.5	82.0		2.9	70.4			37.6		37.6	37.6	
Effective Green, g (s)	14.5	82.0		2.9	70.4			37.6		37.6	37.6	
Actuated g/C Ratio	0.10	0.58		0.02	0.50			0.27		0.27	0.27	
Clearance Time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	183	2962		37	2536			394		372	434	
v/s Ratio Prot	c0.07	0.27		0.01	c0.36						c0.04	
v/s Ratio Perm								0.01		0.04		
v/c Ratio	0.69	0.47		0.43	0.71			0.04		0.15	0.16	
Uniform Delay, d1	60.8	16.8		68.0	27.1			38.1		39.2	39.3	
Progression Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Incremental Delay, d2	10.3	0.1		7.9	1.0			0.2		0.8	0.8	
Delay (s)	71.1	16.9		75.9	28.1			38.2		40.1	40.1	
Level of Service	E	B		E	C			D		D	D	
Approach Delay (s)		21.4			28.5			38.2			40.1	
Approach LOS		C			C			D			D	
Intersection Summary												
HCM Average Control Delay			26.3			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.54									
Actuated Cycle Length (s)			140.5			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			64.1%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

17: E. HALLANDALE BEACH BLVD & 3 Islands Drive

Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak


























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	←←	↑↑↑	↑↑↑	↑	↑	↑
Volume (vph)	227	1010	1265	158	372	368
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.97	0.91	0.91	1.00	1.00	1.00
Frt	1.00	1.00	1.00	0.85	1.00	0.85
Flt Protected	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (prot)	3433	5085	5085	1583	1770	1583
Flt Permitted	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (perm)	3433	5085	5085	1583	1770	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	247	1098	1375	172	404	400
RTOR Reduction (vph)	0	0	0	105	0	210
Lane Group Flow (vph)	247	1098	1375	67	404	190
Turn Type	Prot			Perm		custom
Protected Phases	7	4	8			
Permitted Phases				8	6	6
Actuated Green, G (s)	12.8	53.6	34.8	34.8	24.2	24.2
Effective Green, g (s)	12.8	53.6	34.8	34.8	24.2	24.2
Actuated g/C Ratio	0.14	0.60	0.39	0.39	0.27	0.27
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	489	3035	1971	613	477	427
v/s Ratio Prot	c0.07	0.22	c0.27			
v/s Ratio Perm				0.04	c0.23	0.12
v/c Ratio	0.51	0.36	0.70	0.11	0.85	0.44
Uniform Delay, d1	35.6	9.3	23.1	17.6	31.0	27.2
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	0.8	0.1	1.1	0.1	16.8	3.3
Delay (s)	36.4	9.4	24.2	17.7	47.8	30.5
Level of Service	D	A	C	B	D	C
Approach Delay (s)		14.3	23.5		39.2	
Approach LOS		B	C		D	
Intersection Summary						
HCM Average Control Delay			23.6		HCM Level of Service	C
HCM Volume to Capacity ratio			0.71			
Actuated Cycle Length (s)			89.8		Sum of lost time (s)	18.0
Intersection Capacity Utilization			66.5%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

21: WB E. Hallandale Beach Blvd & S. OCEAN DR



























Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR2	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR2
Lane Configurations												
Volume (vph)	562	37	892	6	179	6	205	474	6	6	362	355
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.95	0.95	1.00		1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00
Frt	1.00	1.00	0.85		1.00	0.85	1.00	1.00	0.85	1.00	1.00	0.85
Flt Protected	0.95	0.96	1.00		1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (prot)	1681	1695	1583		1860	1583	1770	3539	1583	1770	3539	1583
Flt Permitted	0.95	0.96	1.00		1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	1681	1695	1583		1860	1583	1770	3539	1583	1770	3539	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	611	40	970	7	195	7	223	515	7	7	393	386
RTOR Reduction (vph)	0	0	743	0	0	0	0	0	4	0	0	0
Lane Group Flow (vph)	324	327	227	0	202	7	223	515	3	7	393	386
Turn Type	Split		Perm	Split		Perm	Prot		Perm	Prot		Perm
Protected Phases	3	3		7	7		5	2		1	6	
Permitted Phases			3			7			2			6
Actuated Green, G (s)	25.1	25.1	25.1		14.0	14.0	7.0	42.8	42.8	1.3	37.1	37.1
Effective Green, g (s)	25.1	25.1	25.1		14.0	14.0	7.0	42.8	42.8	1.3	37.1	37.1
Actuated g/C Ratio	0.23	0.23	0.23		0.13	0.13	0.07	0.40	0.40	0.01	0.35	0.35
Clearance Time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0		3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	394	397	371		243	207	116	1413	632	21	1225	548
v/s Ratio Prot	0.19	c0.19			c0.11		c0.13	c0.15		0.00	0.11	
v/s Ratio Perm			0.14			0.00			0.00			c0.24
v/c Ratio	0.82	0.82	0.61		0.83	0.03	1.92	0.36	0.00	0.33	0.32	0.70
Uniform Delay, d1	38.9	39.0	36.7		45.4	40.7	50.1	22.6	19.4	52.5	25.8	30.3
Progression Factor	1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	17.4	17.4	7.3		20.8	0.1	445.2	0.7	0.0	9.1	0.2	4.1
Delay (s)	56.3	56.3	44.0		66.3	40.8	495.3	23.4	19.4	61.7	25.9	34.4
Level of Service	E	E	D		E	D	F	C	B	E	C	C
Approach Delay (s)		49.0			65.4			164.6			30.4	
Approach LOS		D			E			F			C	
Intersection Summary												
HCM Average Control Delay			71.3				HCM Level of Service			E		
HCM Volume to Capacity ratio			0.89									
Actuated Cycle Length (s)			107.2				Sum of lost time (s)			30.0		
Intersection Capacity Utilization			90.0%				ICU Level of Service			E		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

22: E. HALLANDALE BEACH BLVD & NE 14 AVE






















Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  		 					
Volume (vph)	102	1584	228	20	1865	54	249	73	28	135	84	196
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91	1.00	1.00	0.91		0.97	1.00		1.00	1.00	
Frt	1.00	1.00	0.85	1.00	1.00		1.00	0.96		1.00	0.89	
Flt Protected	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1770	5085	1583	1770	5064		3433	1786		1770	1667	
Flt Permitted	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (perm)	1770	5085	1583	1770	5064		3433	1786		1770	1667	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	111	1722	248	22	2027	59	271	79	30	147	91	213
RTOR Reduction (vph)	0	0	100	0	2	0	0	8	0	0	52	0
Lane Group Flow (vph)	111	1722	148	22	2084	0	271	101	0	147	252	0
Turn Type	Prot		Perm	Prot			Prot			Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			4									
Actuated Green, G (s)	12.4	66.8	66.8	5.1	59.5		16.5	49.2		16.5	49.2	
Effective Green, g (s)	12.4	66.8	66.8	5.1	59.5		16.5	49.2		16.5	49.2	
Actuated g/C Ratio	0.08	0.41	0.41	0.03	0.37		0.10	0.30		0.10	0.30	
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	136	2102	654	56	1865		351	544		181	508	
v/s Ratio Prot	c0.06	c0.34		0.01	c0.41		0.08	0.06		c0.08	c0.15	
v/s Ratio Perm			0.09									
v/c Ratio	0.82	0.82	0.23	0.39	1.12		0.77	0.19		0.81	0.50	
Uniform Delay, d1	73.5	42.0	30.7	76.7	51.1		70.7	41.4		71.0	46.0	
Progression Factor	1.00	1.00	1.00	1.00	1.00		1.00	1.00		1.00	1.00	
Incremental Delay, d2	30.0	2.6	0.2	4.5	60.8		10.1	0.7		23.4	3.4	
Delay (s)	103.5	44.7	30.8	81.2	111.9		80.8	42.2		94.5	49.5	
Level of Service	F	D	C	F	F		F	D		F	D	
Approach Delay (s)		46.2			111.6			69.7			64.1	
Approach LOS		D			F			E			E	
Intersection Summary												
HCM Average Control Delay			77.0			HCM Level of Service				E		
HCM Volume to Capacity ratio			0.88									
Actuated Cycle Length (s)			161.6			Sum of lost time (s)			30.0			
Intersection Capacity Utilization			86.5%			ICU Level of Service			E			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

26: E. HALLANDALE BEACH BLVD & NE 10 AVE













Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	119	1815	135	281	2051	35	67	2	112	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Lane Util. Factor	1.00	0.91	1.00	0.97	0.91	1.00		0.95	1.00			
Frt	1.00	1.00	0.85	1.00	1.00	0.85		1.00	0.85			
Flt Protected	0.95	1.00	1.00	0.95	1.00	1.00		0.95	1.00			
Satd. Flow (prot)	1770	5085	1583	3433	5085	1583		3375	1583			
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00		0.95	1.00			
Satd. Flow (perm)	1770	5085	1583	3433	5085	1583		3375	1583			
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	129	1973	147	305	2229	38	73	2	122	0	0	0
RTOR Reduction (vph)	0	0	18	0	0	8	0	0	92	0	0	0
Lane Group Flow (vph)	129	1973	129	305	2229	30	0	75	30	0	0	0
Turn Type	Prot		Perm	Prot		Perm	Prot		Perm			
Protected Phases	7	4		3	8		5	2				
Permitted Phases			4			8			2			
Actuated Green, G (s)	16.5	82.0	82.0	15.8	81.3	81.3		37.1	37.1			
Effective Green, g (s)	16.5	82.0	82.0	15.8	81.3	81.3		37.1	37.1			
Actuated g/C Ratio	0.11	0.54	0.54	0.10	0.53	0.53		0.24	0.24			
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0			
Lane Grp Cap (vph)	191	2727	849	355	2704	842		819	384			
v/s Ratio Prot	0.07	0.39		c0.09	c0.44							
v/s Ratio Perm			0.08			0.02		0.02	0.02			
v/c Ratio	0.68	0.72	0.15	0.86	0.82	0.04		0.09	0.08			
Uniform Delay, d1	65.6	26.9	17.9	67.5	29.8	17.1		44.8	44.7			
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00		1.00	1.00			
Incremental Delay, d2	9.1	1.0	0.1	18.3	2.2	0.0		0.0	0.4			
Delay (s)	74.7	27.8	18.0	85.7	32.0	17.1		44.9	45.1			
Level of Service	E	C	B	F	C	B		D	D			
Approach Delay (s)		29.9			38.2			45.0			0.0	
Approach LOS		C			D			D			A	
Intersection Summary												
HCM Average Control Delay			34.7			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.62									
Actuated Cycle Length (s)			152.9			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			64.9%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

29: E. HALLANDALE BEACH BLVD & NE 8 AVE










Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑↑↑	↑	↑	↑↑↑			↑↓		↑	↑	↑
Volume (vph)	0	2105	241	3	2153	0	192	0	96	101	8	189
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Lane Util. Factor		0.91	1.00	1.00	0.91			1.00		0.95	0.95	1.00
Frt		1.00	0.85	1.00	1.00			0.96		1.00	1.00	0.85
Flt Protected		1.00	1.00	0.95	1.00			0.97		0.95	0.96	1.00
Satd. Flow (prot)		5085	1583	1770	5085			1722		1681	1697	1583
Flt Permitted		1.00	1.00	0.05	1.00			0.76		0.66	0.73	1.00
Satd. Flow (perm)		5085	1583	86	5085			1353		1168	1296	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	2288	262	3	2340	0	209	0	104	110	9	205
RTOR Reduction (vph)	0	0	69	0	0	0	0	12	0	0	0	43
Lane Group Flow (vph)	0	2288	193	3	2340	0	0	301	0	59	60	162
Turn Type			Perm	pm+pt			pm+pt			pm+pt		Perm
Protected Phases		4		3	8		5	2		1	6	
Permitted Phases			4	8			2			6		6
Actuated Green, G (s)		81.0	81.0	88.1	88.1			23.2		36.9	36.9	36.9
Effective Green, g (s)		81.0	81.0	88.1	88.1			23.2		36.9	36.9	36.9
Actuated g/C Ratio		0.59	0.59	0.64	0.64			0.17		0.27	0.27	0.27
Clearance Time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Vehicle Extension (s)		3.0	3.0	3.0	3.0			3.0		3.0	3.0	3.0
Lane Grp Cap (vph)		3006	936	69	3270			229		343	372	426
v/s Ratio Prot		c0.45		0.00	c0.46					0.01	0.01	
v/s Ratio Perm			0.12	0.03			c0.22			0.04	0.03	c0.10
v/c Ratio		0.76	0.21	0.04	0.72		1.31			0.17	0.16	0.38
Uniform Delay, d1		20.8	13.0	17.6	16.2		56.9			40.2	38.2	40.7
Progression Factor		1.00	1.00	1.00	1.00		1.00			1.00	1.00	1.00
Incremental Delay, d2		1.2	0.1	0.3	0.8		168.2			0.2	0.2	2.6
Delay (s)		22.0	13.1	17.8	16.9		225.1			40.5	38.4	43.3
Level of Service		C	B	B	B		F			D	D	D
Approach Delay (s)		21.1			16.9		225.1				41.9	
Approach LOS		C			B		F				D	
Intersection Summary												
HCM Average Control Delay			32.1			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.88									
Actuated Cycle Length (s)			137.0			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			84.8%			ICU Level of Service			E			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis

33: DIANA DR & GOLDEN ISLES DR


































Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Volume (veh/h)	50	160	243	69	12	70
Sign Control	Stop		Free			Free
Grade	0%		0%			0%
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	54	174	264	75	13	76
Pedestrians						
Lane Width (ft)						
Walking Speed (ft/s)						
Percent Blockage						
Right turn flare (veh)						
Median type			None			None
Median storage (veh)						
Upstream signal (ft)						345
pX, platoon unblocked						
vC, conflicting volume	404	302			339	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	404	302			339	
tC, single (s)	6.4	6.2			4.1	
tC, 2 stage (s)						
tF (s)	3.5	3.3			2.2	
p0 queue free %	91	76			99	
cM capacity (veh/h)	596	738			1220	
Direction, Lane #	WB 1	NB 1	SB 1			
Volume Total	228	339	89			
Volume Left	54	0	13			
Volume Right	174	75	0			
cSH	698	1700	1220			
Volume to Capacity	0.33	0.20	0.01			
Queue Length 95th (ft)	36	0	1			
Control Delay (s)	12.6	0.0	1.2			
Lane LOS	B		A			
Approach Delay (s)	12.6	0.0	1.2			
Approach LOS	B					
Intersection Summary						
Average Delay		4.6				
Intersection Capacity Utilization		36.3%		ICU Level of Service		A
Analysis Period (min)		15				

HCM Signalized Intersection Capacity Analysis

34: E. HALLANDALE BEACH BLVD & U.S. 1

Beachwalk Traffic Study
Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  		 	  		 	  		 	  	
Volume (vph)	116	1308	655	698	1424	306	483	696	462	444	1237	88
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Lane Util. Factor	1.00	0.91		0.97	0.91		0.97	0.91	1.00	0.97	0.91	
Frt	1.00	0.95		1.00	0.97		1.00	1.00	0.85	1.00	0.99	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1770	4831		3433	4950		3433	5085	1583	3433	5034	
Flt Permitted	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (perm)	1770	4831		3433	4950		3433	5085	1583	3433	5034	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	126	1422	712	759	1548	333	525	757	502	483	1345	96
RTOR Reduction (vph)	0	57	0	0	20	0	0	0	209	0	5	0
Lane Group Flow (vph)	126	2077	0	759	1861	0	525	757	293	483	1436	0
Turn Type	Prot			Prot			Prot		Perm	Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2			
Actuated Green, G (s)	16.7	44.0		24.0	51.3		24.0	44.1	44.1	23.9	42.0	
Effective Green, g (s)	16.7	44.0		24.0	51.3		24.0	44.1	44.1	23.9	42.0	
Actuated g/C Ratio	0.10	0.28		0.15	0.32		0.15	0.28	0.28	0.15	0.26	
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	185	1329		515	1587		515	1402	436	513	1321	
v/s Ratio Prot	0.07	c0.43		c0.22	c0.38		c0.15	0.15		0.14	c0.29	
v/s Ratio Perm									0.19			
v/c Ratio	0.68	1.56		1.47	1.17		1.02	0.54	0.67	0.94	1.09	
Uniform Delay, d1	69.1	58.0		68.0	54.4		68.0	49.3	51.5	67.4	59.0	
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00	1.00	1.00	
Incremental Delay, d2	9.9	257.1		223.6	84.8		44.6	1.5	8.1	25.8	51.9	
Delay (s)	79.0	315.1		291.6	139.2		112.6	50.8	59.6	93.1	110.9	
Level of Service	E	F		F	F		F	D	E	F	F	
Approach Delay (s)		302.0			183.0			71.5			106.5	
Approach LOS		F			F			E			F	
Intersection Summary												
HCM Average Control Delay			174.0			HCM Level of Service			F			
HCM Volume to Capacity ratio			1.36									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			32.0			
Intersection Capacity Utilization			121.1%			ICU Level of Service			H			
Analysis Period (min)			15									
c Critical Lane Group												

Intersection Capacity Utilization

Beachwalk Traffic Study

8: E. HALLANDALE BEACH BLVD & EB E. Hallandale Beach Blvd

Future (2015) Total Traffic - AM Peak



Movement	EBT	EBR	WBL	WBT	NBL	NBR	NBR2	NWL	NWR
Lane Configurations	↑↑↑↱		↱	↑↑↑			↱		
Volume (vph)	1282	96	72	1448	0	0	83	0	0
Pedestrians									
Ped Button									
Pedestrian Timing (s)									
Free Right	No				No		No	No	
Ideal Flow	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Green (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Refr Cycle Length (s)	120								
Volume Combined (vph)	1378	0	72	1448	0	0	83	0	0
Lane Utilization Factor	0.91	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00
Turning Factor (vph)	0.99	0.85	0.95	1.00	0.95	0.85	0.85	0.95	0.85
Saturated Flow (vph)	5122	0	1805	5176	0	0	1615	0	0
Ped Intf Time (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Frequency (%)	0.00			0.00	0.00			0.00	
Protected Option Allowed	Yes			Yes	No			No	
Reference Time (s)	32.3	0.0	4.8	33.6	0.0		6.2	0.0	
Adj Reference Time (s)	36.3	0.0	8.8	37.6	0.0		10.2	0.0	
Permitted Option									
Adj Saturation A (vph)	1707	120		1725	0			0	
Reference Time A (s)	32.3	71.8		33.6	0.0			0.0	
Adj Saturation B (vph)	NA	NA		NA	NA			NA	
Reference Time B (s)	NA	NA		NA	NA			NA	
Reference Time (s)	32.3			71.8					
Adj Reference Time (s)	36.3			75.8					
Split Option									
Ref Time Combined (s)	32.3	4.8		33.6	0.0			0.0	
Ref Time Seperate (s)	30.0	4.8		33.6	0.0			0.0	
Reference Time (s)	32.3	33.6		33.6	0.0			0.0	
Adj Reference Time (s)	36.3	37.6		37.6	0.0			0.0	
Summary	EB WB		NB		NW		Combined		
Protected Option (s)	45.1		NA		NA				
Permitted Option (s)	75.8		Err		Err				
Split Option (s)	73.9		0.0		0.0				
Minimum (s)	45.1		0.0		0.0		45.1		
Right Turns	NBR2								
Adj Reference Time (s)	10.2								
Cross Thru Ref Time (s)	0.0								
Oncoming Left Ref Time (s)	36.3								
Combined (s)	46.5								

Intersection Summary

Intersection Capacity Utilization 38.7% ICU Level of Service A
 Reference Times and Phasing Options do not represent an optimized timing plan.


























**Synchro Output Sheets – Future (2015)
Future Background Traffic plus project traffic
– PM Peak**



HCM Signalized Intersection Capacity Analysis

3: E. HALLANDALE BEACH BLVD & GOLDEN ISLES DR






















Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  			 			 	
Volume (vph)	10	2123	146	119	1677	51	230	19	66	75	13	9
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Lane Util. Factor		0.91		1.00	0.91		0.95	0.95	1.00		0.95	
Frt		0.99		1.00	1.00		1.00	1.00	0.85		0.99	
Flt Protected		1.00		0.95	1.00		0.95	0.96	1.00		0.96	
Satd. Flow (prot)		5035		1770	5063		1681	1698	1583		3359	
Flt Permitted		0.92		0.95	1.00		0.95	0.96	1.00		0.96	
Satd. Flow (perm)		4609		1770	5063		1681	1698	1583		3359	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	11	2308	159	129	1823	55	250	21	72	82	14	10
RTOR Reduction (vph)	0	5	0	0	2	0	0	0	55	0	5	0
Lane Group Flow (vph)	0	2473	0	129	1876	0	135	136	17	0	101	0
Turn Type	Perm			Prot			Split			Perm	Split	
Protected Phases	4			3			2			2	6	
Permitted Phases	4									2		
Actuated Green, G (s)	66.0			12.0			37.0			37.0	21.0	
Effective Green, g (s)	66.0			12.0			37.0			37.0	21.0	
Actuated g/C Ratio	0.41			0.08			0.23			0.23	0.13	
Clearance Time (s)	6.0			6.0			6.0			6.0	6.0	
Vehicle Extension (s)	3.0			3.0			3.0			3.0	3.0	
Lane Grp Cap (vph)	1901			133			389			393	366	
v/s Ratio Prot				c0.07			c0.08			0.08	c0.03	
v/s Ratio Perm	c0.54									0.01		
v/c Ratio	1.30			0.97			0.35			0.35	0.05	
Uniform Delay, d1	47.0			73.8			51.4			51.4	47.8	
Progression Factor	1.00			1.00			1.00			1.00	1.00	
Incremental Delay, d2	139.4			67.9			2.4			2.4	0.2	
Delay (s)	186.4			141.7			53.8			53.8	48.0	
Level of Service	F			F			D			D	D	
Approach Delay (s)	186.4			36.8			52.6				63.5	
Approach LOS	F			D			D				E	
Intersection Summary												
HCM Average Control Delay	113.6			HCM Level of Service			F					
HCM Volume to Capacity ratio	0.85											
Actuated Cycle Length (s)	160.0			Sum of lost time (s)			24.0					
Intersection Capacity Utilization	106.5%			ICU Level of Service			G					
Analysis Period (min)	15											
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

6: E. HALLANDALE BEACH BLVD & LAYNE BLVD




Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	125	2050	54	25	1733	33	167	15	61	144	12	102
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Lane Util. Factor	1.00	0.91		1.00	0.91		0.95	0.95	1.00		1.00	1.00
Frt	1.00	1.00		1.00	1.00		1.00	1.00	0.85		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	0.96	1.00		0.96	1.00
Satd. Flow (prot)	1770	5066		1770	5071		1681	1698	1583		1781	1583
Flt Permitted	0.95	1.00		0.95	1.00		0.95	0.40	1.00		0.67	1.00
Satd. Flow (perm)	1770	5066		1770	5071		1681	702	1583		1244	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	136	2228	59	27	1884	36	182	16	66	157	13	111
RTOR Reduction (vph)	0	1	0	0	1	0	0	0	46	0	0	93
Lane Group Flow (vph)	136	2286	0	27	1919	0	98	100	20	0	170	18
Turn Type	Prot			Prot			Prot		Perm	pm+pt		Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2	6		6
Actuated Green, G (s)	13.6	74.4		5.1	65.9		13.3	41.4	41.4		22.1	22.1
Effective Green, g (s)	13.6	74.4		5.1	65.9		13.3	41.4	41.4		22.1	22.1
Actuated g/C Ratio	0.10	0.54		0.04	0.47		0.10	0.30	0.30		0.16	0.16
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0		3.0	3.0
Lane Grp Cap (vph)	173	2714		65	2406		161	305	472		198	252
v/s Ratio Prot	c0.08	c0.45		0.02	0.38		c0.06	0.03				
v/s Ratio Perm								0.07	0.01		c0.14	0.01
v/c Ratio	0.79	0.84		0.42	0.80		0.61	0.33	0.04		0.86	0.07
Uniform Delay, d1	61.2	27.3		65.4	30.9		60.3	37.9	34.7		56.9	49.7
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00		1.00	1.00
Incremental Delay, d2	20.5	2.5		4.3	1.9		6.4	0.6	0.2		28.9	0.5
Delay (s)	81.8	29.8		69.7	32.8		66.7	38.6	34.8		85.7	50.2
Level of Service	F	C		E	C		E	D	C		F	D
Approach Delay (s)		32.7			33.3			48.1			71.7	
Approach LOS		C			C			D			E	
Intersection Summary												
HCM Average Control Delay			36.0			HCM Level of Service				D		
HCM Volume to Capacity ratio			0.84									
Actuated Cycle Length (s)			138.9			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			74.4%			ICU Level of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis9: DIANA DR & SE 26 Avenue

Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak






















Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Sign Control		Stop	Stop		Stop	
Volume (vph)	45	6	1	2	5	161
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	49	7	1	2	5	175
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total (vph)	55	3	180			
Volume Left (vph)	49	0	5			
Volume Right (vph)	0	2	175			
Hadj (s)	0.21	-0.37	-0.54			
Departure Headway (s)	4.5	3.9	3.5			
Degree Utilization, x	0.07	0.00	0.18			
Capacity (veh/h)	775	868	1004			
Control Delay (s)	7.8	6.9	7.2			
Approach Delay (s)	7.8	6.9	7.2			
Approach LOS	A	A	A			
Intersection Summary						
Delay			7.4			
HCM Level of Service			A			
Intersection Capacity Utilization			26.4%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

10: E. HALLANDALE BEACH BLVD & DIPLOMAT PKWY

Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	194	2145	2	4	1631	51	9	11	13	74	1	118
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91		1.00	0.91			1.00		1.00	1.00	
Frt	1.00	1.00		1.00	1.00			0.95		1.00	0.85	
Flt Protected	0.95	1.00		0.95	1.00			0.99		0.95	1.00	
Satd. Flow (prot)	1770	5085		1770	5062			1741		1770	1585	
Flt Permitted	0.95	1.00		0.95	1.00			0.92		0.73	1.00	
Satd. Flow (perm)	1770	5085		1770	5062			1631		1367	1585	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	211	2332	2	4	1773	55	10	12	14	80	1	128
RTOR Reduction (vph)	0	0	0	0	2	0	0	11	0	0	96	0
Lane Group Flow (vph)	211	2334	0	4	1826	0	0	25	0	80	33	0
Turn Type	Prot			Prot			Perm			Perm		
Protected Phases	7	4		3	8			2			6	
Permitted Phases							2			6		
Actuated Green, G (s)	19.1	92.5		1.2	74.6			37.2		37.2	37.2	
Effective Green, g (s)	19.1	92.5		1.2	74.6			37.2		37.2	37.2	
Actuated g/C Ratio	0.13	0.62		0.01	0.50			0.25		0.25	0.25	
Clearance Time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	227	3159		14	2536			407		342	396	
v/s Ratio Prot	c0.12	c0.46		0.00	0.36						0.02	
v/s Ratio Perm								0.02		c0.06		
v/c Ratio	0.93	0.74		0.29	0.72			0.06		0.23	0.08	
Uniform Delay, d1	64.2	19.7		73.4	29.0			42.6		44.5	42.8	
Progression Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Incremental Delay, d2	40.2	0.9		10.9	1.0			0.3		1.6	0.4	
Delay (s)	104.4	20.7		84.4	30.0			42.9		46.1	43.2	
Level of Service	F	C		F	C			D		D	D	
Approach Delay (s)		27.6			30.1			42.9			44.3	
Approach LOS		C			C			D			D	
Intersection Summary												
HCM Average Control Delay			29.5			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.61									
Actuated Cycle Length (s)			148.9			Sum of lost time (s)			12.0			
Intersection Capacity Utilization			70.6%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

17: E. HALLANDALE BEACH BLVD & 3 ISLANDS BLVD

Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak


























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	←←	↑↑↑	↑↑↑	↑	↑	↑
Volume (vph)	583	1600	1457	319	349	294
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.97	0.91	0.91	1.00	1.00	1.00
Frt	1.00	1.00	1.00	0.85	1.00	0.85
Flt Protected	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (prot)	3433	5085	5085	1583	1770	1583
Flt Permitted	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (perm)	3433	5085	5085	1583	1770	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	634	1739	1584	347	379	320
RTOR Reduction (vph)	0	0	0	202	0	194
Lane Group Flow (vph)	634	1739	1584	145	379	126
Turn Type	Prot			Perm		custom
Protected Phases	7	4	8			
Permitted Phases				8	6	6
Actuated Green, G (s)	24.1	77.8	47.7	47.7	24.1	24.1
Effective Green, g (s)	24.1	77.8	47.7	47.7	24.1	24.1
Actuated g/C Ratio	0.21	0.68	0.42	0.42	0.21	0.21
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	726	3473	2130	663	375	335
v/s Ratio Prot	c0.18	0.34	c0.31			
v/s Ratio Perm				0.09	c0.21	0.08
v/c Ratio	0.87	0.50	0.74	0.22	1.01	0.38
Uniform Delay, d1	43.4	8.7	27.9	21.2	44.9	38.5
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	11.3	0.1	1.4	0.2	49.2	3.2
Delay (s)	54.7	8.8	29.4	21.4	94.1	41.7
Level of Service	D	A	C	C	F	D
Approach Delay (s)		21.1	27.9		70.1	
Approach LOS		C	C		E	
Intersection Summary						
HCM Average Control Delay			30.6		HCM Level of Service	C
HCM Volume to Capacity ratio			0.84			
Actuated Cycle Length (s)			113.9		Sum of lost time (s)	18.0
Intersection Capacity Utilization			79.1%		ICU Level of Service	D
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

21: WB E. Hallandale Beach Blvd & S. OCEAN DR



























Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR2	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR2
Lane Configurations												
Volume (vph)	761	87	1089	12	92	31	228	712	6	17	768	755
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.95	0.95	1.00		1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00
Frt	1.00	1.00	0.85		1.00	0.85	1.00	1.00	0.85	1.00	1.00	0.85
Flt Protected	0.95	0.96	1.00		0.99	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (prot)	1681	1702	1583		1852	1583	1770	3539	1583	1770	3539	1583
Flt Permitted	0.95	0.96	1.00		0.99	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	1681	1702	1583		1852	1583	1770	3539	1583	1770	3539	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	827	95	1184	13	100	34	248	774	7	18	835	821
RTOR Reduction (vph)	0	0	789	0	0	0	0	0	4	0	0	0
Lane Group Flow (vph)	455	467	395	0	113	34	248	774	3	18	835	821
Turn Type	Split		Perm	Split		Perm	Prot		Perm	Prot		Perm
Protected Phases	3	3		7	7		5	2		1	6	
Permitted Phases			3			7			2			6
Actuated Green, G (s)	29.0	29.0	29.0		8.8	8.8	9.0	48.5	48.5	3.1	42.6	42.6
Effective Green, g (s)	29.0	29.0	29.0		8.8	8.8	9.0	48.5	48.5	3.1	42.6	42.6
Actuated g/C Ratio	0.26	0.26	0.26		0.08	0.08	0.08	0.43	0.43	0.03	0.38	0.38
Clearance Time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0		3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	430	435	405		144	123	140	1514	677	48	1329	595
v/s Ratio Prot	0.27	c0.27			c0.06		c0.14	c0.22		0.01	0.24	
v/s Ratio Perm			0.25			0.02			0.00			c0.52
v/c Ratio	1.06	1.07	0.98		0.78	0.28	1.77	0.51	0.00	0.38	0.63	1.38
Uniform Delay, d1	42.2	42.2	41.8		51.4	49.3	52.2	23.8	18.6	54.2	28.9	35.4
Progression Factor	1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	59.6	64.2	39.0		23.8	1.2	374.5	1.2	0.0	4.9	0.9	181.3
Delay (s)	101.8	106.4	80.8		75.2	50.5	426.7	25.0	18.6	59.1	29.9	216.7
Level of Service	F	F	F		E	D	F	C	B	E	C	F
Approach Delay (s)		91.0			69.5			121.8			121.8	
Approach LOS		F			E			F			F	
Intersection Summary												
HCM Average Control Delay			107.2				HCM Level of Service			F		
HCM Volume to Capacity ratio			1.32									
Actuated Cycle Length (s)			113.4				Sum of lost time (s)			30.0		
Intersection Capacity Utilization			109.2%				ICU Level of Service			H		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

22: E. HALLANDALE BEACH BLVD & NE 14 AVE



























Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  		 					
Volume (vph)	327	2145	361	64	2134	96	279	142	112	104	121	147
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91	1.00	1.00	0.91		0.97	1.00		1.00	1.00	
Frt	1.00	1.00	0.85	1.00	0.99		1.00	0.93		1.00	0.92	
Flt Protected	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1770	5085	1583	1770	5053		3433	1739		1770	1710	
Flt Permitted	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (perm)	1770	5085	1583	1770	5053		3433	1739		1770	1710	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	355	2332	392	70	2320	104	303	154	122	113	132	160
RTOR Reduction (vph)	0	0	125	0	3	0	0	18	0	0	27	0
Lane Group Flow (vph)	355	2332	267	70	2421	0	303	258	0	113	265	0
Turn Type	Prot		Perm	Prot			Prot			Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			4									
Actuated Green, G (s)	15.0	57.6	57.6	11.4	54.0		17.2	51.4		14.8	49.0	
Effective Green, g (s)	15.0	57.6	57.6	11.4	54.0		17.2	51.4		14.8	49.0	
Actuated g/C Ratio	0.09	0.36	0.36	0.07	0.34		0.11	0.32		0.09	0.31	
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	167	1840	573	127	1714		371	561		165	526	
v/s Ratio Prot	c0.20	c0.46		0.04	c0.48		c0.09	0.15		0.06	c0.16	
v/s Ratio Perm			0.17									
v/c Ratio	2.13	1.27	0.47	0.55	1.41		0.82	0.46		0.68	0.50	
Uniform Delay, d1	72.1	50.8	39.0	71.4	52.6		69.5	42.9		69.9	45.1	
Progression Factor	1.00	1.00	1.00	1.00	1.00		1.00	1.00		1.00	1.00	
Incremental Delay, d2	526.2	124.8	0.6	5.1	189.1		13.0	2.7		11.2	3.4	
Delay (s)	598.3	175.6	39.6	76.5	241.7		82.5	45.6		81.1	48.6	
Level of Service	F	F	D	E	F		F	D		F	D	
Approach Delay (s)		207.0			237.0			64.9			57.6	
Approach LOS		F			F			E			E	
Intersection Summary												
HCM Average Control Delay			196.7			HCM Level of Service				F		
HCM Volume to Capacity ratio			1.15									
Actuated Cycle Length (s)			159.2			Sum of lost time (s)			30.0			
Intersection Capacity Utilization			104.8%			ICU Level of Service			G			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

26: E. HALLANDALE BEACH BLVD & NE 10 AVE





















Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  		 	  			 				
Volume (vph)	109	2208	143	106	2348	34	86	7	149	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Lane Util. Factor	1.00	0.91	1.00	0.97	0.91	1.00		0.95	1.00			
Frt	1.00	1.00	0.85	1.00	1.00	0.85		1.00	0.85			
Flt Protected	0.95	1.00	1.00	0.95	1.00	1.00		0.96	1.00			
Satd. Flow (prot)	1770	5085	1583	3433	5085	1583		3383	1583			
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00		0.96	1.00			
Satd. Flow (perm)	1770	5085	1583	3433	5085	1583		3383	1583			
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	118	2400	155	115	2552	37	93	8	162	0	0	0
RTOR Reduction (vph)	0	0	14	0	0	8	0	0	86	0	0	0
Lane Group Flow (vph)	118	2400	141	115	2552	29	0	101	76	0	0	0
Turn Type	Prot		Perm	Prot		Perm	Prot		Perm			
Protected Phases	7	4		3	8		5	2				
Permitted Phases			4			8			2			
Actuated Green, G (s)	8.0	88.9	88.9	10.5	91.4	91.4		37.0	37.0			
Effective Green, g (s)	8.0	88.9	88.9	10.5	91.4	91.4		37.0	37.0			
Actuated g/C Ratio	0.05	0.58	0.58	0.07	0.59	0.59		0.24	0.24			
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0			
Lane Grp Cap (vph)	92	2928	911	233	3010	937		811	379			
v/s Ratio Prot	c0.07	0.47		0.03	c0.50							
v/s Ratio Perm			0.09			0.02		0.03	c0.05			
v/c Ratio	1.28	0.82	0.15	0.49	0.85	0.03		0.12	0.20			
Uniform Delay, d1	73.2	26.3	15.2	69.4	25.8	13.1		46.0	46.9			
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00		1.00	1.00			
Incremental Delay, d2	187.4	1.9	0.1	1.6	2.4	0.0		0.1	1.2			
Delay (s)	260.6	28.2	15.3	71.0	28.2	13.1		46.1	48.1			
Level of Service	F	C	B	E	C	B		D	D			
Approach Delay (s)		37.7			29.8			47.3			0.0	
Approach LOS		D			C			D			A	
Intersection Summary												
HCM Average Control Delay			34.4			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.67									
Actuated Cycle Length (s)			154.4			Sum of lost time (s)			12.0			
Intersection Capacity Utilization			71.2%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

29: E. HALLANDALE BEACH BLVD & NE 8 AVE










Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	0	2367	196	87	2263	0	246	0	40	108	12	170
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Lane Util. Factor		0.91	1.00	1.00	0.91			1.00		0.95	0.95	1.00
Frt		1.00	0.85	1.00	1.00			0.98		1.00	1.00	0.85
Flt Protected		1.00	1.00	0.95	1.00			0.96		0.95	0.96	1.00
Satd. Flow (prot)		5085	1583	1770	5085			1752		1681	1701	1583
Flt Permitted		1.00	1.00	0.05	1.00			0.71		0.84	0.88	1.00
Satd. Flow (perm)		5085	1583	95	5085			1292		1483	1550	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	2573	213	95	2460	0	267	0	43	117	13	185
RTOR Reduction (vph)	0	0	57	0	0	0	0	4	0	0	0	28
Lane Group Flow (vph)	0	2573	156	95	2460	0	0	306	0	64	66	157
Turn Type		Perm		pm+pt			pm+pt			pm+pt		Perm
Protected Phases		4		3	8		5	2		1	6	
Permitted Phases			4	8			2			6		6
Actuated Green, G (s)		72.2	72.2	86.9	86.9			22.8		36.9	36.9	36.9
Effective Green, g (s)		72.2	72.2	86.9	86.9			22.8		36.9	36.9	36.9
Actuated g/C Ratio		0.53	0.53	0.64	0.64			0.17		0.27	0.27	0.27
Clearance Time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Vehicle Extension (s)		3.0	3.0	3.0	3.0			3.0		3.0	3.0	3.0
Lane Grp Cap (vph)		2704	842	168	3254			217		415	430	430
v/s Ratio Prot		c0.51		0.04	c0.48					0.01	0.01	
v/s Ratio Perm			0.10	0.32				c0.24		0.03	0.03	c0.10
v/c Ratio		0.95	0.19	0.57	0.76			1.41		0.15	0.15	0.36
Uniform Delay, d1		30.1	16.5	29.4	17.1			56.5		39.7	37.6	40.0
Progression Factor		1.00	1.00	1.00	1.00			1.00		1.00	1.00	1.00
Incremental Delay, d2		8.6	0.1	4.3	1.0			209.4		0.2	0.2	2.4
Delay (s)		38.8	16.6	33.7	18.1			265.9		39.9	37.7	42.3
Level of Service		D	B	C	B			F		D	D	D
Approach Delay (s)		37.1			18.7			265.9			40.9	
Approach LOS		D			B			F			D	
Intersection Summary												
HCM Average Control Delay			41.3			HCM Level of Service				D		
HCM Volume to Capacity ratio			1.02									
Actuated Cycle Length (s)			135.8			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			88.3%			ICU Level of Service			E			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis

33: DIANA DR & GOLDEN ISLES DR























Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Volume (veh/h)	69	205	118	56	44	220
Sign Control	Stop		Free			Free
Grade	0%		0%			0%
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	75	223	128	61	48	239
Pedestrians						
Lane Width (ft)						
Walking Speed (ft/s)						
Percent Blockage						
Right turn flare (veh)						
Median type			None			None
Median storage veh						
Upstream signal (ft)						345
pX, platoon unblocked						
vC, conflicting volume	493	159			189	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	493	159			189	
tC, single (s)	6.4	6.2			4.1	
tC, 2 stage (s)						
tF (s)	3.5	3.3			2.2	
p0 queue free %	85	75			97	
cM capacity (veh/h)	516	887			1385	
Direction, Lane #	WB 1	NB 1	SB 1			
Volume Total	298	189	287			
Volume Left	75	0	48			
Volume Right	223	61	0			
cSH	751	1700	1385			
Volume to Capacity	0.40	0.11	0.03			
Queue Length 95th (ft)	48	0	3			
Control Delay (s)	12.9	0.0	1.5			
Lane LOS	B		A			
Approach Delay (s)	12.9	0.0	1.5			
Approach LOS	B					
Intersection Summary						
Average Delay			5.5			
Intersection Capacity Utilization			50.1%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

34: E. HALLANDALE BEACH BLVD & U.S. 1

Beachwalk Traffic Study
Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	209	1219	570	762	1624	368	847	1473	771	562	1082	121
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Lane Util. Factor	1.00	0.91		0.97	0.91		0.97	0.91	1.00	0.97	0.91	
Frt	1.00	0.95		1.00	0.97		1.00	1.00	0.85	1.00	0.98	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1770	4842		3433	4944		3433	5085	1583	3433	5008	
Flt Permitted	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (perm)	1770	4842		3433	4944		3433	5085	1583	3433	5008	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	227	1325	620	828	1765	400	921	1601	838	611	1176	132
RTOR Reduction (vph)	0	53	0	0	23	0	0	0	207	0	9	0
Lane Group Flow (vph)	227	1892	0	828	2142	0	921	1601	631	611	1299	0
Turn Type	Prot			Prot			Prot		Perm	Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2			
Actuated Green, G (s)	23.0	44.0		24.0	45.0		24.0	44.0	44.0	24.0	42.0	
Effective Green, g (s)	23.0	44.0		24.0	45.0		24.0	44.0	44.0	24.0	42.0	
Actuated g/C Ratio	0.14	0.28		0.15	0.28		0.15	0.28	0.28	0.15	0.26	
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	254	1332		515	1391		515	1398	435	515	1315	
v/s Ratio Prot	0.13	0.39		c0.24	c0.43		c0.27	0.31		0.18	0.26	
v/s Ratio Perm									c0.40			
v/c Ratio	0.89	1.42		1.61	1.54		1.79	1.15	1.45	1.19	0.99	
Uniform Delay, d1	67.3	58.0		68.0	57.5		68.0	58.0	58.0	68.0	58.7	
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00	1.00	1.00	
Incremental Delay, d2	30.1	193.7		282.4	246.6		362.5	74.3	215.0	102.2	22.1	
Delay (s)	97.4	251.7		350.4	304.1		430.5	132.3	273.0	170.2	80.9	
Level of Service	F	F		F	F		F	F	F	F	F	
Approach Delay (s)		235.6			316.9			249.1			109.3	
Approach LOS		F			F			F			F	
Intersection Summary												
HCM Average Control Delay			240.0			HCM Level of Service			F			
HCM Volume to Capacity ratio			1.51									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			127.5%			ICU Level of Service			H			
Analysis Period (min)			15									
c Critical Lane Group												

Intersection Capacity Utilization

Beachwalk Traffic Study

8: E. HALLANDALE BEACH BLVD & EB E. Hallandale Beach Blvd Future (2015) Total Traffic - PM Peak



Movement	EBT	EBR	WBL	WBT	NBL	NBR	NBR2	NWL	NWR
Lane Configurations	↑↑↑↵		↵	↑↑↑			↵		
Volume (vph)	1942	93	107	1744	0	0	83	0	0
Pedestrians									
Ped Button									
Pedestrian Timing (s)									
Free Right		No				No	No		No
Ideal Flow	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Green (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Refr Cycle Length (s)	120								
Volume Combined (vph)	2035	0	107	1744	0	0	83	0	0
Lane Utilization Factor	0.91	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00
Turning Factor (vph)	0.99	0.85	0.95	1.00	0.95	0.85	0.85	0.95	0.85
Saturated Flow (vph)	5140	0	1805	5176	0	0	1615	0	0
Ped Intf Time (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Frequency (%)	0.00			0.00	0.00			0.00	
Protected Option Allowed	Yes			Yes	No			No	
Reference Time (s)	47.5	0.0	7.1	40.4		0.0	6.2		0.0
Adj Reference Time (s)	51.5	0.0	11.1	44.4		0.0	10.2		0.0
Permitted Option									
Adj Saturation A (vph)	1713		120	1725	0			0	
Reference Time A (s)	47.5		106.7	40.4	0.0			0.0	
Adj Saturation B (vph)	NA		NA	NA	NA			NA	
Reference Time B (s)	NA		NA	NA	NA			NA	
Reference Time (s)	47.5			106.7					
Adj Reference Time (s)	51.5			110.7					
Split Option									
Ref Time Combined (s)	47.5		7.1	40.4	0.0			0.0	
Ref Time Seperate (s)	45.3		7.1	40.4	0.0			0.0	
Reference Time (s)	47.5		40.4	40.4	0.0			0.0	
Adj Reference Time (s)	51.5		44.4	44.4	0.0			0.0	
Summary		EB WB		NB		NW		Combined	
Protected Option (s)		62.6		NA		NA			
Permitted Option (s)		110.7		Err		Err			
Split Option (s)		95.9		0.0		0.0			
Minimum (s)		62.6		0.0		0.0		62.6	
Right Turns		NBR2							
Adj Reference Time (s)		10.2							
Cross Thru Ref Time (s)		0.0							
Oncoming Left Ref Time (s)		51.5							
Combined (s)		61.7							

Intersection Summary

Intersection Capacity Utilization 52.2% ICU Level of Service A
Reference Times and Phasing Options do not represent an optimized timing plan.




















**Synchro Output Sheets – Future (2015)
Optimized Future Background Traffic plus
project traffic – AM Peak**



HCM Signalized Intersection Capacity Analysis

3: E. HALLANDALE BEACH BLVD & GOLDEN ISLES DR


Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	14	1351	63	44	1671	37	263	18	123	14	5	2
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Lane Util. Factor		0.91		1.00	0.91		0.95	0.95	1.00		0.95	
Frt		0.99		1.00	1.00		1.00	1.00	0.85		0.99	
Flt Protected		1.00		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (prot)		5049		1770	5069		1681	1696	1583		3376	
Flt Permitted		0.89		0.95	1.00		0.95	0.96	1.00		0.97	
Satd. Flow (perm)		4489		1770	5069		1681	1696	1583		3376	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	15	1468	68	48	1816	40	286	20	134	15	5	2
RTOR Reduction (vph)	0	3	0	0	1	0	0	0	104	0	2	0
Lane Group Flow (vph)	0	1548	0	48	1855	0	152	154	30	0	20	0
Turn Type	Perm			Prot			Split			Perm		
Protected Phases		4		3	8		2	2		6	6	
Permitted Phases	4								2			
Actuated Green, G (s)		62.9		7.4	76.3		31.4	31.4	31.4		16.2	
Effective Green, g (s)		62.9		7.4	76.3		31.4	31.4	31.4		16.2	
Actuated g/C Ratio		0.44		0.05	0.54		0.22	0.22	0.22		0.11	
Clearance Time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Vehicle Extension (s)		3.0		3.0	3.0		3.0	3.0	3.0		3.0	
Lane Grp Cap (vph)		1990		92	2726		372	375	350		385	
v/s Ratio Prot				0.03	c0.37		0.09	c0.09			c0.01	
v/s Ratio Perm		c0.34							0.02			
v/c Ratio		0.78		0.52	0.68		0.41	0.41	0.08		0.05	
Uniform Delay, d1		33.6		65.5	23.9		47.3	47.3	43.8		56.0	
Progression Factor		1.00		1.00	1.00		1.00	1.00	1.00		1.00	
Incremental Delay, d2		2.0		5.3	0.7		3.3	3.3	0.5		0.3	
Delay (s)		35.5		70.8	24.6		50.6	50.6	44.3		56.3	
Level of Service		D		E	C		D	D	D		E	
Approach Delay (s)		35.5			25.8			48.7			56.3	
Approach LOS		D			C			D			E	
Intersection Summary												
HCM Average Control Delay			32.4			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.59									
Actuated Cycle Length (s)			141.9			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			61.7%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

6: E. HALLANDALE BEACH BLVD & LAYNE BLVD

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↰	↰↰↰		↰	↰↰↰		↰	↰	↰		↰	↰
Volume (vph)	80	1333	105	29	1911	84	104	15	53	22	5	76
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Lane Util. Factor	1.00	0.91		1.00	0.91		0.95	0.95	1.00		1.00	1.00
Frt	1.00	0.99		1.00	0.99		1.00	1.00	0.85		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	0.96	1.00		0.96	1.00
Satd. Flow (prot)	1770	5030		1770	5053		1681	1705	1583		1789	1583
Flt Permitted	0.95	1.00		0.95	1.00		0.95	0.73	1.00		0.76	1.00
Satd. Flow (perm)	1770	5030		1770	5053		1681	1293	1583		1417	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	87	1449	114	32	2077	91	113	16	58	24	5	83
RTOR Reduction (vph)	0	6	0	0	3	0	0	0	44	0	0	71
Lane Group Flow (vph)	87	1557	0	32	2165	0	64	65	14	0	29	12
Turn Type	Prot			Prot			Prot		Perm	pm+pt		Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2	6		6
Actuated Green, G (s)	12.5	88.9		5.3	81.7		8.8	37.3	37.3		22.5	22.5
Effective Green, g (s)	12.5	88.9		5.3	81.7		8.8	37.3	37.3		22.5	22.5
Actuated g/C Ratio	0.08	0.59		0.04	0.55		0.06	0.25	0.25		0.15	0.15
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0		3.0	3.0
Lane Grp Cap (vph)	148	2991		63	2761		99	347	395		213	238
v/s Ratio Prot	c0.05	c0.31		0.02	c0.43		c0.04	0.01				
v/s Ratio Perm								c0.04	0.01		0.02	0.01
v/c Ratio	0.59	0.52		0.51	0.78		0.65	0.19	0.04		0.14	0.05
Uniform Delay, d1	66.0	17.8		70.8	26.9		68.8	44.2	42.5		55.1	54.4
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00		1.00	1.00
Incremental Delay, d2	5.9	0.2		6.3	1.5		13.6	0.3	0.2		0.3	0.4
Delay (s)	71.9	18.0		77.1	28.4		82.4	44.4	42.7		55.4	54.8
Level of Service	E	B		E	C		F	D	D		E	D
Approach Delay (s)		20.8			29.1			56.9			54.9	
Approach LOS		C			C			E			D	

Intersection Summary




HCM Average Control Delay	27.8	HCM Level of Service	C
HCM Volume to Capacity ratio	0.65		
Actuated Cycle Length (s)	149.5	Sum of lost time (s)	24.0
Intersection Capacity Utilization	68.2%	ICU Level of Service	C
Analysis Period (min)	15		
c Critical Lane Group			

HCM Unsignalized Intersection Capacity Analysis

9: DIANA DR & SE 26 Avenue

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak






















Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Sign Control		Stop	Stop		Stop	
Volume (vph)	69	1	2	0	1	142
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	75	1	2	0	1	154
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total (vph)	76	2	155			
Volume Left (vph)	75	0	1			
Volume Right (vph)	0	0	154			
Hadj (s)	0.23	0.03	-0.56			
Departure Headway (s)	4.4	4.3	3.5			
Degree Utilization, x	0.09	0.00	0.15			
Capacity (veh/h)	783	799	992			
Control Delay (s)	7.9	7.3	7.2			
Approach Delay (s)	7.9	7.3	7.2			
Approach LOS	A	A	A			
Intersection Summary						
Delay			7.4			
HCM Level of Service			A			
Intersection Capacity Utilization			26.1%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

10: E. HALLANDALE BEACH BLVD & DIPLOMAT PKWY

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	116	1260	17	15	1609	50	11	1	5	51	23	149
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91		1.00	0.91			1.00		1.00	1.00	
Frt	1.00	1.00		1.00	1.00			0.96		1.00	0.87	
Flt Protected	0.95	1.00		0.95	1.00			0.97		0.95	1.00	
Satd. Flow (prot)	1770	5075		1770	5062			1735		1770	1621	
Flt Permitted	0.95	1.00		0.95	1.00			0.82		0.75	1.00	
Satd. Flow (perm)	1770	5075		1770	5062			1468		1389	1621	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	126	1370	18	16	1749	54	12	1	5	55	25	162
RTOR Reduction (vph)	0	1	0	0	2	0	0	4	0	0	122	0
Lane Group Flow (vph)	126	1387	0	16	1801	0	0	14	0	55	65	0
Turn Type	Prot			Prot			Perm			Perm		
Protected Phases	7	4		3	8			2			6	
Permitted Phases							2			6		
Actuated Green, G (s)	15.0	80.5		2.5	68.0			33.6		33.6	33.6	
Effective Green, g (s)	15.0	80.5		2.5	68.0			33.6		33.6	33.6	
Actuated g/C Ratio	0.11	0.60		0.02	0.51			0.25		0.25	0.25	
Clearance Time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	197	3035		33	2557			366		347	405	
v/s Ratio Prot	c0.07	0.27		0.01	c0.36						c0.04	
v/s Ratio Perm								0.01		0.04		
v/c Ratio	0.64	0.46		0.48	0.70			0.04		0.16	0.16	
Uniform Delay, d1	57.2	15.0		65.4	25.6			38.3		39.5	39.5	
Progression Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Incremental Delay, d2	6.7	0.1		10.8	0.9			0.2		1.0	0.9	
Delay (s)	63.9	15.1		76.2	26.5			38.5		40.4	40.3	
Level of Service	E	B		E	C			D		D	D	
Approach Delay (s)		19.1			26.9			38.5			40.4	
Approach LOS		B			C			D			D	
Intersection Summary												
HCM Average Control Delay			24.6			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.54									
Actuated Cycle Length (s)			134.6			Sum of lost time (s)			18.0			
Intersection Capacity Utilization			64.1%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

17: E. HALLANDALE BEACH BLVD & 3 Islands Drive

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak


























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	←←	↑↑↑	↑↑↑	↑	↑	↑
Volume (vph)	227	1010	1265	158	372	368
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.97	0.91	0.91	1.00	1.00	1.00
Frt	1.00	1.00	1.00	0.85	1.00	0.85
Flt Protected	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (prot)	3433	5085	5085	1583	1770	1583
Flt Permitted	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (perm)	3433	5085	5085	1583	1770	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	247	1098	1375	172	404	400
RTOR Reduction (vph)	0	0	0	113	0	196
Lane Group Flow (vph)	247	1098	1375	59	404	204
Turn Type	Prot			Perm		custom
Protected Phases	7	4	8			
Permitted Phases				8	6	6
Actuated Green, G (s)	15.1	67.3	46.2	46.2	56.3	56.3
Effective Green, g (s)	15.1	67.3	46.2	46.2	56.3	56.3
Actuated g/C Ratio	0.11	0.50	0.34	0.34	0.42	0.42
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	382	2524	1733	539	735	657
v/s Ratio Prot	c0.07	0.22	c0.27			
v/s Ratio Perm				0.04	c0.23	0.13
v/c Ratio	0.65	0.44	0.79	0.11	0.55	0.31
Uniform Delay, d1	57.7	21.9	40.4	30.6	30.0	26.6
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	3.7	0.1	2.6	0.1	2.9	1.2
Delay (s)	61.4	22.1	43.0	30.7	33.0	27.8
Level of Service	E	C	D	C	C	C
Approach Delay (s)		29.3	41.6		30.4	
Approach LOS		C	D		C	
Intersection Summary						
HCM Average Control Delay			34.7		HCM Level of Service	C
HCM Volume to Capacity ratio			0.66			
Actuated Cycle Length (s)			135.6		Sum of lost time (s)	18.0
Intersection Capacity Utilization			66.5%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

21: WB E. Hallandale Beach Blvd & S. OCEAN DR



























Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR2	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR2
Lane Configurations												
Volume (vph)	562	37	892	6	179	6	205	474	6	6	362	355
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.95	0.95	1.00		1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00
Frt	1.00	1.00	0.85		1.00	0.85	1.00	1.00	0.85	1.00	1.00	0.85
Flt Protected	0.95	0.96	1.00		1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (prot)	1681	1695	1583		1860	1583	1770	3539	1583	1770	3539	1583
Flt Permitted	0.95	0.96	1.00		1.00	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	1681	1695	1583		1860	1583	1770	3539	1583	1770	3539	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	611	40	970	7	195	7	223	515	7	7	393	386
RTOR Reduction (vph)	0	0	737	0	0	0	0	0	4	0	0	0
Lane Group Flow (vph)	324	327	233	0	202	7	223	515	3	7	393	386
Turn Type	Split		Perm	Split		Perm	Prot		Perm	Prot		Perm
Protected Phases	3	3		7	7		5	2		1	6	
Permitted Phases			3			7			2			6
Actuated Green, G (s)	27.0	27.0	27.0		12.0	12.0	15.0	48.6	48.6	0.8	34.4	34.4
Effective Green, g (s)	27.0	27.0	27.0		12.0	12.0	15.0	48.6	48.6	0.8	34.4	34.4
Actuated g/C Ratio	0.24	0.24	0.24		0.11	0.11	0.13	0.43	0.43	0.01	0.31	0.31
Clearance Time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0		3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	404	407	380		199	169	236	1530	684	13	1083	484
v/s Ratio Prot	0.19	c0.19			c0.11		c0.13	0.15		0.00	0.11	
v/s Ratio Perm			0.15			0.00			0.00			c0.24
v/c Ratio	0.80	0.80	0.61		1.02	0.04	0.94	0.34	0.00	0.54	0.36	0.80
Uniform Delay, d1	40.2	40.2	38.0		50.2	45.0	48.3	21.2	18.1	55.6	30.4	35.8
Progression Factor	1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	15.4	15.4	7.2		67.8	0.1	43.2	0.6	0.0	36.8	0.2	8.9
Delay (s)	55.6	55.6	45.3		118.0	45.1	91.4	21.8	18.2	92.4	30.7	44.7
Level of Service	E	E	D		F	D	F	C	B	F	C	D
Approach Delay (s)		49.4			115.5			42.6			38.1	
Approach LOS		D			F			D			D	
Intersection Summary												
HCM Average Control Delay			49.4				HCM Level of Service			D		
HCM Volume to Capacity ratio			0.85									
Actuated Cycle Length (s)			112.4				Sum of lost time (s)			24.0		
Intersection Capacity Utilization			90.0%				ICU Level of Service			E		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

22: E. HALLANDALE BEACH BLVD & NE 14 AVE





















Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  		 					
Volume (vph)	102	1584	228	20	1865	54	249	73	28	135	84	196
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91	1.00	1.00	0.91		0.97	1.00		1.00	1.00	
Frt	1.00	1.00	0.85	1.00	1.00		1.00	0.96		1.00	0.89	
Flt Protected	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1770	5085	1583	1770	5064		3433	1786		1770	1667	
Flt Permitted	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (perm)	1770	5085	1583	1770	5064		3433	1786		1770	1667	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	111	1722	248	22	2027	59	271	79	30	147	91	213
RTOR Reduction (vph)	0	0	106	0	2	0	0	8	0	0	52	0
Lane Group Flow (vph)	111	1722	142	22	2084	0	271	101	0	147	252	0
Turn Type	Prot		Perm	Prot			Prot			Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			4									
Actuated Green, G (s)	13.1	84.0	84.0	3.6	74.5		15.4	32.6		17.9	35.1	
Effective Green, g (s)	13.1	84.0	84.0	3.6	74.5		15.4	32.6		17.9	35.1	
Actuated g/C Ratio	0.08	0.52	0.52	0.02	0.46		0.10	0.20		0.11	0.22	
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	143	2635	820	39	2327		326	359		195	361	
v/s Ratio Prot	c0.06	0.34		0.01	c0.41		0.08	0.06		c0.08	c0.15	
v/s Ratio Perm			0.09									
v/c Ratio	0.78	0.65	0.17	0.56	0.90		0.83	0.28		0.75	0.70	
Uniform Delay, d1	73.1	28.4	20.7	78.5	40.2		72.1	54.8		70.0	58.6	
Progression Factor	1.00	1.00	1.00	1.00	1.00		1.00	1.00		1.00	1.00	
Incremental Delay, d2	22.7	0.6	0.1	17.3	5.0		16.3	2.0		15.2	10.6	
Delay (s)	95.8	29.0	20.8	95.8	45.2		88.4	56.8		85.1	69.2	
Level of Service	F	C	C	F	D		F	E		F	E	
Approach Delay (s)		31.6			45.7			79.3			74.4	
Approach LOS		C			D			E			E	
Intersection Summary												
HCM Average Control Delay			45.0			HCM Level of Service				D		
HCM Volume to Capacity ratio			0.80									
Actuated Cycle Length (s)			162.1			Sum of lost time (s)				18.0		
Intersection Capacity Utilization			86.5%			ICU Level of Service				E		
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

26: E. HALLANDALE BEACH BLVD & NE 10 AVE













Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	119	1815	135	281	2051	35	67	2	112	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Lane Util. Factor	1.00	0.91	1.00	0.97	0.91	1.00		0.95	1.00			
Frt	1.00	1.00	0.85	1.00	1.00	0.85		1.00	0.85			
Flt Protected	0.95	1.00	1.00	0.95	1.00	1.00		0.95	1.00			
Satd. Flow (prot)	1770	5085	1583	3433	5085	1583		3375	1583			
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00		0.95	1.00			
Satd. Flow (perm)	1770	5085	1583	3433	5085	1583		3375	1583			
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	129	1973	147	305	2229	38	73	2	122	0	0	0
RTOR Reduction (vph)	0	0	18	0	0	9	0	0	103	0	0	0
Lane Group Flow (vph)	129	1973	129	305	2229	29	0	75	19	0	0	0
Turn Type	Prot		Perm	Prot		Perm	Prot		Perm			
Protected Phases	7	4		3	8		5	2				
Permitted Phases			4			8			2			
Actuated Green, G (s)	15.8	83.0	83.0	18.1	85.3	85.3		21.4	21.4			
Effective Green, g (s)	15.8	83.0	83.0	18.1	85.3	85.3		21.4	21.4			
Actuated g/C Ratio	0.11	0.59	0.59	0.13	0.61	0.61		0.15	0.15			
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0			
Lane Grp Cap (vph)	199	3004	935	442	3087	961		514	241			
v/s Ratio Prot	0.07	0.39		c0.09	c0.44							
v/s Ratio Perm			0.08			0.02		0.02	0.01			
v/c Ratio	0.65	0.66	0.14	0.69	0.72	0.03		0.15	0.08			
Uniform Delay, d1	59.7	19.2	12.8	58.5	19.3	11.0		51.6	51.1			
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00		1.00	1.00			
Incremental Delay, d2	7.1	0.5	0.1	4.6	0.9	0.0		0.1	0.6			
Delay (s)	66.8	19.8	12.9	63.1	20.2	11.1		51.8	51.7			
Level of Service	E	B	B	E	C	B		D	D			
Approach Delay (s)		22.0			25.1			51.7			0.0	
Approach LOS		C			C			D			A	
Intersection Summary												
HCM Average Control Delay			24.8			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.60									
Actuated Cycle Length (s)			140.5			Sum of lost time (s)			12.0			
Intersection Capacity Utilization			64.9%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

29: E. HALLANDALE BEACH BLVD & NE 8 AVE










Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑↑↑	↑	↑	↑↑↑			↑↓		↑	↑	↑
Volume (vph)	0	2105	241	3	2153	0	192	0	96	101	8	189
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Lane Util. Factor		0.91	1.00	1.00	0.91			1.00		0.95	0.95	1.00
Frt		1.00	0.85	1.00	1.00			0.96		1.00	1.00	0.85
Flt Protected		1.00	1.00	0.95	1.00			0.97		0.95	0.96	1.00
Satd. Flow (prot)		5085	1583	1770	5085			1722		1681	1697	1583
Flt Permitted		1.00	1.00	0.04	1.00			0.76		0.62	0.67	1.00
Satd. Flow (perm)		5085	1583	79	5085			1353		1095	1191	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	2288	262	3	2340	0	209	0	104	110	9	205
RTOR Reduction (vph)	0	0	88	0	0	0	0	11	0	0	0	13
Lane Group Flow (vph)	0	2288	174	3	2340	0	0	302	0	59	60	192
Turn Type		Perm		pm+pt			pm+pt			pm+pt		Perm
Protected Phases		4		3	8		5	2		1	6	
Permitted Phases			4	8			2			6		6
Actuated Green, G (s)		87.8	87.8	94.6	94.6			46.2		55.3	55.3	55.3
Effective Green, g (s)		87.8	87.8	94.6	94.6			46.2		55.3	55.3	55.3
Actuated g/C Ratio		0.54	0.54	0.58	0.58			0.29		0.34	0.34	0.34
Clearance Time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Vehicle Extension (s)		3.0	3.0	3.0	3.0			3.0		3.0	3.0	3.0
Lane Grp Cap (vph)		2758	858	55	2971			386		385	416	541
v/s Ratio Prot		c0.45		0.00	c0.46					0.00	0.00	
v/s Ratio Perm			0.11	0.03				c0.22		0.05	0.05	c0.12
v/c Ratio		0.83	0.20	0.05	0.79			0.78		0.15	0.14	0.35
Uniform Delay, d1		30.8	19.0	27.0	25.9			53.2		42.0	36.9	39.9
Progression Factor		1.00	1.00	1.00	1.00			1.00		1.00	1.00	1.00
Incremental Delay, d2		2.2	0.1	0.4	1.4			9.9		0.2	0.2	1.8
Delay (s)		33.0	19.2	27.5	27.4			63.1		42.2	37.1	41.7
Level of Service		C	B	C	C			E		D	D	D
Approach Delay (s)		31.6			27.4			63.1			41.0	
Approach LOS		C			C			E			D	
Intersection Summary												
HCM Average Control Delay			32.1			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.83									
Actuated Cycle Length (s)			161.9			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			84.8%			ICU Level of Service			E			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis

33: DIANA DR & GOLDEN ISLES DR

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - AM Peak























						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Volume (veh/h)	50	160	243	69	12	70
Sign Control	Stop		Free			Free
Grade	0%		0%			0%
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	54	174	264	75	13	76
Pedestrians						
Lane Width (ft)						
Walking Speed (ft/s)						
Percent Blockage						
Right turn flare (veh)						
Median type			None			None
Median storage (veh)						
Upstream signal (ft)						345
pX, platoon unblocked						
vC, conflicting volume	404	302			339	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	404	302			339	
tC, single (s)	6.4	6.2			4.1	
tC, 2 stage (s)						
tF (s)	3.5	3.3			2.2	
p0 queue free %	91	76			99	
cM capacity (veh/h)	596	738			1220	
Direction, Lane #	WB 1	NB 1	SB 1			
Volume Total	228	339	89			
Volume Left	54	0	13			
Volume Right	174	75	0			
cSH	698	1700	1220			
Volume to Capacity	0.33	0.20	0.01			
Queue Length 95th (ft)	36	0	1			
Control Delay (s)	12.6	0.0	1.2			
Lane LOS	B		A			
Approach Delay (s)	12.6	0.0	1.2			
Approach LOS	B					
Intersection Summary						
Average Delay		4.6				
Intersection Capacity Utilization		36.3%		ICU Level of Service		A
Analysis Period (min)		15				

HCM Signalized Intersection Capacity Analysis

34: E. HALLANDALE BEACH BLVD & U.S. 1

Beachwalk Traffic Study

Optimized Future (2015) Total Traffic - AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	116	1308	655	698	1424	306	483	696	462	444	1237	88
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Lane Util. Factor	1.00	0.91		0.97	0.91		0.97	0.91	1.00	0.97	0.91	
Frt	1.00	0.95		1.00	0.97		1.00	1.00	0.85	1.00	0.99	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1770	4831		3433	4950		3433	5085	1583	3433	5034	
Flt Permitted	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (perm)	1770	4831		3433	4950		3433	5085	1583	3433	5034	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	126	1422	712	759	1548	333	525	757	502	483	1345	96
RTOR Reduction (vph)	0	57	0	0	21	0	0	0	191	0	5	0
Lane Group Flow (vph)	126	2077	0	759	1860	0	525	757	311	483	1436	0
Turn Type	Prot			Prot			Prot		Perm	Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2			
Actuated Green, G (s)	12.0	51.0		26.0	65.0		19.0	36.0	36.0	23.0	38.0	
Effective Green, g (s)	12.0	51.0		26.0	65.0		19.0	36.0	36.0	23.0	38.0	
Actuated g/C Ratio	0.08	0.32		0.16	0.41		0.12	0.22	0.22	0.14	0.24	
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	133	1540		558	2011		408	1144	356	493	1196	
v/s Ratio Prot	0.07	c0.43		c0.22	0.38		c0.15	0.15		0.14	c0.29	
v/s Ratio Perm									0.20			
v/c Ratio	0.95	1.35		1.36	0.93		1.29	0.66	0.87	0.98	1.20	
Uniform Delay, d1	73.7	54.5		67.0	45.2		70.5	56.5	59.8	68.3	61.0	
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00	1.00	1.00	
Incremental Delay, d2	61.3	161.4		173.5	7.8		146.5	3.0	24.6	34.8	98.4	
Delay (s)	135.0	215.9		240.5	53.0		217.0	59.5	84.4	103.1	159.4	
Level of Service	F	F		F	D		F	E	F	F	F	
Approach Delay (s)		211.4			106.9			112.8			145.3	
Approach LOS		F			F			F			F	
Intersection Summary												
HCM Average Control Delay			144.2			HCM Level of Service			F			
HCM Volume to Capacity ratio			1.30									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			26.0			
Intersection Capacity Utilization			121.1%			ICU Level of Service			H			
Analysis Period (min)			15									
c Critical Lane Group												

Intersection Capacity Utilization

Beachwalk Traffic Study

8: E. HALLANDALE BEACH BLVD & EB E. Hallandale Beach Blvd

Planned Future (2015) Total Traffic - AM Peak



Movement	EBT	EBR	WBL	WBT	NBL	NBR	NBR2	NWL	NWR
Lane Configurations	↑↑↑↱		↱	↑↑↑			↱		
Volume (vph)	1282	96	72	1448	0	0	83	0	0
Pedestrians									
Ped Button									
Pedestrian Timing (s)									
Free Right	No				No		No	No	
Ideal Flow	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Green (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Refr Cycle Length (s)	120								
Volume Combined (vph)	1378	0	72	1448	0	0	83	0	0
Lane Utilization Factor	0.91	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00
Turning Factor (vph)	0.99	0.85	0.95	1.00	0.95	0.85	0.85	0.95	0.85
Saturated Flow (vph)	5122	0	1805	5176	0	0	1615	0	0
Ped Intf Time (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Frequency (%)	0.00			0.00	0.00			0.00	
Protected Option Allowed	Yes			Yes	No			No	
Reference Time (s)	32.3	0.0	4.8	33.6	0.0		6.2	0.0	
Adj Reference Time (s)	36.3	0.0	8.8	37.6	0.0		10.2	0.0	
Permitted Option									
Adj Saturation A (vph)	1707	120		1725	0			0	
Reference Time A (s)	32.3	71.8		33.6	0.0			0.0	
Adj Saturation B (vph)	NA	NA		NA	NA			NA	
Reference Time B (s)	NA	NA		NA	NA			NA	
Reference Time (s)	32.3			71.8					
Adj Reference Time (s)	36.3			75.8					
Split Option									
Ref Time Combined (s)	32.3	4.8		33.6	0.0			0.0	
Ref Time Seperate (s)	30.0	4.8		33.6	0.0			0.0	
Reference Time (s)	32.3	33.6		33.6	0.0			0.0	
Adj Reference Time (s)	36.3	37.6		37.6	0.0			0.0	
Summary	EB WB		NB		NW		Combined		
Protected Option (s)	45.1		NA		NA				
Permitted Option (s)	75.8		Err		Err				
Split Option (s)	73.9		0.0		0.0				
Minimum (s)	45.1		0.0		0.0		45.1		
Right Turns	NBR2								
Adj Reference Time (s)	10.2								
Cross Thru Ref Time (s)	0.0								
Oncoming Left Ref Time (s)	36.3								
Combined (s)	46.5								

Intersection Summary

Intersection Capacity Utilization 38.7% ICU Level of Service
Reference Times and Phasing Options do not represent an optimized timing plan.

A
























**Synchro Output Sheets – Future (2015)
Optimized Future Background Traffic plus
project traffic – PM Peak**



HCM Signalized Intersection Capacity Analysis

3: E. HALLANDALE BEACH BLVD & GOLDEN ISLES DR






















Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	10	2123	146	119	1677	51	230	19	66	75	13	9
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Lane Util. Factor		0.91		1.00	0.91		0.95	0.95	1.00		0.95	
Frt		0.99		1.00	1.00		1.00	1.00	0.85		0.99	
Flt Protected		1.00		0.95	1.00		0.95	0.96	1.00		0.96	
Satd. Flow (prot)		5035		1770	5063		1681	1698	1583		3359	
Flt Permitted		0.92		0.95	1.00		0.95	0.96	1.00		0.96	
Satd. Flow (perm)		4616		1770	5063		1681	1698	1583		3359	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	11	2308	159	129	1823	55	250	21	72	82	14	10
RTOR Reduction (vph)	0	5	0	0	2	0	0	0	64	0	5	0
Lane Group Flow (vph)	0	2473	0	129	1876	0	135	136	8	0	102	0
Turn Type	Perm			Prot			Split			Perm	Split	
Protected Phases		4		3	8		2	2			6	6
Permitted Phases	4								2			
Actuated Green, G (s)		90.0		13.0	109.0		17.0	17.0	17.0		16.0	
Effective Green, g (s)		90.0		13.0	109.0		17.0	17.0	17.0		16.0	
Actuated g/C Ratio		0.56		0.08	0.68		0.11	0.11	0.11		0.10	
Clearance Time (s)		6.0		6.0	6.0		6.0	6.0	6.0		6.0	
Vehicle Extension (s)		3.0		3.0	3.0		3.0	3.0	3.0		3.0	
Lane Grp Cap (vph)		2597		144	3449		179	180	168		336	
v/s Ratio Prot				c0.07	0.37		c0.08	0.08			c0.03	
v/s Ratio Perm		c0.54							0.00			
v/c Ratio		0.95		0.90	0.54		0.75	0.76	0.05		0.30	
Uniform Delay, d1		33.0		72.8	12.9		69.5	69.5	64.2		66.8	
Progression Factor		1.00		1.00	1.00		1.00	1.00	1.00		1.00	
Incremental Delay, d2		9.0		45.1	0.2		25.1	25.2	0.5		2.3	
Delay (s)		42.0		118.0	13.1		94.6	94.6	64.7		69.1	
Level of Service		D		F	B		F	F	E		E	
Approach Delay (s)		42.0			19.8			88.3			69.1	
Approach LOS		D			B			F			E	
Intersection Summary												
HCM Average Control Delay			36.8			HCM Level of Service			D			
HCM Volume to Capacity ratio			0.85									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			106.5%			ICU Level of Service			G			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

6: E. HALLANDALE BEACH BLVD & LAYNE BLVD




Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	125	2050	54	25	1733	33	167	15	61	144	12	102
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Lane Util. Factor	1.00	0.91		1.00	0.91		0.95	0.95	1.00		1.00	1.00
Frt	1.00	1.00		1.00	1.00		1.00	1.00	0.85		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	0.96	1.00		0.96	1.00
Satd. Flow (prot)	1770	5066		1770	5071		1681	1698	1583		1781	1583
Flt Permitted	0.95	1.00		0.95	1.00		0.95	0.47	1.00		0.67	1.00
Satd. Flow (perm)	1770	5066		1770	5071		1681	839	1583		1244	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	136	2228	59	27	1884	36	182	16	66	157	13	111
RTOR Reduction (vph)	0	2	0	0	1	0	0	0	44	0	0	87
Lane Group Flow (vph)	136	2285	0	27	1919	0	98	100	22	0	170	24
Turn Type	Prot			Prot			Prot		Perm	pm+pt		Perm
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2	6		6
Actuated Green, G (s)	16.0	83.1		2.9	70.0		12.9	52.1	52.1		33.2	33.2
Effective Green, g (s)	16.0	83.1		2.9	70.0		12.9	52.1	52.1		33.2	33.2
Actuated g/C Ratio	0.10	0.53		0.02	0.45		0.08	0.33	0.33		0.21	0.21
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0		6.0	6.0
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0		3.0	3.0
Lane Grp Cap (vph)	181	2697		33	2274		139	351	528		265	337
v/s Ratio Prot	c0.08	c0.45		0.02	0.38		c0.06	0.02				
v/s Ratio Perm								0.07	0.01		c0.14	0.01
v/c Ratio	0.75	0.85		0.82	0.84		0.71	0.28	0.04		0.64	0.07
Uniform Delay, d1	68.1	31.1		76.3	38.2		69.7	38.3	35.1		56.0	49.1
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00		1.00	1.00
Incremental Delay, d2	16.0	2.7		84.2	3.1		15.0	0.4	0.1		5.2	0.4
Delay (s)	84.2	33.7		160.5	41.3		84.8	38.7	35.3		61.3	49.5
Level of Service	F	C		F	D		F	D	D		E	D
Approach Delay (s)		36.6			42.9			55.0			56.6	
Approach LOS		D			D			D			E	
Intersection Summary												
HCM Average Control Delay			41.2			HCM Level of Service				D		
HCM Volume to Capacity ratio			0.80									
Actuated Cycle Length (s)			156.1			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			74.4%			ICU Level of Service			D			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Unsignalized Intersection Capacity Analysis 9: DIANA DR & SE 26 Avenue

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak






















Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Sign Control		Stop	Stop		Stop	
Volume (vph)	45	6	1	2	5	161
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	49	7	1	2	5	175
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total (vph)	55	3	180			
Volume Left (vph)	49	0	5			
Volume Right (vph)	0	2	175			
Hadj (s)	0.21	-0.37	-0.54			
Departure Headway (s)	4.5	3.9	3.5			
Degree Utilization, x	0.07	0.00	0.18			
Capacity (veh/h)	775	868	1004			
Control Delay (s)	7.8	6.9	7.2			
Approach Delay (s)	7.8	6.9	7.2			
Approach LOS	A	A	A			
Intersection Summary						
Delay			7.4			
HCM Level of Service			A			
Intersection Capacity Utilization			26.4%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

10: E. HALLANDALE BEACH BLVD & DIPLOMAT PKWY

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	194	2145	2	4	1631	51	9	11	13	74	1	118
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91		1.00	0.91			1.00		1.00	1.00	
Frt	1.00	1.00		1.00	1.00			0.95		1.00	0.85	
Flt Protected	0.95	1.00		0.95	1.00			0.99		0.95	1.00	
Satd. Flow (prot)	1770	5085		1770	5062			1741		1770	1585	
Flt Permitted	0.95	1.00		0.95	1.00			0.92		0.73	1.00	
Satd. Flow (perm)	1770	5085		1770	5062			1617		1367	1585	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	211	2332	2	4	1773	55	10	12	14	80	1	128
RTOR Reduction (vph)	0	0	0	0	2	0	0	11	0	0	104	0
Lane Group Flow (vph)	211	2334	0	4	1826	0	0	25	0	80	25	0
Turn Type	Prot			Prot			Perm			Perm		
Protected Phases	7	4		3	8			2			6	
Permitted Phases							2			6		
Actuated Green, G (s)	21.5	91.3		0.6	70.4			25.6		25.6	25.6	
Effective Green, g (s)	21.5	91.3		0.6	70.4			25.6		25.6	25.6	
Actuated g/C Ratio	0.16	0.67		0.00	0.52			0.19		0.19	0.19	
Clearance Time (s)	6.0	6.0		6.0	6.0			6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0			3.0		3.0	3.0	
Lane Grp Cap (vph)	281	3426		8	2630			305		258	299	
v/s Ratio Prot	c0.12	c0.46		0.00	0.36						0.02	
v/s Ratio Perm								0.02		c0.06		
v/c Ratio	0.75	0.68		0.50	0.69			0.08		0.31	0.08	
Uniform Delay, d1	54.4	13.3		67.3	24.5			45.3		47.3	45.3	
Progression Factor	1.00	1.00		1.00	1.00			1.00		1.00	1.00	
Incremental Delay, d2	10.7	0.6		41.8	0.8			0.5		3.1	0.6	
Delay (s)	65.2	13.9		109.1	25.3			45.8		50.4	45.8	
Level of Service	E	B		F	C			D		D	D	
Approach Delay (s)		18.1			25.5			45.8			47.6	
Approach LOS		B			C			D			D	
Intersection Summary												
HCM Average Control Delay			22.6			HCM Level of Service				C		
HCM Volume to Capacity ratio			0.60									
Actuated Cycle Length (s)			135.5			Sum of lost time (s)			12.0			
Intersection Capacity Utilization			70.6%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

17: E. HALLANDALE BEACH BLVD & 3 ISLANDS BLVD

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak


























Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	↰↱	↑↑↑	↑↑↑	↰	↰	↰
Volume (vph)	583	1600	1457	319	349	294
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.97	0.91	0.91	1.00	1.00	1.00
Frt	1.00	1.00	1.00	0.85	1.00	0.85
Flt Protected	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (prot)	3433	5085	5085	1583	1770	1583
Flt Permitted	0.95	1.00	1.00	1.00	0.95	1.00
Satd. Flow (perm)	3433	5085	5085	1583	1770	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	634	1739	1584	347	379	320
RTOR Reduction (vph)	0	0	0	221	0	201
Lane Group Flow (vph)	634	1739	1584	126	379	119
Turn Type	Prot			Perm		custom
Protected Phases	7	4	8			
Permitted Phases				8	6	6
Actuated Green, G (s)	31.3	90.3	53.0	53.0	43.1	43.1
Effective Green, g (s)	31.3	90.3	53.0	53.0	43.1	43.1
Actuated g/C Ratio	0.22	0.62	0.36	0.36	0.30	0.30
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	739	3158	1854	577	525	469
v/s Ratio Prot	c0.18	0.34	c0.31			
v/s Ratio Perm				0.08	c0.21	0.08
v/c Ratio	0.86	0.55	0.85	0.22	0.72	0.25
Uniform Delay, d1	54.9	15.9	42.6	31.9	45.8	38.9
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	9.7	0.2	4.1	0.2	8.3	1.3
Delay (s)	64.6	16.1	46.7	32.1	54.1	40.2
Level of Service	E	B	D	C	D	D
Approach Delay (s)		29.0	44.1		47.8	
Approach LOS		C	D		D	
Intersection Summary						
HCM Average Control Delay			37.5		HCM Level of Service	D
HCM Volume to Capacity ratio			0.81			
Actuated Cycle Length (s)			145.4		Sum of lost time (s)	18.0
Intersection Capacity Utilization			79.1%		ICU Level of Service	D
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

21: WB E. Hallandale Beach Blvd & S. OCEAN DR



























Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR2	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR2
Lane Configurations												
Volume (vph)	761	87	1089	12	92	31	228	712	6	17	768	755
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Lane Util. Factor	0.95	0.95	1.00		1.00	1.00	1.00	0.95	1.00	1.00	0.95	1.00
Frt	1.00	1.00	0.85		1.00	0.85	1.00	1.00	0.85	1.00	1.00	0.85
Flt Protected	0.95	0.96	1.00		0.99	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (prot)	1681	1702	1583		1852	1583	1770	3539	1583	1770	3539	1583
Flt Permitted	0.95	0.96	1.00		0.99	1.00	0.95	1.00	1.00	0.95	1.00	1.00
Satd. Flow (perm)	1681	1702	1583		1852	1583	1770	3539	1583	1770	3539	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	827	95	1184	13	100	34	248	774	7	18	835	821
RTOR Reduction (vph)	0	0	856	0	0	0	0	0	3	0	0	0
Lane Group Flow (vph)	455	467	328	0	113	34	248	774	4	18	835	821
Turn Type	Split		Perm	Split		Perm	Prot		Perm	Prot		Perm
Protected Phases	3	3		7	7		5	2		1	6	
Permitted Phases			3			7			2			6
Actuated Green, G (s)	22.0	22.0	22.0		5.0	5.0	12.0	60.6	60.6	2.0	50.6	50.6
Effective Green, g (s)	22.0	22.0	22.0		5.0	5.0	12.0	60.6	60.6	2.0	50.6	50.6
Actuated g/C Ratio	0.19	0.19	0.19		0.04	0.04	0.11	0.53	0.53	0.02	0.45	0.45
Clearance Time (s)	6.0	6.0	6.0		6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0
Vehicle Extension (s)	3.0	3.0	3.0		3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	326	330	307		82	70	187	1888	844	31	1576	705
v/s Ratio Prot	0.27	c0.27			c0.06		c0.14	0.22		0.01	0.24	
v/s Ratio Perm			0.21			0.02			0.00			c0.52
v/c Ratio	1.40	1.42	1.07		1.38	0.49	1.33	0.41	0.00	0.58	0.53	1.16
Uniform Delay, d1	45.8	45.8	45.8		54.3	53.0	50.8	15.8	12.4	55.4	22.9	31.5
Progression Factor	1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Incremental Delay, d2	195.8	203.9	70.3		229.4	5.2	178.9	0.7	0.0	24.7	0.3	89.1
Delay (s)	241.6	249.7	116.1		283.7	58.3	229.7	16.5	12.4	80.1	23.2	120.6
Level of Service	F	F	F		F	E	F	B	B	F	C	F
Approach Delay (s)		172.8			231.6			67.8			71.6	
Approach LOS		F			F			E			E	
Intersection Summary												
HCM Average Control Delay			118.6				HCM Level of Service			F		
HCM Volume to Capacity ratio			1.26									
Actuated Cycle Length (s)			113.6				Sum of lost time (s)		24.0			
Intersection Capacity Utilization			109.2%				ICU Level of Service		H			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

22: E. HALLANDALE BEACH BLVD & NE 14 AVE





















Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  			  		 					
Volume (vph)	327	2145	361	64	2134	96	279	142	112	104	121	147
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Lane Util. Factor	1.00	0.91	1.00	1.00	0.91		0.97	1.00		1.00	1.00	
Frt	1.00	1.00	0.85	1.00	0.99		1.00	0.93		1.00	0.92	
Flt Protected	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (prot)	1770	5085	1583	1770	5053		3433	1739		1770	1710	
Flt Permitted	0.95	1.00	1.00	0.95	1.00		0.95	1.00		0.95	1.00	
Satd. Flow (perm)	1770	5085	1583	1770	5053		3433	1739		1770	1710	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	355	2332	392	70	2320	104	303	154	122	113	132	160
RTOR Reduction (vph)	0	0	128	0	3	0	0	18	0	0	27	0
Lane Group Flow (vph)	355	2332	264	70	2421	0	303	258	0	113	265	0
Turn Type	Prot		Perm	Prot			Prot			Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases			4									
Actuated Green, G (s)	31.0	89.0	89.0	10.0	68.0		13.0	26.0		11.0	24.0	
Effective Green, g (s)	31.0	89.0	89.0	10.0	68.0		13.0	26.0		11.0	24.0	
Actuated g/C Ratio	0.19	0.56	0.56	0.06	0.42		0.08	0.16		0.07	0.15	
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0		6.0	6.0		6.0	6.0	
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0		3.0	3.0		3.0	3.0	
Lane Grp Cap (vph)	343	2829	881	111	2148		279	283		122	257	
v/s Ratio Prot	c0.20	0.46		0.04	c0.48		c0.09	0.15		0.06	c0.15	
v/s Ratio Perm			0.17									
v/c Ratio	1.03	0.82	0.30	0.63	1.13		1.09	0.91		0.93	1.03	
Uniform Delay, d1	64.5	29.1	18.9	73.2	46.0		73.5	65.9		74.1	68.0	
Progression Factor	1.00	1.00	1.00	1.00	1.00		1.00	1.00		1.00	1.00	
Incremental Delay, d2	57.9	2.1	0.2	11.1	63.9		78.7	35.2		58.5	64.2	
Delay (s)	122.4	31.2	19.1	84.3	109.9		152.2	101.1		132.6	132.2	
Level of Service	F	C	B	F	F		F	F		F	F	
Approach Delay (s)		40.2			109.2			127.9			132.3	
Approach LOS		D			F			F			F	
Intersection Summary												
HCM Average Control Delay			79.8			HCM Level of Service				E		
HCM Volume to Capacity ratio			1.09									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			104.8%			ICU Level of Service			G			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

26: E. HALLANDALE BEACH BLVD & NE 10 AVE













Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Volume (vph)	109	2208	143	106	2348	34	86	7	149	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Lane Util. Factor	1.00	0.91	1.00	0.97	0.91	1.00		0.95	1.00			
Frt	1.00	1.00	0.85	1.00	1.00	0.85		1.00	0.85			
Flt Protected	0.95	1.00	1.00	0.95	1.00	1.00		0.96	1.00			
Satd. Flow (prot)	1770	5085	1583	3433	5085	1583		3383	1583			
Flt Permitted	0.95	1.00	1.00	0.95	1.00	1.00		0.96	1.00			
Satd. Flow (perm)	1770	5085	1583	3433	5085	1583		3383	1583			
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	118	2400	155	115	2552	37	93	8	162	0	0	0
RTOR Reduction (vph)	0	0	15	0	0	7	0	0	88	0	0	0
Lane Group Flow (vph)	118	2400	140	115	2552	30	0	101	74	0	0	0
Turn Type	Prot		Perm	Prot		Perm	Prot		Perm			
Protected Phases	7	4		3	8		5	2				
Permitted Phases			4			8			2			
Actuated Green, G (s)	15.1	104.1	104.1	9.3	98.3	98.3		23.1	23.1			
Effective Green, g (s)	15.1	104.1	104.1	9.3	98.3	98.3		23.1	23.1			
Actuated g/C Ratio	0.10	0.67	0.67	0.06	0.64	0.64		0.15	0.15			
Clearance Time (s)	6.0	6.0	6.0	6.0	6.0	6.0		6.0	6.0			
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0		3.0	3.0			
Lane Grp Cap (vph)	173	3426	1067	207	3235	1007		506	237			
v/s Ratio Prot	c0.07	c0.47		0.03	c0.50							
v/s Ratio Perm			0.09			0.02		0.03	c0.05			
v/c Ratio	0.68	0.70	0.13	0.56	0.79	0.03		0.20	0.31			
Uniform Delay, d1	67.4	15.6	9.0	70.6	20.5	10.4		57.6	58.6			
Progression Factor	1.00	1.00	1.00	1.00	1.00	1.00		1.00	1.00			
Incremental Delay, d2	10.6	0.7	0.1	3.2	1.3	0.0		0.2	3.4			
Delay (s)	77.9	16.2	9.1	73.8	21.9	10.4		57.8	62.0			
Level of Service	E	B	A	E	C	B		E	E			
Approach Delay (s)		18.5			23.9			60.4			0.0	
Approach LOS		B			C			E			A	
Intersection Summary												
HCM Average Control Delay			23.1			HCM Level of Service			C			
HCM Volume to Capacity ratio			0.73									
Actuated Cycle Length (s)			154.5			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			71.2%			ICU Level of Service			C			
Analysis Period (min)			15									
c Critical Lane Group												

HCM Signalized Intersection Capacity Analysis

29: E. HALLANDALE BEACH BLVD & NE 8 AVE

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑↑↑	↑	↑	↑↑↑			↑↓		↑	↑	↑
Volume (vph)	0	2367	196	87	2263	0	246	0	40	108	12	170
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Lane Util. Factor		0.91	1.00	1.00	0.91			1.00		0.95	0.95	1.00
Frt		1.00	0.85	1.00	1.00			0.98		1.00	1.00	0.85
Flt Protected		1.00	1.00	0.95	1.00			0.96		0.95	0.96	1.00
Satd. Flow (prot)		5085	1583	1770	5085			1752		1681	1701	1583
Flt Permitted		1.00	1.00	0.04	1.00			0.71		0.74	0.77	1.00
Satd. Flow (perm)		5085	1583	82	5085			1292		1310	1364	1583
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	2573	213	95	2460	0	267	0	43	117	13	185
RTOR Reduction (vph)	0	0	68	0	0	0	0	4	0	0	0	8
Lane Group Flow (vph)	0	2573	145	95	2460	0	0	306	0	64	66	177
Turn Type			Perm	pm+pt			pm+pt			pm+pt		Perm
Protected Phases		4		3	8		5	2		1	6	
Permitted Phases			4	8			2			6		6
Actuated Green, G (s)		85.1	85.1	98.1	98.1			40.0		49.2	49.2	49.2
Effective Green, g (s)		85.1	85.1	98.1	98.1			40.0		49.2	49.2	49.2
Actuated g/C Ratio		0.53	0.53	0.62	0.62			0.25		0.31	0.31	0.31
Clearance Time (s)		6.0	6.0	6.0	6.0			6.0		6.0	6.0	6.0
Vehicle Extension (s)		3.0	3.0	3.0	3.0			3.0		3.0	3.0	3.0
Lane Grp Cap (vph)		2716	846	125	3131			324		412	428	489
v/s Ratio Prot		c0.51		0.03	c0.48					0.00	0.00	
v/s Ratio Perm			0.09	0.44				c0.24		0.04	0.04	c0.11
v/c Ratio		0.95	0.17	0.76	0.79			0.95		0.16	0.15	0.36
Uniform Delay, d1		35.0	19.0	41.3	22.8			58.6		46.8	40.0	42.8
Progression Factor		1.00	1.00	1.00	1.00			1.00		1.00	1.00	1.00
Incremental Delay, d2		8.0	0.1	23.4	1.4			35.5		0.2	0.2	2.1
Delay (s)		43.0	19.1	64.7	24.1			94.1		47.0	40.1	44.9
Level of Service		D	B	E	C			F		D	D	D
Approach Delay (s)		41.2			25.6			94.1			44.3	
Approach LOS		D			C			F			D	










Intersection Summary

HCM Average Control Delay	37.5	HCM Level of Service	D
HCM Volume to Capacity ratio	0.95		
Actuated Cycle Length (s)	159.3	Sum of lost time (s)	24.0
Intersection Capacity Utilization	88.3%	ICU Level of Service	E
Analysis Period (min)	15		
c Critical Lane Group			

HCM Unsignalized Intersection Capacity Analysis

33: DIANA DR & GOLDEN ISLES DR


































Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Volume (veh/h)	69	205	118	56	44	220
Sign Control	Stop		Free			Free
Grade	0%		0%			0%
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	75	223	128	61	48	239
Pedestrians						
Lane Width (ft)						
Walking Speed (ft/s)						
Percent Blockage						
Right turn flare (veh)						
Median type			None			None
Median storage veh						
Upstream signal (ft)						345
pX, platoon unblocked						
vC, conflicting volume	493	159			189	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	493	159			189	
tC, single (s)	6.4	6.2			4.1	
tC, 2 stage (s)						
tF (s)	3.5	3.3			2.2	
p0 queue free %	85	75			97	
cM capacity (veh/h)	516	887			1385	
Direction, Lane #	WB 1	NB 1	SB 1			
Volume Total	298	189	287			
Volume Left	75	0	48			
Volume Right	223	61	0			
cSH	751	1700	1385			
Volume to Capacity	0.40	0.11	0.03			
Queue Length 95th (ft)	48	0	3			
Control Delay (s)	12.9	0.0	1.5			
Lane LOS	B		A			
Approach Delay (s)	12.9	0.0	1.5			
Approach LOS	B					
Intersection Summary						
Average Delay			5.5			
Intersection Capacity Utilization			50.1%	ICU Level of Service	A	
Analysis Period (min)			15			

HCM Signalized Intersection Capacity Analysis

34: E. HALLANDALE BEACH BLVD & U.S. 1

Beachwalk Traffic Study
Optimized Future (2015) Total Traffic - PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		  		 	  		 	  		 	  	
Volume (vph)	209	1219	570	762	1624	368	847	1473	771	562	1082	121
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Lane Util. Factor	1.00	0.91		0.97	0.91		0.97	0.91	1.00	0.97	0.91	
Frt	1.00	0.95		1.00	0.97		1.00	1.00	0.85	1.00	0.98	
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (prot)	1770	4842		3433	4944		3433	5085	1583	3433	5008	
Flt Permitted	0.95	1.00		0.95	1.00		0.95	1.00	1.00	0.95	1.00	
Satd. Flow (perm)	1770	4842		3433	4944		3433	5085	1583	3433	5008	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	227	1325	620	828	1765	400	921	1601	838	611	1176	132
RTOR Reduction (vph)	0	53	0	0	23	0	0	0	186	0	9	0
Lane Group Flow (vph)	227	1892	0	828	2142	0	921	1601	652	611	1299	0
Turn Type	Prot			Prot			Prot		Perm	Prot		
Protected Phases	7	4		3	8		5	2		1	6	
Permitted Phases									2			
Actuated Green, G (s)	15.0	44.0		26.0	55.0		29.0	46.0	46.0	20.0	35.0	
Effective Green, g (s)	15.0	44.0		26.0	55.0		29.0	46.0	46.0	20.0	35.0	
Actuated g/C Ratio	0.09	0.28		0.16	0.34		0.18	0.29	0.29	0.12	0.22	
Clearance Time (s)	6.0	6.0		6.0	6.0		6.0	6.0	6.0	6.0	8.0	
Vehicle Extension (s)	3.0	3.0		3.0	3.0		3.0	3.0	3.0	3.0	3.0	
Lane Grp Cap (vph)	166	1332		558	1700		622	1462	455	429	1096	
v/s Ratio Prot	0.13	c0.39		c0.24	0.43		c0.27	0.31		0.18	0.26	
v/s Ratio Perm									c0.41			
v/c Ratio	1.37	1.42		1.48	1.26		1.48	1.10	1.43	1.42	1.19	
Uniform Delay, d1	72.5	58.0		67.0	52.5		65.5	57.0	57.0	70.0	62.5	
Progression Factor	1.00	1.00		1.00	1.00		1.00	1.00	1.00	1.00	1.00	
Incremental Delay, d2	198.9	193.7		227.2	121.9		224.9	54.0	207.2	204.1	92.9	
Delay (s)	271.4	251.7		294.2	174.4		290.4	111.0	264.2	274.1	155.4	
Level of Service	F	F		F	F		F	F	F	F	F	
Approach Delay (s)		253.7			207.6			198.4			193.2	
Approach LOS		F			F			F			F	
Intersection Summary												
HCM Average Control Delay			211.6			HCM Level of Service			F			
HCM Volume to Capacity ratio			1.48									
Actuated Cycle Length (s)			160.0			Sum of lost time (s)			24.0			
Intersection Capacity Utilization			127.5%			ICU Level of Service			H			
Analysis Period (min)			15									
c Critical Lane Group												

Intersection Capacity Utilization

Beachwalk Traffic Study

8: E. HALLANDALE BEACH BLVD & EB E. Hallandale Beach Blvd - Divided Future (2015) Total Traffic - PM Peak



Movement	EBT	EBR	WBL	WBT	NBL	NBR	NBR2	NWL	NWR
Lane Configurations	↑↑↑↵		↵	↑↑↑			↵		
Volume (vph)	1942	93	107	1744	0	0	83	0	0
Pedestrians									
Ped Button									
Pedestrian Timing (s)									
Free Right	No				No		No	No	
Ideal Flow	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lost Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Green (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Refr Cycle Length (s)	120								
Volume Combined (vph)	2035	0	107	1744	0	0	83	0	0
Lane Utilization Factor	0.91	1.00	1.00	0.91	1.00	1.00	1.00	1.00	1.00
Turning Factor (vph)	0.99	0.85	0.95	1.00	0.95	0.85	0.85	0.95	0.85
Saturated Flow (vph)	5140	0	1805	5176	0	0	1615	0	0
Ped Intf Time (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Frequency (%)	0.00			0.00	0.00			0.00	
Protected Option Allowed	Yes			Yes	No			No	
Reference Time (s)	47.5	0.0	7.1	40.4	0.0		6.2	0.0	
Adj Reference Time (s)	51.5	0.0	11.1	44.4	0.0		10.2	0.0	
Permitted Option									
Adj Saturation A (vph)	1713	120		1725	0			0	
Reference Time A (s)	47.5	106.7		40.4	0.0			0.0	
Adj Saturation B (vph)	NA	NA		NA	NA			NA	
Reference Time B (s)	NA	NA		NA	NA			NA	
Reference Time (s)	47.5			106.7					
Adj Reference Time (s)	51.5			110.7					
Split Option									
Ref Time Combined (s)	47.5	7.1		40.4	0.0			0.0	
Ref Time Seperate (s)	45.3	7.1		40.4	0.0			0.0	
Reference Time (s)	47.5	40.4		40.4	0.0			0.0	
Adj Reference Time (s)	51.5	44.4		44.4	0.0			0.0	
Summary		EB WB		NB		NW		Combined	
Protected Option (s)	62.6		NA		NA				
Permitted Option (s)	110.7		Err		Err				
Split Option (s)	95.9		0.0		0.0				
Minimum (s)	62.6		0.0		0.0		62.6		
Right Turns		NBR2							
Adj Reference Time (s)	10.2								
Cross Thru Ref Time (s)	0.0								
Oncoming Left Ref Time (s)	51.5								
Combined (s)	61.7								

Intersection Summary

Intersection Capacity Utilization 52.2% ICU Level of Service A
Reference Times and Phasing Options do not represent an optimized timing plan.